

SITE CLEANUP AND INVESTIGATION REPORT  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA

VOLUME 1  
EXPANDED SITE INVESTIGATION/  
INTERIM CLEANUP

Contract No. DTFA04-90-C-20014  
Task Order No. 31

May 1995

Prepared for:

DEPARTMENT OF TRANSPORTATION  
Federal Aviation Administration  
Alaskan Region  
222 West 7th Avenue, No. 14  
Anchorage, Alaska 99513-7587



ecology and environment, inc.

International Specialists in the Environment

---

840 K Street, Anchorage, Alaska 99501,  
Tel: (907) 257-5000, Fax: (907) 257-5007

recycled paper

## **EXECUTIVE SUMMARY**

Pursuant to Task Order No. 31 of Contract No. DTFA 04-90-C-20014, issued by the United States Department of Transportation (DOT); Federal Aviation Administration, Alaskan Region (FAA); Ecology and Environment, Inc. (E & E) implemented an expanded site investigation and interim cleanup (ESI/IC) plan at the Annette Island FAA Station, Annette Island, Alaska. This Site Cleanup and Investigation Report (SCIR) details E & E's implementation of the ESI/IC and the results of these activities.

The objective of this ESI/IC is to further identify and control immediate releases, as regulated by the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) and the Clean Water Act (CWA), and petroleum and hazardous substances, as regulated by the Alaska Department of Environmental Conservation's (ADEC) Hazardous Substance Act.

ESI/IC activities were performed at the Very High Frequency Omnidirectional Range Tactical Air Navigation/Directional Finder (VORTAC/DF), Nondirectional Beacon (NDB)/H-marker, Remote Center Air/Ground Communications (RCAG), Hangar, Approach Lighting System (ALS), Glide Slope (GS), and Localizer (LOC) facilities. The VORTAC/DF, NDB/H-marker, and RCAG facilities are on land leased by the FAA from the Metlakatla Indian Council. The other facilities are on land formerly leased by FAA.

Annette Island is located entirely within the Annette Island Indian Reservation. The Indian village community of Metlakatla is located approximately 5 miles north of the FAA station. Approximately 1,000 people reside on Annette Island.

## **EXPANDED SITE INVESTIGATION CONCLUSIONS AND RECOMMENDATIONS VORTAC/DF**

Lead, a CERCLA-regulated contaminant, was detected at concentrations exceeding media-specific evaluation criteria (MSEC) and toxicity and characteristic leaching procedure (TCLP) regulatory criteria at the VORTAC/DF facility. Approximately 300 cubic yards of soil at this facility are potentially contaminated. Further action is recommended to address this issue.

### **NDB/H-MARKER**

Lead, a CERCLA-regulated contaminant, was detected at concentrations exceeding MSEC and TCLP regulatory criteria at the NDB/H-marker facility. Approximately 150 cubic yards of soil at this facility are potentially affected. Further action is recommended to address this issue. Additionally, since access to this facility is unrestricted, steps should be taken to contain the contaminated soil and control access to it.

### **RCAG**

No CERCLA-regulated contaminants were detected at concentrations that exceeded MSEC or TCLP regulatory criteria at the RCAG facility. No further investigation at this facility is recommended.

## **INTERIM CLEANUP ACTIVITIES AND RECOMMENDATIONS**

The following IC activities were completed at the Annette Island FAA Station for the RCAG, Hangar, ALS, GS, and LOC facilities.

### **RCAG**

The inactive, gasoline underground storage tank (UST) at the RCAG was inspected, found to be empty, and locked. Further action is required to decommission this UST according to ADEC regulations.

### **Hangar**

A small area of the Hangar floor, which was the former location of polychlorinated biphenyl (PCB)-containing transformers was swept clean of lead-containing debris and paint chips and cleaned several times with solvent. The floor sweepings and cleaning solvents and

materials were containerized and disposed according to appropriate regulations. According to PCB wipe sampling, the floor cleaning was unsuccessful in removing PCB contamination; therefore, further cleaning or the removal of the floor is recommended to remediate the area to Toxic Substance Control Act (TSCA) regulatory standards.

#### ALS

Eight oil-filled transformers were sampled for PCBs in the short approach lighting system/runway end identification lights (SALSR) building, which was discovered during on-site activities. Based on this sampling, further action is recommended to dispose of one PCB-containing transformer and various non-PCB oil-filled and dry electrical equipment according to TSCA and FAA good housekeeping practices. The ALS is inactive.

#### GS

Approximately 15 gallons of non-PCB oil was pumped from a transformer into a drum and disposed according to appropriate regulations. Further action is recommended to dispose of the empty transformer according to FAA good housekeeping practices. The GS is inactive.

#### LOC

Five small, sealed transformers, which were discovered at the LOC during field activities, were drummed and stored in the hazardous materials building located at the VORTAC/DF. No further action is required for this facility. The LOC is inactive.



<p><b>Table ES-1</b></p> <p><b>SITE CLEANUP AND INVESTIGATION ACTIVITIES MATRIX</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p>						
Facility/Site	ESI CERCLA		ESI POL		IC	
	Further Action	No Further Action	Further Action	Tank Decommissioning	Removal	No Further Action
VORTAC/DF	X					
NDB/H-Marker	X					
RCAG		X		X		
Hangar					X	
ALS					X	
GS					X	
LOC						X

**Key:**

ALS = Airport lighting system.  
 CERCLA = Comprehensive Environmental Response, Compensation, and Liability Act.  
 ESI = Expanded Site Investigation.  
 FAA = Federal Aviation Administration, Alaskan Region,  
 GS = Glide slope.  
 IC = Interim Cleanup.  
 LOC = Localizer.  
 NDB = Nondirectional beacon.  
 POL = Petroleum, oils, and lubricants.  
 VORTAC/DF = Very high frequency omnidirectional range tactical air/ground communications/directional finder.

## TABLE OF CONTENTS

<u>Section</u>		<u>Page</u>
	Volume 1	
	EXECUTIVE SUMMARY .....	ES-1
1	INTRODUCTION .....	1-1
	1.1 PURPOSE .....	1-1
	1.2 STATION OVERVIEW .....	1-3
	1.3 ENVIRONMENTAL SETTING .....	1-4
	1.3.1 Climate .....	1-4
	1.3.2 Vegetation and Wildlife .....	1-4
	1.3.3 Regional Geology .....	1-5
	1.3.4 Regional Hydrology .....	1-6
	1.3.5 Cultural Resources .....	1-7
	1.4 PROJECT HISTORY .....	1-7
	1.4.1 FAA 1988 Site Investigation .....	1-7
	1.4.2 USACE Site Investigation .....	1-7
	1.4.3 FAA 1990 Underground Storage Tank Study .....	1-8
	1.4.4 FAA 1991 Environmental Compliance Investigation .....	1-8
	1.4.5 FAA 1992 Removal Project .....	1-8
	1.5 SITE CLEANUP AND INVESTIGATION REPORT ORGANIZATION .....	1-9

## Table of Contents (Cont.)

<u>Section</u>		<u>Page</u>
2	EXPANDED SITE INVESTIGATION AND INTERIM CLEANUP ACTIVITIES . . . . .	2-1
2.1	EXPANDED SITE INVESTIGATION . . . . .	2-1
2.1.1	General . . . . .	2-1
2.1.2	Expanded Site Investigation Activities . . . . .	2-2
2.1.3	Deviations from the Work Plan . . . . .	2-3
2.2	INTERIM CLEANUP . . . . .	2-3
2.2.1	General . . . . .	2-3
2.2.2	Interim Cleanup Activities . . . . .	2-3
2.2.3	Deviations from the Work Plan . . . . .	2-4
2.3	SAMPLE QUALITY ASSURANCE . . . . .	2-4
2.4	DATA VALIDATION . . . . .	2-5
2.4.1	Data Qualifiers . . . . .	2-5
2.4.2	Metals Data . . . . .	2-6
2.4.3	Organic Data . . . . .	2-6
2.5	DATA USABILITY . . . . .	2-6
2.6	PRESENTATION OF ANALYTICAL RESULTS . . . . .	2-7
2.7	FIELD QUALITY ASSURANCE SAMPLES . . . . .	2-8
2.7.1	Background Samples . . . . .	2-8
2.7.2	Rinsate Samples . . . . .	2-10
2.7.3	Level II Field Screening . . . . .	2-10
2.7.4	Level II Confirmation Samples . . . . .	2-10
2.8	UPDATED MEDIA-SPECIFIC EVALUATION CRITERIA (MSECs) FOR FAA SITES . . . . .	2-12
3	VORTAC/DF FACILITY . . . . .	3-1
3.1	LOCATION AND DESCRIPTION . . . . .	3-1
3.2	EXPANDED SITE INVESTIGATION . . . . .	3-2
3.2.1	Level II Soil Grid Sampling . . . . .	3-2
3.2.2	Level III POL and Lead Sampling . . . . .	3-4
3.2.3	Level IV Source and Target Sampling . . . . .	3-5

## Table of Contents (Cont.)

<u>Section</u>		<u>Page</u>
	3.2.4 Background Samples . . . . .	3-7
	3.2.5 Level IV TCLP Sampling . . . . .	3-7
	3.2.6 Wetlands Survey . . . . .	3-8
	3.2.7 Site-Specific Remedial Goals . . . . .	3-10
	3.2.8 Deviations from the Work Plan . . . . .	3-13
	3.2.9 Expanded Site Investigation Conclusions and Recommendations . . . . .	3-13
4	NDB/H-MARKER FACILITY . . . . .	4-1
4.1	LOCATION AND DESCRIPTION . . . . .	4-1
4.2	EXPANDED SITE INVESTIGATION . . . . .	4-2
	4.2.1 Level II Soil Grid Sampling . . . . .	4-2
	4.2.2 Lead III Lead Sampling . . . . .	4-2
	4.2.3 Level IV Source and Target Sampling . . . . .	4-3
	4.2.4 Background Samples . . . . .	4-5
	4.2.5 Level IV TCLP Sampling . . . . .	4-5
	4.2.6 Wetlands Survey . . . . .	4-5
	4.2.7 Site-Specific Remedial Goals . . . . .	4-6
	4.2.8 Deviations from the Work Plan . . . . .	4-8
	4.2.9 Conclusions and Recommendations . . . . .	4-9
5	RCAG FACILITY . . . . .	5-1
5.1	LOCATION AND DESCRIPTION . . . . .	5-1
5.2	EXPANDED SITE INVESTIGATION . . . . .	5-1
	5.2.1 Level IV Source and Target Sampling . . . . .	5-1
	5.2.2 Background Samples . . . . .	5-3
	5.2.3 Level IV TCLP Sampling . . . . .	5-3
	5.2.4 Wetlands Survey . . . . .	5-3
	5.2.5 Deviations from the Work Plan . . . . .	5-4

## Table of Contents (Cont.)

<u>Section</u>		<u>Page</u>
	5.2.6 Expanded Site Investigation Conclusions and Recommendations . . . . .	5-5
5.3	INTERIM CLEANUP ACTIVITY . . . . .	5-5
	5.3.1 Field Activities . . . . .	5-5
	5.3.2 Conclusions and Recommendations . . . . .	5-5
6	HANGAR FACILITY . . . . .	6-1
	6.1 LOCATION AND DESCRIPTION . . . . .	6-1
	6.2 INTERIM CLEANUP . . . . .	6-1
	6.2.1 Field Activities . . . . .	6-1
	6.2.2 Deviations From the Work Plan . . . . .	6-3
	6.2.3 Conclusions and Recommendations . . . . .	6-3
7	ALS FACILITY . . . . .	7-1
	7.1 LOCATION AND DESCRIPTION . . . . .	7-1
	7.2 INTERIM CLEANUP . . . . .	7-1
	7.2.1 Field Activities . . . . .	7-1
	7.2.2 Deviations From the Work Plan . . . . .	7-2
	7.2.3 Conclusions and Recommendations . . . . .	7-2
8	GS TRANSMITTER FACILITY . . . . .	8-1
	8.1 LOCATION AND DESCRIPTION . . . . .	8-1
	8.2 INTERIM CLEANUP ACTIVITIES . . . . .	8-1
	8.2.1 Field Activities . . . . .	8-1
	8.2.2 Deviations From the Work Plan . . . . .	8-2
	8.2.3 Conclusions and Recommendations . . . . .	8-2
9	LOC FACILITY . . . . .	9-1
	9.1 LOCATION AND DESCRIPTION . . . . .	9-1
	9.2 INTERIM CLEANUP ACTIVITIES . . . . .	9-1

## Table of Contents (Cont.)

<u>Section</u>		<u>Page</u>
	9.2.1 Field Activities . . . . .	9-1
	9.2.2 Deviations From the Work Plan . . . . .	9-1
	9.2.3 Conclusions and Recommendations . . . . .	9-1
10	STATION RECOMMENDATION SUMMARY . . . . .	10-1
	10.1 VORTAC/DF FACILITY . . . . .	10-1
	10.1.1 Expanded Site Investigation . . . . .	10-1
	10.2 NDB/H-MARKER FACILITY . . . . .	10-1
	10.2.1 Expanded Site Investigation . . . . .	10-1
	10.3 RCAG FACILITY . . . . .	10-1
	10.3.1 Expanded Site Investigation . . . . .	10-1
	10.3.2 Interim Cleanup . . . . .	10-2
	10.4 HANGAR FACILITY . . . . .	10-2
	10.4.1 Interim Cleanup . . . . .	10-2
	10.5 ALS FACILITY . . . . .	10-2
	10.5.1 Interim Cleanup . . . . .	10-2
	10.6 GS FACILITY . . . . .	10-2
	10.6.1 Interim Cleanup . . . . .	10-2
	10.7 LOC FACILITY . . . . .	10-2
	10.7.1 Interim Cleanup . . . . .	10-2
	10.8 ADDITIONAL RECOMMENDATIONS . . . . .	10-2
11	REFERENCES . . . . .	11-1

<u>Appendix</u>		<u>Page</u>
	Volume 2	
A	PHOTOLOGS . . . . .	A-1
B	OFF-SITE LABORATORY DATA VALIDATION MEMORANDUM AND LABORATORY DATA SHEETS . . . . .	B-1

## Table of Contents (Cont.)

<u>Appendix</u>		<u>Page</u>
C	CHAIN-OF-CUSTODY RECORDS .....	C-1
D	ALASKA STATE CLEANUP MATRIX SCORESHEET .....	D-1
E	WASTE INVENTORY AND DISPOSAL DOCUMENTATION .....	E-1
E.1	INVENTORY OF WASTE REMOVED .....	E-3
E.2	WASTE TRANSPORTERS AND TREATMENT, STORAGE, AND DISPOSAL FACILITIES .....	E-7
E.3	WASTE SHIPPING MANIFEST .....	E-11
Volume 3		
F	FIELD SCREENING ANALYSES PROTOCOL .....	F-1
F.1	XRF SOIL ANALYSIS PROTOCOL .....	F-3
F.2	XRF PAINT ANALYSIS PROTOCOL .....	F-7
F.3	EPA ERT SPECTRACE 9000 XRF SOP .....	F-11
F.4	ENSYS PETRO RISC ANALYSIS PROTOCOL .....	F-43
F.5	ENSYS PCB RISC ANALYSIS PROTOCOL .....	F-57
G	XRF RAW DATA .....	G-1

## LIST OF TABLES

<u>Table</u>	<u>Page</u>
ES-1      Site Cleanup and Investigation Activities Matrix .....	ES-4
1-1      Normal Ranges of Elemental Concentrations in Soils .....	1-10
2-1      Expanded Site Investigation/Interim Cleanup Field Team Personnel ..	2-14
2-2      Field Quality Assurance Sample Summary .....	2-15
2-3      Field Quality Assurance Samples (Background, Rinsate, and Trip Blanks)—Positively Identified Organic Compounds .....	2-16
2-4      Field Quality Assurance Samples (Background and Rinsate)— Positively Identified Inorganic Compounds .....	2-17
2-5      Field Quality Assurance Samples (Background and Rinsate)— Positively Identified Dioxin Isomers .....	2-19
2-6      Media-Specific Evaluation Criteria—Soil .....	2-20
3-1      Expanded Site Investigation Sample Summary—VORTAC Facility .....	3-14
3-2      Expanded Site Investigation Level II Soil Samples— XRF Metals Results, VORTAC Facility .....	3-22
3-3      Expanded Site Investigation Soil Samples—Positively Identified Petroleum Compounds and Total Lead, Level III Analysis, VORTAC Facility .....	3-31
3-4      Expanded Site Investigation Soil and Sediment Samples— Positively Identified Inorganic Compounds, Level IV Analysis, VORTAC Facility .....	3-33



## List of Tables (Cont.)

<u>Table</u>		<u>Page</u>
3-5	Expanded Site Investigation Soil and Sediment Samples— Positively Identified Organic Compounds, Level IV Analysis, VORTAC Facility . . . . .	3-36
3-6	Expanded Site Investigation Soil Samples—Positively Identified TCLP Metals, Level IV Analysis, VORTAC Facility . . . . .	3-37
4-1	Expanded Site Investigation Sample Summary— NDB/H-Marker Facility . . . . .	4-10
4-2	Expanded Site Investigation Soil Samples—XRF Metals Results, Level II Analysis, NDB/H-Marker Facility . . . . .	4-14
4-3	Expanded Site Investigation Soil Samples—Total Lead Analysis, Level III Analysis, NDB Facility . . . . .	4-23
4-4	Expanded Site Investigation Soil and Sediment Samples— Positively Identified Inorganic Compounds, Level IV Analysis, NDB Facility . . . . .	4-24
4-5	Expanded Site Investigation Soil and Sediment Samples— Positively Identified Dioxin Isomers, Level IV Analysis, NDB Facility . . . . .	4-26
4-6	Expanded Site Investigation Soil and Sediment Samples— Positively Identified Organic Compounds, Level IV Analysis, NDB Facility . . . . .	4-28
4-7	Expanded Site Investigation Soil and Sediment Samples— Positively Identified TCLP Metals, Level IV Analysis, NDB Facility . . . . .	4-29
5-1	Expanded Site Investigation Sample Summary—RCAG Facility . . . . .	5-6
5-2	Expanded Site Investigation Soil and Sediment Samples— Positively Identified Inorganic Compounds, Level IV Analysis, RCAG Facility . . . . .	5-7
5-3	Expanded Site Investigation Soil and Sediment Samples— Positively Identified Organic Compounds, Level IV Analysis, RCAG Facility . . . . .	5-9
5-4	Expanded Site Investigation Soil and Sediment Samples—Positively Identified TCLP Metals, Level IV Analysis, RCAG Facility . . . . .	5-10

## List of Tables (Cont.)

<u>Table</u>		<u>Page</u>
6-1	Interim Cleanup Sample Summary, Hangar Facility . . . . .	6-4
6-2	Interim Cleanup PCB Wipe Samples—Positively Identified PCBs, Level III Analysis, Hangar Facility . . . . .	6-5
7-1	Interim Cleanup Electrical Equipment Inventory, ALS Facility . . . . .	7-3
7-2	Interim Cleanup Sample Summary, ALS Facility . . . . .	7-4
7-3	IC Oil Samples, Positively Identified PCB Compounds—Level III, ALS Facility . . . . .	7-5
10-1	Station Recommendations . . . . .	10-3

## LIST OF ILLUSTRATIONS

<u>Figure</u>	<u>Page</u>
1-1      Location Map .....	1-12
1-2      Site Map .....	1-13
1-3      Remote Sample Location Map .....	1-15
2-1      NDB/H-Marker Background Sample Location Map .....	2-23
2-2      Sediment Background Sample Location Map .....	2-25
3-1      VORTAC/DF Facility Site Map .....	3-38
3-2      VORTAC Facility Level II XRF Screening Sample Location Map .....	3-39
3-3      VORTAC Facility Level II XRF Screening Lead Results Map .....	3-40
3-4      VORTAC Facility Level III and IV Source Sample Location Map .....	3-41
3-5      VORTAC Facility Level III and IV TAL/TCLP Lead Results Map .....	3-42
3-6      VORTAC Facility Overland Surface Water Pathway Sample Location Map .....	3-43
4-1      NDB/H-Marker Background Site Map .....	4-31
4-2      NDB Facility Level II XRF Screening Sample Locations .....	4-33
4-3      NDB Facility Level II XRF Screening Lead Results Map .....	4-34
4-4      NDB Facility Level III and IV Sample Location Map .....	4-35

## List of Illustrations (Cont.)

<u>Figure</u>		<u>Page</u>
4-5	NDB Facility Level III and IV TAL/TCLP Lead Results Map . . . . .	4-36
4-6	NDB Facility Overland Surface Water Pathway and Target Sample Location Map . . . . .	4-37
5-1	RCAG Facility Sample Location Map . . . . .	5-11
5-2	RCAG Facility Overland Surface Water Pathway and Target Sample Location Map . . . . .	5-13
6-1	Hangar Facility Site Map . . . . .	6-6
6-2	Hangar Facility Wipe Sample Location and Results Map . . . . .	6-7
7-1	ALS Facility Transformer Oil Sample Location Map . . . . .	7-6

## ACRONYM LIST

AAC	Alaska Administrative Code
ADEC	Alaska Department of Environmental Conservation
ADNR	Alaska Department of Natural Resources
ANLCSA	Alaska Native Land Claims Settlement Act
BGS	Below Ground Surface
BNA	Base, Neutral/Acid Extractable
BTEX	Benzene, Toluene, Ethylbenzene, and Xylenes
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CERCLIS	Comprehensive Environmental Response, Compensation, and Liability Information System
DOT	Department of Transportation
DRO	Diesel-Range Organics
ECI	Environmental Compliance Investigation
ECIR	Environmental Compliance Investigation Report
ESI/IC	Expanded Site Investigation/Interim Cleanup
FAA	Federal Aviation Administration
FECF	Facilities Environmental Compliance Program
FSS	Flight Service Station
HRS	Hazard Ranking System
MCP	Master Compliance Plan
MSEC	Media-Specific Evaluation Criteria
PCB	Polychlorinated Biphenyl
POL	Petroleum, Oil, and Lubricant
QA	Quality Assurance
QC	Quality Control
RCRA	Resource Conservation and Recovery Act
SCIR	Site Cleanup and Investigation Report
TCLP	Toxicity characteristic leaching procedure
TSCA	Toxic Substances Control Act
TRPH	Total Recoverable Petroleum Hydrocarbons
UHF	Ultra High Frequency
USFWS	United States Fish and Wildlife Service
VHF	Very High Frequency
VOC	Volatile Organic Compounds
VOR	Very High Frequency, Omnidirectional-Range
VORTAC	Very High Frequency, Omnidirectional-Range, Tactical Air Navigation
VPH	Volatile Petroleum Hydrocarbon
VPH-G	Volatile Petroleum Hydrocarbon as Gasoline
VPH-D	Volatile Petroleum Hydrocarbon as Diesel
XRF	X-ray fluorescence

## 1. INTRODUCTION

### 1.1 PURPOSE

Pursuant to Task Order No. 27 of Contract No. DTFA 04-90-C-20014, issued by the United States Department of Transportation (DOT), Federal Aviation Administration, Alaskan Region (FAA), Ecology and Environment, Inc., (E & E) implemented an expanded site investigation and interim cleanup (ESI/IC) plan at the Annette Island FAA Station, Annette Island, Alaska. This Site Cleanup and Investigation Report (SCIR) details E & E's implementation of the ESI/IC and the results of these activities.

The objective of this ESI/IC is to further identify and control immediate releases, as regulated by the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) and the Clean Water Act (CWA), and petroleum and hazardous substances, as regulated by the Alaska Department of Environmental Conservation's (ADEC) Hazardous Substance Act. The systematic ESI/IC activities reported in this SCIR conform with procedures established in FAA's 1992 Facilities Environmental Compliance Program (FECF), Master Compliance Plan (MCP). CERCLA Section 120 requires that preliminary assessments and site investigations be conducted by each federal agency that has facilities and sites on which hazardous substances have been used and potentially removed for disposal.

FAA, under its FECF, conducted an environmental compliance investigation (ECI) of Annette Island FAA Station in 1991 for potential hazardous materials contamination. The results were reported in the *Environmental Compliance Investigation Report (ECIR) for Annette Island FAA Station* (E & E 1992b). The ECIR recommended additional ESIs at two selected Annette Island facilities and sites and IC of identified hazardous wastes. These recommendations and a draft ESI/IC work plan were submitted to the United States Environmental Protection Agency (EPA) and ADEC for review and comment.

EPA and ADEC review comments were incorporated into the final ESI/IC work plan (E & E 1993b). The work plan constituted the primary scope of work for this field investigation, which was conducted from June 10 to June 22, 1994.

ESIs were conducted on three Annette Island facilities/sites: Very High Frequency Omnidirectional Range Tactical Air Navigational/Directional Finder (VORTAC/DF), Nondirectional Beacon (NDB)/H-marker, and Remote Center Air/Ground Communications (RCAG), where the ECIR indicated CERCLA-related hazardous material usage or disposal. The CERCLA results from the ECIR were used to focus on source, target, and pathway sampling as defined by EPA's Hazard Ranking System (HRS). EPA Level IV analysis was used to characterize these areas for HRS scoring purposes. Additional background, pathway, and target data were collected where warranted. The facility sampling activities and data results are discussed individually for each facility or site. These discussions are designed to fulfill FAA's responsibilities to provide detailed site information pursuant to Section 120(d) of CERCLA 42 V.S.C. 9620(d). Because the ECIR addresses spills, petroleum, and hazardous materials, release investigations were also conducted to address the requirements of Article 3 of Title 18, Alaska Administrative Code, Chapter 75 (18 AAC 75), State of Alaska Oil and Hazardous Substances Pollution Control Regulations, as implemented by ADEC.

Wetland surveys were conducted at each facility in conjunction with the ESI. The primary objective of the wetland surveys were to identify wetlands within 0.2 mile down-gradient of any potential CERCLA source of contamination. These wetland surveys conform to the EPA definition of wetlands in 40 Code of Federal Regulations (CFR), Part 230, Subpart E, Section 230.41, which identify three factors (vegetation, soils, and hydrology) that must be considered to determine the presence of a wetland. Consistent with this definition, dominant plant species in each major vegetation stratum (tree, sapling/shrub, herbaceous) within the study area were identified and listed. Each plant's wetland indicator status (e.g., obligate, facultative wet, facultative, facultative upland, obligate upland) was then assigned using the United States Fish and Wildlife Service's (USFWS's) *National List of Plant Species that Occur in Wetlands: Alaska (Region A)* to determine the presence of hydrophytic vegetation (Reed 1988). Soils are evaluated by determining the soil type, examining soil horizonation and color, and determining the height to which and the length of time soils are saturated. The hydrology criteria are met when an area is periodically inundated or has soil saturated at or near the surface at some time during the growing season sufficient to support

hydrophytic vegetation. When water levels drop, visual indications typically remain, thereby allowing assessment of hydrology, as indicated by water marks and drainage patterns.

The IC portion of this task order was a definitive action taken by FAA to remove any immediately identified CERCLA, Resource Conservation and Recovery Act (RCRA), Toxic Substances Control Act (TSCA), or petroleum hazardous substances from the station, pursuant to appropriate regulations. An IC was conducted at the RCAG, Hangar, Approach Lighting System (ALS), Glide Slope (GS), and Localizer (LOC) facilities and included cleaning polychlorinated biphenyl (PCB)-containing oil from a concrete floor, removal of electrical equipment, and sampling transformer oil for PCBs.

## 1.2 STATION OVERVIEW

The Annette Island FAA Station is an air navigation station whose property currently is leased to the FAA by the Metlakatla Indian Council. The Annette Island FAA Station is located near the abandoned Annette Airport on Annette Island, 5 miles south of the town of Metlakatla (population approximately 1,000) (see Figures 1-1 and 1-2). Annette Island is surrounded by saltwater and is situated near Dixon Entrance and the Canadian border, 15 miles south of Ketchikan, Alaska. Facilities at the station lie within 0.5 mile of both Clarence Strait to the west and Tamgass Harbor to the east. The latitude and longitude for the airport are 55°02'34"N and 131°34'14"W. The United States Public Land Survey coordinates are Township 79S, Range 92E, Sections 4, 5, 8, and 9 Copper River Meridian.

FAA has operated the Annette Island FAA Station since the construction of air navigational facilities in 1948. The Annette Island FAA Station is not continuously manned, but the station is visited regularly by FAA personnel based in Ketchikan. The Annette Island FAA Station was deactivated in 1973 prior to FAA's transfer of its property title to the Metlakatla Indian Council. Since then, several facilities and properties have been reactivated and added to or subtracted from the total station area. FAA owns buildings associated with the air navigation and communication facilities, which are on leased property. The currently leased station facilities investigated under this ESI effort consist of the VORTAC/DF, NDB/H-marker, and RCAG.



### 1.3 ENVIRONMENTAL SETTING

This section describes the Annette Island FAA Station environmental setting. It includes detailed discussions of the station geology, groundwater, surface water, climate, and a description of sensitive environments in the station area.

#### 1.3.1 Climate

The Metlakatla Peninsula lies in the maritime climate zone of southeastern Alaska with warm winters, cool summers, and relatively heavy precipitation. Average summer temperatures range from 36° Fahrenheit (F) to 52°F. Frequent storms contribute to the high average annual precipitation of 115 inches. In addition to the rain, cloud cover is present 62% of the time, resulting in poor visibility. Average winter temperatures range from 28°F to 42°F. Annual snowfall averages 51 inches (Alaska Department of Community and Regional Affairs [ADCRA] 1984).

Annette Island wind data, collected over a 29-year period, indicates an average wind speed of 10 miles per hour with winds primarily from the southeast. Metlakatla, however, is generally protected from southeasterly winds due to its location on the lee side of the island (ADCRA 1984).

#### 1.3.2 Vegetation and Wildlife

Wetlands dominate the landscape on the Metlakatla Peninsula. Vegetation on the peninsula primarily is composed of sedges, sphagnum moss (*Sphagnum spp.*), crowberry (*Empetrum nigrum*), Labrador tea (*Ledum dewmbens*), bog rosemary, bog laurel (*Kalmia microphylla*), isolated strands of western hemlock (*Tsuga heterophylla*), Alaska yellow cedar (*Chamaecyparis motilatensis*), and shore pine (*Pinus cintorta*) (ADCRA 1984).

The dominant wetlands present on the Metlakatla Peninsula include: open water, shore pine-yellow cedar muskeg, and forested. The open water and shore pine-yellow cedar wetlands constitute a wetland complex that covers thousands of acres on the level and rolling hills areas of the peninsula. The forested wetlands are found in isolated inland areas and along the coast line. Wetlands at the FAA facilities consist primarily of the open water/shore pine-yellow cedar wetland complex.

Soils and wetlands in the vicinity of the FAA facilities have some common characteristics. The soil on Annette Island is classified as SO18 by the Exploratory Soil Survey of Alaska (United States Department of Agriculture [USDA 1979]). The applicable soils within

this soil classification includes Typic Sphagnofibrists and Fluvaquentic Cryofibrists. These both consist of poorly drained organic soils that occur in nearly level or rolling areas or in marshes in valley bottoms. According to field observations and the USFWS National Wetlands Inventory map of the area, a scrub-shrub wetland complex, containing both isolated upland islands and open water wetlands, covers several thousand acres of Annette Island in the vicinity of the FAA facilities. The American Peregrine falcon is a federally listed endangered species that nests in southeastern Alaska. They breed primarily in the outer islands and along the coast, but none have been identified on Annette Island. Other regional endangered species include the humpback, fin, and gray whales, which may pass through neighboring waters as they migrate from summer feeding areas to winter breeding areas.

The shoreline of the island, particularly in areas protected from wave action, is bordered by strand vegetation that consists of Lyngbye's sedge, sand spurry, tufted hairgrass, beach ryegrass, and Pacific silverweed. Nearshore vegetation includes several species of kelp, large brown algae, red coralline algae, and eelgrass.

The Misty Fjords National Monument Wilderness lies on the mainland approximately 10 miles east of Annette Island, across Revillagigedo Channel. The wilderness area does not border Annette Island.

Fishing and lumbering industries support the Metlakatla town economy. A sizable fishing fleet exists in this area, and the only fish traps allowed in Alaska are used in this area. According to the 1989 preliminary Alaska commercial fisheries harvest values, the commercial harvest for the state of Alaska in the southeastern region was: total salmon, 257,870 pounds (Annette Island trap salmon, 500.26 pounds; gill net salmon, 9,930.60 pounds) total herring harvest (in areas other than Seymour Canal, Sitka Sound, and Kah Shakes), 3,400 pounds; total shellfish harvest, 9,929 pounds; total groundfish landed for all gears, 9,162.5 pounds (ADCRA 1984).

### **1.3.3 Regional Geology**

Annette Island is part of the northern region of an extensive coastal mountain range called the Cordilleran Range. The range and its associated Alaskan offshore islands extend along the western edge of North America from Southern California to the Alaskan Peninsula. Annette Island lies in the Wrangell-Revillagigedo belt of metamorphic rocks.

During the Pleistocene Epoch, the Metlakatla area was presumably covered by ice several times. Glaciers smoothed the present Metlakatla Peninsula and deeply eroded the

valleys on the rest of Annette Island. The last major glaciation ended more than 10,000 years ago.

The Annette Island FAA Station is situated on the southwestern portion of Annette Island in an area referred to as the Metlakatla Peninsula (see Figure 1-1). This area is relatively flat compared to the mountainous northern part of the island. The maximum elevation on the peninsula is Yellow Hill at 540 feet above mean sea level (AMSL), compared to mountains of over 2,000 feet AMSL in the northern part of the island. The airport area elevation is less than 100 feet AMSL. The Metlakatla Peninsula comprises approximately 18 square miles.

Bedrock underlying the Metlakatla Peninsula is chiefly composed of schist, gneiss, and hornfels. These rocks are locally mixed and in part gradational with foliated granitic rocks, which in turn grade into foliated quartz diorite and diorite. Strike and dip of beds are generally variable, and minor offsets are common. Bedrock is of late Paleozoic to early Mesozoic age. Six types of surficial geologic materials of Quaternary age are present: firm diamicton, emerged shore, modern shore and delta, alluvial deposits, very soft muskeg and other organic deposits, and firm to soft artificial fill (United States Geological Survey [USGS 1971]).

Surface lithology found on the island include organic muck, glacial till, and raised beach deposits. The general lithology and stratigraphy of the raised beach deposits change laterally over short distances. The deposits are generally 5 to 10 feet in thickness. At a location on the northern edge of the Annette Island FAA Station, the deposits consist of 4 to 6 feet of sandy gravel overlying silty and clayey bluish-gray sand of unknown thickness. The gravel is poorly sorted (USGS 1971).

Surface soil consists of poorly drained sandy gravel intermixed with marine clay and decomposed organic matter. The depth of the sandy gravel typically ranges from 4 to 6 feet, with a maximum thickness of 30 feet (ADCRA 1984; USGS 1971). Normal ranges of elemental concentrations in Alaskan soils are presented in Table 1-1.

#### **1.3.4 Regional Hydrology**

Although annual precipitation at the Annette Island FAA Station is 115 inches, the igneous and metamorphic rocks underlying most of the region generally yield only small amounts of water. The overlying muck, when present, is relatively impermeable and does not allow for recharge of the underlying bedrock. Interbedded gravel, sand, silt, and clay

interpreted as raised beach deposits may be sources of groundwater. The number, spacing, attitude, size, and interconnection of fractures in bedrock determine the availability and movement of groundwater. Highly fractured ultrabasic rocks located south of Yellow Hill (north of the Annette Island FAA Station) provide openings for seeps and small springs. Other small springs, which typically are dry in the summer, issue from fractured rocks along the west side of the peninsula. The Metlakatla Peninsula is a swampy, heavily vegetated low-land generally less than 200 feet AMSL (USGS 1971). A test hole drilled at the northern end of the Annette Island FAA Station produced water at 0.5 gallons per minute (gpm) for 8 hours from 70 to 90 feet below ground surface (BGS) and 37 gpm for 23 hours from 332 to 336 feet BGS (USGS 1971). Groundwater is not currently used as a drinking water source on the island.

Chester Lake is Metlakatla's community water source. The lake is approximately 3.5 miles northeast of the Annette Island FAA Station (see Figure 1-2). Water is transferred to a treatment plant for addition of chloride and fluoride and then flows via underground pipes to approximately 400 connections in the town. Average per capita consumption is estimated at 250 gallons per day (gpd) with peak use in the community reaching an estimated 0.8 million to 1.5 million gpd. The system capacity is 1.5 million gpd (ADCRA 1984).

### **1.3.5 Cultural Resources**

A request was made of the State of Alaska, Department of Natural Resources (ADNR), to determine whether prehistoric or historic cultural resources exist at any of the FAA stations under investigation. Based on the Alaska Heritage Resources Survey, no cultural resources have been identified at the Annette Island FAA Station (ADNR 1991).

## **1.4 PROJECT HISTORY**

### **1.4.1 FAA 1988 Site Investigation**

In 1988, FAA performed a site investigation at Annette Island to inspect the station for hazardous materials (Eberhardt 1988). The investigation's findings were not relative to the FAA-leased or formerly leased facilities included in this report.

### **1.4.2 United States Army Corps of Engineers (USACE) Site Investigation**

In September 1985, the United States Department of Defense performed an inventory of materials and debris remaining at the landing field (USACE 1990). Electrical equipment

stored in Room A of then Hangar facility was sampled for PCBs. Results are included in the Annette Island ECIR (E & E 1992b).

#### **1.4.3 FAA 1990 Underground Storage Tank Study**

An underground storage tank (UST) investigation was performed by FAA in 1990 at the Annette Island FAA Station (Harding Lawson Associates [HLA] 1990). Three USTs were identified during that investigation. Two USTs were located at the VORTAC/DF facility, and one UST was located at the RCAG facility. One UST at the VORTAC/DF subsequently was removed, and the fuel in the remaining UST was changed from gasoline to diesel. These three tanks were present at the time of the ECI. In addition, the previous investigation indicated that a 515-gallon gasoline UST located at the NDB/H-marker facility had been removed in 1981.

#### **1.4.4 FAA 1991 Environmental Compliance Investigation**

In August 1991, E & E conducted an ECI for the Annette Island FAA Station. ECI activities included conducting literature searches, real estate searches, site reconnaissance, site inventory of toxic and hazardous materials, site sampling, sample analysis and production of an ECIR which presented conclusions and recommendations for each facility and presented information for EPA's HRS.

#### **1.4.5 FAA 1992 Removal Project**

Hazardous and nonhazardous wastes were removed from the Annette Island FAA Station under Task Order No. 13. A preliminary station visit, performed to inventory and inspect the wastes to be disposed of, was conducted on September 10 and 11, 1992. The removal action was conducted on October 15 to 17, 1992. All wastes designated for disposal were packaged for shipment and were released to the initial off-site transporter. Waste packaging efforts included securing large transformers within steel or plastic totes, bulking residual drum liquids into a new drum, and labpacking smaller waste items into drums. Stained soil found contaminated with PCB oil from rectifiers behind the former FAA warehouse building (now Metlakatla Power and Light [MPL] offices) was excavated and removed for disposal. Laboratory samples were collected from this excavation site, and wipe samples were collected at the old FAA hanger building from stained patches of concrete that had resulted from transformer oil leakage. Laboratory results later indicated that the soil

excavation had been conducted successfully, but residual PCB contamination was still present in the concrete stains.

### **1.5 SITE CLEANUP AND INVESTIGATION REPORT ORGANIZATION**

This SCIR is organized to provide the reviewer with the relevant ESI and IC activities on a facility-by-facility basis. For convenience, the SCIR is divided into three volumes to allow review and research of a particular element while concentrating on a particular FAA facility or site.

Volume 1 is structured with major chapters defining:

- Purpose and organization
- General site investigation and cleanup activities
- Detailed ESI and IC activities discussed on a facility-by-facility basis and
- Overall station conclusions and recommendations.

Volume 2 supports Volume 1 with:

- Photolog
- Laboratory data validation memoranda
- Laboratory data sheets and
- Chain-of-custody reports.
- Waste categorization and disposal documentation, including:
  - Inventory of waste removed
  - Waste transporters and Treatment, Storage, and Disposal (TSD) facilities and
  - Waste shipping papers.

Volume 3 supports Volume 1 with:

- X-ray fluorescence (XRF) field screening raw data.

<p><b>Table 1-1</b></p> <p><b>NORMAL RANGES OF ELEMENTAL CONCENTRATIONS IN SOILS</b></p> <p><b>(All measurements are in ppm [mg/kg].)</b></p>					
Element	Crustal Average <sup>a</sup>	Alaska Mean <sup>b</sup>	Western U.S. Mean <sup>c</sup>	Western U.S. Normal Range Mean $\pm$ 1 s.d. <sup>b</sup>	Normal Alaskan Range <sup>d</sup>
Aluminum	71,000	62,000	58,000	29,000-116,000	12,000-120,000
Antimony	0.2	—	0.47	0.22-1.01	—
Arsenic	1.8	6.7	5.5	2.8-10.9	<10-750
Barium	424	595	580	337-998	39-3,100
Beryllium	2.8	1.5	0.68	0.30-1.56	<1-7
Cadmium	0.2	—	0.2	0.1-0.5	—
Chromium	100	50	41	19-90	5-390
Cobalt	25	13	7.1	3.6-14.0	<2-55
Copper	55	24	21	10-43	3-810
Iron	50,000	35,000	21,000	10,800-41,000	5,500-100,000
Lead	13	12	17	9-31	<4-310
Manganese	950	510	380	192-752	200-400
Mercury	0.08	—	0.05	0.02-0.11	—
Nickel	75	24	15	7-32	<3-320
Selenium	0.05	—	0.23	0.09-0.56	—
Silver	0.07	—	0.2	0.1-0.5	—
Thallium	0.5	—	0.2	0.1-0.4	—
Tin	2	—	0.9	0.4-1.9	—
Vanadium	—	—	70	36-136	—
Zinc	70	70	55	31-98	<20-2,700
Molybdenum	1.5	0.86	0.85	0.39-1.85	<2-15
Thorium	7.2	—	9.1	6.1-13.6	<1.6-76
Uranium	1.8	2.3	2.5	1.7-3.6	<0.2-4.5
Yttrium	33	14	22	13-37	<4-100

Key at end of table.

- a Various published sources.
- b Alaska Soil Data From: Gough, L.P., Severson, R.C., Shacklette, H.T. 1988. Element Concentrations in Soils and Other Surficial Materials of Alaska. U.S. Geological Survey Professional Paper 1458.
- c Western Soil Data From: Shacklette, H.T., and Boerngen, J.G.; 1984: Element Concentrations in Soils and Other Surficial Materials of the Conterminous United States. U.S. Geological Survey Professional Paper 1270.
- d Means and standard deviations are Geometric to account for log-normal distributions.





Key:

- = Data not provided.
- mg/kg = Milligrams per kilogram.
- ppm = Parts per million.

Source: Ecology and Environment, Inc. 1994.



Source: USGS Ketchikan (A-5) Quadrangle, Alaska.



Ecology and Environment, Inc.


Figure 1-1

Proj. No.: VS1000

Date: 8-30-94


Drawn By:

Title: Annette Island FAA  
Station Location



VS150018

Source: ALD-ANN-020.003



## LOCATION MAP

TOWNSHIP 79S  
RANGE 92E  
COPPER RIVER MERIDIAN

## LEGEND

Shores



APPROXIMATE SCALE IN FEET

0 1000 2000 4000 6000

Ecology and Environment Inc.	
Figure: 1-3	Proj. No: VR1000
Date: 9/08/94	Drawn by: EGM
Title: ANNETTE ISLAND FAA STATION REMOTE SAMPLE LOCATION MAP	

## **2. EXPANDED SITE INVESTIGATION AND INTERIM CLEANUP ACTIVITIES**

The site investigation and cleanup activity at the Annette Island FAA Station consisted of ESIs at the following facilities:

- VORTAC/DF
- NDB/H-marker and
- RCAG.

IC activities were conducted at the following facilities:

- RCAG
- Hangar
- ALS
- GS and
- LOC.

This section describes first the ESI and then the IC activities conducted at the site. The third part of this section discusses the development of site-specific risk-based evaluation criteria. An in-depth discussion of individual facility investigations and cleanup activities is presented in Sections 3 through 9.

### **2.1 EXPANDED SITE INVESTIGATION**

#### **2.1.1 General**

The ESI was performed at the Annette Island FAA Station from June 10 to 22, 1994. The investigation consisted of the collection of potential source and target characterization

samples at potential CERCLA contaminant source areas in the VORTAC/DF, NDB/H-marker, and RCAG facilities; wetlands survey associated with CERCLA source areas; and collection of samples at potential ADEC-contaminated source areas at the VORTAC/DF facility. The field team that performed the ESI and their affiliations and assignments are listed in Table 2-1.

## **2.1.2 Expanded Site Investigation Activities**

### **2.1.2.1 VORTAC/DF Facility**

Activities at the VORTAC/DF facility included the collection of sediment, surface and subsurface soil samples. Surface and subsurface soil samples were collected to delineate lead contamination potentially associated with leaded paint overspraying operations and to delineate petroleum contamination associated with the UST. Surface sediment and soil samples were collected along overland surface water routes and in adjoining wetlands for target characterization. Details of the ESI conducted at the VORTAC/DF facility are provided in Section 3.2

### **2.1.2.2 NDB/H-MARKER Facility**

Sampling at the NDB/H-marker facility included the collection of sediment, surface, and subsurface soil samples. Surface and subsurface soil samples were collected to delineate the areal and vertical extent of CERCLA contamination associated with ash deposited in the soil around the former NDB/H-marker building foundation, resulting from when the building was burned down. Surface sediments and soil samples were collected along overland surface water pathways and in adjoining wetlands for target characterization. Details of the ESI at the NDB/H-Marker facility are provided in Section 4.2.

### **2.1.2.3 RCAG Facility**

Sampling at the RCAG facility included the collection of surface soil samples to delineate the areal extent of potential CERCLA contamination associated with drums formerly stored in the area. Sediment samples were also collected along overland surface water pathways and in adjoining wetlands for HRS target characterization. Details of the ESI at the RCAG facility are provided in Section 5.2.

### **2.1.3 Deviations from the Work Plan**

Deviations from the ESI work plan are described on a facility-specific basis in Sections 3.2.1.4, 4.2.1.4, and 5.2.1.3. All deviations were undertaken with the concurrence of FAA and were based on sound technical considerations.

## **2.2 INTERIM CLEANUP**

### **2.2.1 General**

IC activities were performed at the RCAG, Hangar, ALS, GS, and LOC facilities. Work was conducted between June 13 and June 17, 1994. The field team for the IC activities consisted of two E & E personnel and one subcontractor personnel. The personnel and their affiliations and roles are listed in Table 2-1.

### **2.2.2 Interim Cleanup Activities**

#### **2.2.2.1 RCAG Facility**

IC activities at the RCAG facility were to include pumping out remaining fuel from the inactive gasoline UST. Upon inspection, however, the UST was observed to be empty and was capped and locked. Details of the IC activities at the RCAG facility are provided in Section 5.3.

#### **2.2.2.2 Hangar Facility**

IC activities at the Hangar facility included the cleanup and subsequent sampling of a small section of the hangar concrete floor. This section of the hangar was the former location of three FAA-owned, PCB-containing transformers. Debris from the floor was first removed and then the floor cleaned with solvents. PCB wipe samples were then collected from this area. Details of the IC activities at the Hangar facility are presented in Section 6.2.

#### **2.2.2.3 ALS Facility**

IC activities at the ALS facility included sampling inactive, oil-filled transformers and electrical equipment for PCB in accordance with TSCA regulations. Details of the IC activities at the ALS are presented in Section 7.2.

#### **2.2.2.4 GS Facility**

IC activities at the GS facility included pumping non-PCB transformer oil into a drum and removing the drum from Annette Island. Details of the IC activities at the GS are presented in Section 8.2.

#### **2.2.2.5 LOC Facility**

IC activities at the LOC facility included drumming several small, sealed transformers and properly storing the drum at the VORTAC/DF facility. Details of the IC activities at the LOC are presented in Section 9.2.

#### **2.2.3 Deviations from the Work Plan**

Deviations from the work plan are described on a facility-specific basis in Sections 5.2.1.3, 6.3, 7.3, 8.3, and 9.3. All deviations were undertaken with the concurrence of FAA.

### **2.3 SAMPLE QUALITY ASSURANCE**

The Annette Island Station sampling program was designed using sampling strategies to focus on localized areas of surface and subsurface soil, and sediment contamination. Specific sampling locations were selected based on the approved ESI/IC work plan (E & E 1993b) and field observations. Sample points were recorded using a global position system. With the exception of the background samples, samples were collected at points either known or suspected to be the most probable locations of contamination or along migration pathways. When actual sample locations differed from the sample locations defined in the ESI/IC, approval from the FAA Contracting Officer (CO) was obtained.

Level II, III, and IV samples were collected to provide the maximum amount of information with the appropriate level of quality in the most cost-effective manner possible. Level III samples were collected to confirm the presence of contaminants identified by Level II screening analysis. Level II samples were field screening samples. Field screening methods included Spectrace XRF analysis for metals in soils and lead in paint; EnSys Petro RISC analysis for petroleum fuels in soils; and EnSys PCB RISC analysis for PCBs in wipe samples. Sampling and analysis protocol for each of these screening methods is presented in Appendix F.

All samples were collected, packaged, stored, shipped, and analyzed in accordance with EPA and ADEC guidelines and standard operating procedures as defined in the Task No. 11, Generic Work Plan (E & E 1992c) and the Annette Island ESI/IC. Data validation qualifiers are discussed in Section 2.4.1; data usability is described in Section 2.5; Section 2.6 presents the quality assurance (QA)/quality control (QC) results for samples from the Annette Island FAA Station; and field QA information and analytical QA/QC specifics are presented in Appendix F.

## **2.4 DATA VALIDATION**

Levels III and IV analytical data were validated following the guidelines referenced in the data validation memoranda presented in Appendix B. The memoranda identify laboratory analytical QA/QC data related to all sample results. Sample analysis procedures specified in the ESI/IC identify the method/matrix-specific QC tests and criteria limits for the results of these tests. In validation, QC and associated sample results underwent QA review to identify analytical results that failed to meet criteria. Data associated with QC tests that failed to meet the criteria were flagged with qualifiers. The data validation memoranda document the sample/analyte-specific causes for all flags. Level II data were validated according to the protocols presented in Appendix F.

### **2.4.1 Data Qualifiers**

Data qualifiers are employed for both metal and organic data results. These qualifiers are defined below:

- J = The analyte was analyzed for and was positively identified, but the associated numerical value may not be consistent with the amount actually present in the sample. The data should be seriously considered for decision-making and are usable for many purposes.
- NJ = The analysis indicated that the analyte has been tentatively identified and that the associated numerical value may not be consistent with the amount actually present in the sample.
- R = QC information indicated that data are unusable for any purpose. The analyte was analyzed for, but the presence or absence of the analyte has not been verified.



#### **2.4.2 Metals Data**

Data validation for metals analyses applies to data for all Level III and Level IV Target Analyte List (TAL) furnace metals, mercury, and inductively coupled argon plasma metals, toxicity characteristic leaching procedure (TCLP) extractable metals, and Level II XRF metals. QC criteria considered for metals analyses include or apply to sample holding times, calibration verification, laboratory-reported detection limits, preparation blank results, inductively coupled argon plasma spectrometry interference check sample results, spike sample results, duplicate sample results, laboratory control sample results, and atomic absorption (AA) post-digestion spike recovery, and duplicate injection results.

#### **2.4.3 Organic Data**

Data validation for organic analyses applies to data for all Level II, III, and IV: benzene, toluene, ethylbenzene, xylenes (BTEX); base neutral/acid extractables (BNAs); volatile organic compounds (VOCs); chlorinated pesticides/PCB; volatile petroleum hydrocarbons as gasoline (VPH-G); extractable diesel-range petroleum hydrocarbons as diesel-range organics (DROs); total recoverable petroleum hydrocarbons (TRPH); and dioxin. Due to the analytical procedures for organic analyses, data qualifiers are assigned using slightly different criteria when compared to inorganic analyses. These QC criteria include or apply to sample holding times, instrument calibration, laboratory method blank results, surrogate spike recovery results, matrix spike/matrix spike duplicate results, and internal standard performance results.

### **2.5 DATA USABILITY**

In addition to data validation of laboratory performance, a data usability review was completed for all Annette Island FAA Station data. The usability review determines the adequacy of data and/or information on a project-/site-/sample-/analyte-specific basis to:

- Describe or characterize sample or site conditions;
- Describe, characterize, or interpret conditions or activities impacting a sample or site; and
- Describe, characterize, or interpret the results of conditions or activities impacting a sample or site.

Data usability is a function of the data quality objectives (DQOs) outlined as ESI/IC objectives and the overall QA review of field, laboratory, and files/reference search data. The qualification of analytical data does not necessarily preclude the use of that data.

The primary goal of sample collection and analysis under the ESI process is to determine the presence or absence of target analytes and, if present, to provide a reasonable estimate of concentration. Data that failed to meet minimum data validation standards were rejected (annotated with an "R" qualifier in the data validation memoranda in Appendix B) and are neither reported nor utilized beyond that point. Data flagged "J" or "NJ", however, were reviewed further to identify specific reasons for flagging, and it was determined that qualified data are usable for the purposes of this report; this information was incorporated into a determination of usability. Qualifiers from the associated data validation memorandum were not included in summary tables or text unless they had an impact on decisions regarding recommendations for further actions at the station.

Such decisions require accurate data; therefore, data whose qualitative and/or quantitative accuracy at action level concentrations is in doubt require the decision-maker to consider the consequences of a determination either to take no further action or to take action. Recommendations for such decisions are presented in facility-specific sections and are summarized in Section 10.

## **2.6 PRESENTATION OF ANALYTICAL RESULTS**

Annette Island FAA Station sample collection information are presented in facility sections. This information includes sample number, matrix, location, sampling date, and laboratory analyses for each sample. Low levels of several common laboratory and/or sampling contaminants are normally encountered in environmental laboratory analyses. The most common of these are acetone, methylene chloride, 2-butanone, carbon disulfide, toluene, di-n-butyl phthalate, bis(2-ethylhexyl)phthalate, di-n-octyl phthalate, and butyl benzyl phthalate. The determination whether to include these analytical results in this report was made on a sample-by-sample basis during the QA and data usability review.

Analytes detected in samples at less than five times the levels measured in the corresponding trip and/or rinsate blanks are included in the summary tables but not discussed in the text. All analytical results are included in Appendices B and G. Summary tables of analytes found in samples, including background samples, collected at the Annette Island FAA Station are presented in facility sections.

## 2.7 FIELD QUALITY ASSURANCE SAMPLES

Field QC samples for Levels II, III, and IV were collected by sampling teams to assess the quality of the sampling effort and analytical data. QC samples collected include background samples, rinsate samples, field screening QA/QC samples, and confirmation samples.

### 2.7.1 Background Samples

Four background samples were collected to characterize background soil and sediment in order to establish baseline concentrations of analytes in road/pad gravel, peat sediment, stream sediment, and beach sediment (see Table 2-2). All of these samples were analyzed for Level IV TAL metals, BNA, VOC, pesticides/PCB, and dioxin. The analytical results of these background samples were compared to the results of samples collected at the VORTAC/DF, NDB/H-marker, and RCAG facilities and are discussed in the facility sections. Positive results from the background analyses are summarized in Tables 2-3, 2-4, and 2-5, and sample locations are presented on Figures 2-1 and 2-2. Data validation memorandum and laboratory reports are presented in Appendix A.

Background soil sample ANN94ESB-SD-101 was collected approximately 0.1 mile southeast of the NDB/H-marker building in an area upgradient of all known sources and represents the gravelly soil used to elevate roads and FAA structures above the muskeg (see Figure 2-2). Source samples collected from the VORTAC/DF and NDB/H-marker facilities were compared to this sample.

Analytical results indicated toluene at 56 micrograms per kilogram ( $\mu\text{g}/\text{kg}$ ) and xylene at 6  $\mu\text{g}/\text{kg}$  (see Table 2-3). Both of these compounds were also found in the rinsate blank and are suspected to be attributed to laboratory contamination. Most TAL metals were present in the sample at varying concentrations (see Table 2-4). No BNAs, pesticides, PCBs, or dioxins were detected in this sample.

Background sediment samples were collected in areas with similar ecological areas in drainages that appeared not to have been impacted by any contaminant sources. Background sediment sample ANN94ESB-SE-100, representative of background beach sediments, was collected in a stream channel at the beach south of the south end of the runway at the south end of the island, between the high and low water tide lines west of Grey Point (see Figure 2-2). The stream channel contained a gravelly sand substrate. No vegetation grew within or adjacent to the stream channel. Grass species grew on elevated areas of the beach. Target

beach sediment samples collected from the VORTAC/DF, NDB/H-marker, and RCAG facilities were compared to this sample.

Analytical results indicated low concentrations of toluene and xylene at 5 and 1  $\mu\text{g/kg}$ , respectively (see Table 2-3). Both of these compounds were also found in the rinsate sample and are suspected to be attributed to laboratory contamination. TAL metals were also detected in this sample at varying concentrations (see Table 2-4). No other compounds were detected in this sample.

The background stream sediment sample ANN94ESB-SE-101 was also collected on the southern end of the island, west of Grey Point, but it was collected in a different stream channel than the background beach sample (see Figure 2-2). The stream substrate was a gravelly sandy soil. Skunk cabbage (*Lysichiton americanum*), sphagnum moss, false-lily of the valley (*Maiantheophum dilatatum*), arrowhead (*Sagittaria latifolia*) were in the herbaceous layer on the stream banks. Salmonberry (*Rubus spectalalis*) and fool's huckleberry (*Menziesia ferruginea*) were in the shrub layer. Western redcedar (*Thuja plicata*), yellow cedar, and western hemlock occupied the tree stratum. The soil on the banks was an organic peat. This sample represents background stream sediment conditions. Target stream sediment samples collected at the VORTAC/DF, NBD/H-marker, and RCAG facilities were compared to this sample. TAL metals were detected in this background sediment sample at varying concentrations (see Table 2-4). No other compounds were detected in this sample.

The background peaty sediment sample ANN94ESB-SE-102 was collected west of the airport along Point Davison Road (see Figure 2-2). This sample was collected in a shore pine-yellow cedar-muskeg/open water wetland complex. The muskeg wetland contained deer cabbage (*Fauria crista-galli*), bog laurel, jeffrey shooting star (*Dodecatheon*), common juniper (*Junieris communis*), sphagnum moss, and grass species in the herbaceous layer. The shrub layer contained sweet gale (*Myrica gale*), labrador tea, yellow cedar, western redcedar, and shore pine. The tree layer contained yellow cedar, western redcedar, and shore pine. The soil was composed of organic peat material and was saturated. The open water wetland was vegetated with buckbean (*Menyanthis trifohata*). This sample represents background peat sediment conditions. Target peat sediment samples collected at the VORTAC/DF, NDB/H-marker, and RCAG facilities, and source samples collected at the RCAG facility were compared to this sample. Toluene and xylene were detected in this sample at 7 and 22  $\mu\text{g/kg}$ , respectively (see Table 2-3). Both of these compounds were also detected in the rinsate and are suspected to be laboratory contamination. Several TAL metals were also detected in the

sample at varying concentrations (see Table 2-4). Additionally, low concentrations of several dioxin isomers were detected in this sample (see Table 2-5).

### **2.7.2 Rinsate Samples**

Two reagent water and one dioxin hexane rinsate samples were collected to identify potential sources of cross-contamination from sampling equipment used on site. Results are presented in Tables 2-3, 2-4, and 2-5. Samples ANN94ESV-WA-100, ANN94ESV-WA-400, and ANN94ESN-HE-100 were collected following decontamination of a stainless-steel trowel used to collect surface soil and sediment samples. Sample ANN94ESV-WA-100 was submitted for Level IV analysis of TAL metals, BNA, VOC, pesticides/PCB, and dioxin. Sample ANN94ESV-WA-400 was submitted for Level III analysis of TRPH, DRO, and VPH-G. Sample ANN94ESN-HE-100 was a hexane rinsate submitted for Level IV dioxin analysis. All results for rinsate samples were below method detection limits (MDLs) with the following exceptions: ANN94ESV-WA-100 contained 12.4 micrograms per liter ( $\mu\text{g/l}$ ) iron, 6  $\mu\text{g/l}$  toluene, and 1.0  $\mu\text{g/l}$  xylene. Low levels of these contaminants are likely due to laboratory contamination.

### **2.7.3 Level II Field Screening**

Four types of field screening analyses were performed for the Annette Island FAA Station ESI including: XRF metals in soils; XRF lead in paint, ENSYS Petrol RISC analysis for petroleum hydrocarbons in soil, and ENSYS PCB RISC analysis for PCBs in wipe samples.

Field screening analyses protocols are presented in Appendix F and include sample preparation, instrument calibration, sample analysis, QA/QC samples, and QA/QC validation. XRF field screening methods follow the EPA Emergency Response Team (ERT) Standard Operating Procedures (SOP) for the Spectrace 9000 XRF. The ENSYS RISC analyses follow the appropriate ENSYS User Guides.

### **2.7.4 Level II Confirmation Samples**

In addition to daily QA/QC procedures, some samples analyzed by field screening methods were submitted to fixed laboratories for confirmation of results. Samples analyzed for XRF metals in soil, petroleum hydrocarbons in soil, and PCBs in wipe samples were submitted to fixed laboratories for confirmation. XRF field screening results for metals may

be low compared to off-site laboratory confirmation results because water content in some samples was above the recommended 5% to 20% sample percent water in the XRF operating procedures.

#### **2.7.4.1 XRF Soil Confirmation Samples**

Approximately 10% of the soil samples collected at the VORTAC/DF and NDB/H-marker facilities that were analyzed for metals with the XRF were also submitted to the Analytical Services Center (ASC) for total lead analysis per EPA Method SW-846. Since XRF reflects total lead concentrations and EPA Method SW-846 reflects acid digestible lead concentrations, a linear regression was performed for lead rather than a direct comparison of results. Twenty-nine samples collected from the VORTAC/DF (22 samples) and NDB/H-marker (seven samples) facilities were submitted for confirmation. A linear regression was performed for all 29 samples and yielded a relatively low correlation coefficient ( $r = 0.78535$ ). Due to the gravel and ash soil matrix found at the NDB/H-marker, high sample heterogeneity was suspected for these samples. Therefore, a linear regression was again performed, but only for the 22 VORTAC/DF samples. This regression yielded a higher correlation coefficient ( $r = 0.96068$ ), indicating the XRF and ASC lead results are strongly correlated. The slope was calculated to be 1.198 with an intercept of 103. Since the soil matrix at the VORTAC facility is relatively fine-grained and homogeneous, these analytical results are more accurately reproduced within an analytical method. In the same way, sample results from VORTAC samples would also yield a more accurate comparison of analytical methods. Therefore, this second regression more accurately describes the overall XRF method results as they relate to EPA Method SW-846 results for this ESI. The slope and intercept are further used below to estimate expected EPA Method SW-846 lead results from XRF screening lead results. For example, a 500 milligram per kilogram (mg/kg) SW-846 lead result would correlate to 331 mg/kg on the XRF. However, the XRF instrument reads directly in parts per million (ppm) and makes no adjustment to a dry weight basis as laboratory results are reported.

#### **2.7.4.2 ENSYS Confirmation Samples**

All samples collected for ENSYS Petrol RISC analysis for petroleum hydrocarbons in soil and ENSYS PCB RISC analysis for PCBs in wipe samples were submitted to fixed laboratories for confirmation. Results are discussed in facility sections.

## 2.8 UPDATED MEDIA-SPECIFIC EVALUATION CRITERIA (MSECs) FOR FAA SITES

The MSECs were originally developed by E & E, Inc. when the RCRA Corrective Measures (CMS) Action Levels were EPA's only source of guidance on developing risk-based screening levels for environmental media. Consequently, the CMS action level calculations and assumptions were incorporated in the MSECs for screening contaminant concentrations at remote FAA sites in Alaska. Since that time, EPA's Superfund Program has refined its guidance on calculating risk-based screening levels for environmental media in the form of Risk Assessment Guidance for Superfund (RAGS), Part B (EPA 1991a). In addition, EPA Region 3 publishes risk-based concentrations (RBC) tables for various media that are based on the methodology described in RAGS, Part B, and EPA's standard default reasonable maximum exposure assumptions (EPA 1991b). The Region 3 RBC Table is updated quarterly to incorporate EPA's latest toxicological indices (reference doses [RfDs] and cancer slope factors [SF]) for chemicals and to add chemicals for which RfDs and Sfs have just become available. The Region 3 RBC table now includes nearly 600 chemicals. Because of its breadth of coverage, its frequent updates, and its ready availability, the Region 3 RBC Table is recommended as a source of screening criteria by several EPA regions, including Region 10. For these reasons, the MSECs will henceforth be based on the calculations, exposure assumptions, and RBC values in the current Region 3 RBC Table. The methodology used in calculating the RCRA CMS action levels and the Region 3 RBCs is essentially the same; however, there are minor differences in the receptors and exposure assumptions used in calculating the values. As noted earlier, the Region 3 RBCs incorporate EPA's standard default exposure assumptions and thus best reflect agency guidance on risk-based screening criteria.

The MSECs for soil are based on the Region 3 RBCs for residential soil and will continue to use a multiplier of 4 to adjust for the lower exposure frequency expected to occur at remote FAA stations in Alaska (see Table 2-6). The MSECs for other environmental media will be equal to the Region 3 RBCs for the same or comparable media.

MSECs were used to screen the analytical results for Annette Island to identify contaminants and areas that could have the potential to pose a significant risk of adverse human health effects. With the exception of lead, the MSECs were based on EPA Region 3 RBCs which incorporate EPA's standard default exposure assumptions. No RBC's are available for lead because EPA has been unable to derive verifiable reference doses or slope factors from the available toxicity data. Therefore the new soil screening level of 400 mg/kg

recommended in EPA's Office of Solid Waste and Emergency Response (OSWER) directive 9355.4-12 (EPA 1994) was used as the basis of the MSEC for lead. MSECs for soil for Annette Island were obtained by adjusting the standard EPA Region 3 RBCs for residential soil and the new lead screening level upward by a factor of 4 to reflect the climatic conditions in Alaska and more limited contact with contaminated areas than assumed for the standard RBCs and screening levels. For media other than soil, the EPA Region 3 RBCs were used as the MSECs without adjustment.



Table 2-1	
EXPANDED SITE INVESTIGATION/INTERIM CLEANUP FIELD TEAM PERSONNEL ANNETTE ISLAND FAA STATION ANNETTE ISLAND, ALASKA	
Name	Role
<b>EXPANDED SITE INVESTIGATION</b>	
<b>Ecology and Environment, Inc.</b>	
Stuart Richardson	Project director
Dave Franzen	Project manager, field team leader
Mike Jones	Sampler, site safety officer
Annette Sackman	Chemist
Louise Flynn	Wetlands specialist
<b>NISC- FAA Support Contractor</b>	
Russell Renk	Contracting officer's representative
<b>INTERIM CLEANUP</b>	
<b>NISC- FAA Support Contractor</b>	
Russell Renk	FAA contracting officer's representative
<b>Ecology and Environment, Inc.</b>	
Dave Franzen	Project manager, field team leader
Louise Flynn	Sampler
Annette Sackman	Field chemist
<b>PENCO- Remedial Subcontractor</b>	
Don Orvis	Field worker
Doug Ferguson	Pilot
Rex Lumpkin	Project supervisor

recycled paper

2-15

ecology and environment

<p><b>Table 2-2</b></p> <p><b>FIELD QUALITY ASSURANCE SAMPLE SUMMARY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p>					
Sample No.	QA Use	Matrix	Analytical Parameters	Laboratory	Comments
ANN-94ESB-SD-101	Background	Soil	BNA, Pest/PCB, TAL metals, VOC, Dioxin	ASC/Triangle Level IV	Background soil sample for the NDB and VORTAC facilities, collected of gravel road shoulder, 0.1 mile southeast of NDB.
ANN-94ESB-SE-100	Background	Sediment	BNA, Pest/PCB, TAL metals, VOC, Dioxin	ASC/Triangle Level IV	Background beach sediment collected at the beach immediately south of the end of the runway.
ANN-94ESB-SE-101	Background	Sediment	BNA, Pest/PCB, TAL metals, VOC, Dioxin	ASC/Triangle Level IV	Background stream sediment collected from a streambed flowing onto the beach where SE-100 was collected.
ANN-94ESB-SE-102	Background	Sediment	BNA, Pest/PCB, TAL metals, VOC, Dioxin	ASC/Triangle Level IV	Background peat sediment collected 0.7 mile west of the south end of the runway.
ANN-94ESV-WA-100	Rinsate	Water	Pest/PCB, TAL metals, VOC, BNA	ASC Level IV	Rinsate sample collected from a sampling trowel after decontamination.
ANN-94ESV-WA-400	Rinsate	Water	DRO, TRPH, VPH-G	ASC Level III	Rinsate sample collected from a sampling trowel after decontamination.
ANN-94ESN-HE-100	Rinsate	Hexane	Dioxin	Triangle Level IV	Rinsate sample collected from a sampling trowel after decontamination.

**Key:**

- ASC = Analytical Service Center.
- BNA = Base neutral/acid extractable compounds.
- DRO = Diesel-range organics.
- Pest/PCB = Organochlorine pesticides/polychlorinated biphenyls.
- TAL metals = Target Analyte List metals.
- TRPH = Total recoverable petroleum hydrocarbons.
- VOC = Volatile organic compounds.
- VPH-G = Volatile petroleum hydrocarbons as gasoline.

2-16

<p align="center"><b>Table 2-3</b></p> <p align="center"><b>FIELD QUALITY ASSURANCE SAMPLES</b>  <b>(BACKGROUND, RINSATE, AND TRIP BLANKS)</b>  <b>POSITIVELY IDENTIFIED ORGANIC COMPOUNDS</b>  <b>ANNETTE ISLAND FAA STATION</b>  <b>ANNETTE ISLAND, ALASKA</b>  <b>(soil in µg/kg, water in µg/l)</b></p>					
Sample Number:	ANN94ESB-SD-101 (Background)	ANN94ESB-SE-100 (Background)	ANN94-ESB-SE-101 (Background)	ANN94ESB-SE-102 (Background)	ANN94ESV-WA-100 (Rinsate)
Compound					
<b>VOC</b>					
Toluene	56	5 J	ND	7 J	6
Total Xylenes	6	1 J	ND	ND	1
<b>BNA</b>					
bis(2-Ethylhexyl)phthalate	ND	ND	ND	ND	2

**Key:**

BNA = Base neutral/acid extractable organic compound.  
 J = Result is estimated because it is below method detection limits.  
 µg/kg = Micrograms per kilogram.  
 µg/L = Micrograms per liter.  
 ND = Not detected at quantitation limits noted in parentheses.  
 SD = Soil sample.  
 SE = Sediment sample.  
 VOC = Volatile organic compounds.  
 WA = Water sample.

<p><b>Table 2-4</b></p> <p><b>FIELD QUALITY ASSURANCE SAMPLES (BACKGROUND, RINSATE)</b></p> <p><b>POSITIVELY IDENTIFIED INORGANIC COMPOUNDS</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(soil in mg/kg, water in µg/l)</b></p>					
Sample Number:	ANN94ESB-SD-101 (Background)	ANN94ESB-SE-100 (Background)	ANN94ESB-SE-101 (Background)	ANN94ESB-SE-102 (Background)	ANN94ESV-WA-100 (Rinsate)
Compound	Soil	Beach Sediment	Stream Sediment	Peat	
<b>Metals</b>					
Aluminum	9,420	5,090	3,110	959	ND
Arsenic	9.5	1.2	0.83	ND	ND
Barium	37.8	23.7	9.8	4.7	ND
Beryllium	0.21	0.14	0.08	ND	ND
Calcium	1,240	3,180	948	528	ND
Chromium	10.5	4.8	3.6	4.0	ND
Cobalt	18.1	4.1	4.0	ND	ND
Copper	13.0	6.8	8.9	1.5	ND
Iron	16,500	10,900 J	8,560 J	1,950 J	12.4
Lead	4.7	4.2 J	3.2 J	4.8 J	ND
Magnesium	23,100	3,570	2,360	446	ND
Manganese	247	122	94.8	7.4	ND
Nickel	95.5	4.8	5.1	ND	ND

Key at end of table.

<p><b>Table 2-4</b></p> <p><b>FIELD QUALITY ASSURANCE SAMPLES (BACKGROUND, RINSATE)</b></p> <p><b>POSITIVELY IDENTIFIED INORGANIC COMPOUNDS</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(soil in mg/kg, water in µg/l)</b></p>					
Sample Number:	ANN94ESB-SD-101 (Background)	ANN94ESB-SE-100 (Background)	ANN94ESB-SE-101 (Background)	ANN94ESB-SE-102 (Background)	ANN94ESV-WA-100 (Rinsate)
Compound	Soil	Beach Sediment	Stream Sediment	Peat	
Potassium	630	701	ND	ND	ND
Sodium	ND	1,160	ND	ND	ND
Vanadium	31.8	17.7	10.6	ND	ND
Zinc	49.4	19.6	27.5	ND	ND

**Key:**

J = Estimated.  
 µg/L = Micrograms per liter.  
 mg/kg = Milligrams per kilogram.  
 ND = Not detected.  
 SD = Soil sample.  
 SE = Sediment sample.  
 WA = Water sample.

<p><b>Table 2-5</b></p> <p><b>FIELD QUALITY ASSURANCE SAMPLES (BACKGROUND, RINSATE)</b></p> <p><b>POSITIVELY IDENTIFIED DIOXIN ISOMERS</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(soil in ng/kg; liquid in ng/kg)</b></p>					
Sample Number: (ANN94-)	ESB-SD-101	ESB-SE-100	ESB-SE-101	ESB-SE-102	V-HE-100 (Hexane Rinsate)
Compound	Soil	Beach Sediment	Stream Sediment	Peat	
<b>Dioxin Isomers</b>					
1,2,3,4,6,7,8-HpCDD	ND	ND	ND	35.4	ND
OCDD	ND	ND	ND	170	ND
1,2,3,4,6,7,8-HpCDF	ND	ND	ND	6.49	ND
TEF	0	0	0	0.589	0
Total PeCDD	ND	ND	ND	29.0	ND
Total HxCDD	ND	ND	ND	68.1	ND
Total HpCDD	ND	ND	ND	35.4	ND
Total TCDF	ND	ND	ND	226	ND
Total HpCDF	ND	ND	ND	23.4	ND

**Key:**

HE = Hexane rinsate.  
 ND = Not detected.  
 ng/g = Nanograms per gram.  
 ng/kg = Nanograms per kilogram.  
 SD = Soil sample.  
 SE = Sediment sample.

Table 2-6		
MEDIA-SPECIFIC EVALUATION CRITERIA—SOIL FOR ANALYTES WITH POSITIVE RESULTS		
Chemical	Value (mg/kg)	
REGULATORY GUIDANCE VALUES		
ADEC POLs		
Diesel Range	100	
Gasoline Range	50	
Benzene	0.1	
Total BTEX	10	
TRPH <sup>a</sup>	2,000	
EPA Values		
Polychlorinated biphenyls	25	
Dioxins	0.001	
Lead	400	
RBC <sup>b</sup>		Calculated MSEC
Inorganics		
Antimony	31	124
Arsenic	23	92
Barium	5,500	22,000
Beryllium	0.15	0.60
Cadmium	39	156
Chromium	78,000	312,000
Copper	2,900	11,600
Mercury	23	92
Nickel	1,600	6,400
Selenium	390	1,560
Silver	390	1,560
Thallium	5.5	22 <sup>c</sup>
Zinc	23,000	92,000
Organics		
Anthracene	23,000	92,000
Benzo(b)fluoranthene	0.875	3.5
alpha-BHC	0.35	1.4

Key at end of table.

Table 2-6		
MEDIA-SPECIFIC EVALUATION CRITERIA—SOIL FOR ANALYTES WITH POSITIVE RESULTS		
Chemical	Value (mg/kg)	
Chloroform	100	400
Chrysene	88	352
Diethylphthalate	63,000	252,000
Fluoranthene	3,100	12,400
Phenanthrene	3,100	12,400 <sup>d</sup>
Pyrene	2,300	9,200


- <sup>a</sup> TRPH evaluation criterion is to be used only if DRO, VPH-G, benzene, or BTEX do not exceed their respective evaluation criteria.  
<sup>b</sup> EPA, Region 3 RBCs.  
<sup>c</sup> As thallium oxide.  
<sup>d</sup> Value is based upon reference dose for naphthalene.

Key:



ADEC = Alaska Department of Environmental Conservation.  
 BTEX = Benzene, toluene, ethylbenzene, and xylene.  
 DRO = Diesel-range organics.  
 EPA = United States Environmental Protection Agency.  
 mg/kg = Milligrams per kilogram.  
 MSEC = Media-specific evaluation criteria  
 NS = No standard.  
 POLs = Petroleum, oil, and lubricants.  
 RBCs = Risk-based concentrations.  
 TRPH = Total recoverable petroleum hydrocarbons.  
 VPH-G = Volatile petroleum hydrocarbons-gasoline (gasoline-range organics).



Source: Ecology and Environment, Inc. 1994



Source: ALD-ANN-020.000



LEGEND

- Shores
- Sample Locations (ANN94-ES- )



APPROXIMATE SCALE IN FEET  
0 500 1000 2000 3000

Ecology and Environment Inc.	
Figure: 2-2	Proj. No: VR1000
Date: 9/08/94	Drawn by: EGM
Title: ANNETTE ISLAND FAA STATION SEDIMENT BACKGROUND SAMPLE LOCATION MAP	

### **3. VORTAC/DF FACILITY**

This section discusses the ESI and the IC field activities conducted at the VORTAC/DF facility. The location and a brief historical description of the VORTAC/DF and the sites investigated at this facility are discussed in Section 3.1. Section 3.2 discusses the ESI, including details of sampling activities, presentation of the analytical results, risk-based evaluation of contaminants, a geophysical survey, wetlands survey, deviations from the work plan, and conclusions and recommendations.

#### **3.1 LOCATION AND DESCRIPTION**

The VORTAC facility is an active aircraft navigation facility located on 91.82 leased acres approximately 1 mile northeast of the north end of the runway. The DF facility is also active and lies adjacent to the south side of the VORTAC/DF on 0.92 acre (see Figure 3-1). The VORTAC/DF facility has been operated by FAA since 1963.

The VORTAC/DF facility consists of a fenced gravel pad area, which includes the VORTAC Building 413, one active 1,000 gallon diesel UST; a live, high voltage transformer owned by MPL; a storage shed; and the adjoining property where the DF antenna, the VORTAC beacon tower, three tank foundations and piping, a hazardous materials storage building, and an active MPL transformer are located. The VORTAC building is a cinder-block structure built on a concrete foundation, with dimensions of approximately 30- by 30-feet. The roof is flat and covered with a tar and gravel mixture. The building is surrounded by a circular gravel pad that is elevated approximately 10 feet above the surrounding terrain and extends approximately 50 feet radially from the building. A chainlink fence has been constructed around the edge of the pad. An overhead steel antenna (ground plane) extends from the building roof to the fence and covers the gravel pad. A locked gate blocks entrance inside the fence at all times when the building is not occupied.

With the exception of the gravel pad and road, most of the adjoining property is covered by standing water and muskeg. The following structures are located outside of the fenced area: the DF antenna complex consisting of four towers located immediately northwest of the fence; the VORTAC beacon tower; three tank foundations and piping; a hazardous materials storage building; an active MPL transformer; and a gravel service road leading from the north end of the runway to the VORTAC building. A gate crosses the service road approximately 500 feet from the building. The gate is locked at all times when the VORTAC/DF facility is not occupied by authorized personnel.

An ECI conducted in August 1991 (E & E 1992b) identified the presence of lead in soil samples located on the west side of building 413 and beneath the fill port of the 1,000-gallon UST, which exceeded risk-based MSEC. The soil contamination next to building 413 also exceeded MSEC criteria. The lead contamination associated with the UST exceeded evaluation criteria established for petroleum, oil, and lubricants (POL) concerns. Additionally, contaminants in the TAL metal fraction exceeded the 3-times background concentrations. Both of these areas were targeted for further investigation in the ESI as stated in the FAA Statement of Work (SOW) dated September 29, 1993.

### **3.2 EXPANDED SITE INVESTIGATION**

#### **3.2.1 Level II Soil Grid Sampling**

To determine the extent of lead contamination around Building 413, a radial sampling array was developed to cover the gravel pad (see Figure 3-2). A portion of this array was positioned over the area occupied by a former gasoline above-ground storage tank (AGT). The elevated lead and petroleum concentrations found during the ECI were suspected to have been caused by leaded gasoline usage or spillage, leaded paint overspraying, or chipped lead paint. As mentioned previously, the entire gravel pad is covered by a steel antenna structure. Flaking and sandblasted paint from this overhead structure was a likely source of lead found in the soil beneath it.

A minimum of six Level II surface soil samples were collected at intervals of: 0, 5, 10, 25, 47 (at the fenceline), and at 77 feet along each of eight radial lines extending from Building 413 and following the overhead structure of the antenna. Some samples were collected up to approximately 1 foot from the designated radial lines. The samples were analyzed for lead using a field portable XRF. Samples were prepared and analyzed according to the EPA SOP for the Spectrace 9000 field portable XRF (Appendices F.1). Where

elevated lead levels in excess of 500 mg/kg were found, a subsurface soil sample was collected 12-inches beneath the surface soil sample. A contingency was presented in the ESI to collect samples at a deeper 24-inch contour if lead concentrations greater than 500 mg/kg were found following XRF analysis of the 12-inch subsurface samples. None of the samples collected at the 12-inch depth exceeded 500 mg/kg; consequently, collection of the deeper samples was not required. The sample locations and corresponding sample numbers for all surface and subsurface soil samples are shown on Figure 3-2. Table 3-1 summarizes sample identification, matrices, and analyses.

The results of XRF lead analysis for all surface and subsurface sample locations are presented in Figure 3-3. The distribution of lead concentration in surface and subsurface soil was variable throughout the study area and ranged from not detected (ND) to 3,338 mg/kg. Generally, elevated lead concentrations were limited to surface soils except in samples collected around the UST, at the former gasoline AGT, and at the 5-foot interval on radial line 3. Elevated lead levels at the UST and former AGT locations are suspected to be POL-related. Subsurface lead levels at the 5-foot interval on radial line 3 may be due to an isolated spill of unknown material. Concentrations greater than 500 mg/kg were found at various locations inside the fenceline (47-foot contour). Lead levels greater than 1,000 mg/kg were found only on radial lines 1 and 3. Outside of the fenced area, at the 77 foot contour, XRF screening results indicated that lead was generally in the 100 to 500 mg/kg range. Since the elevated lead concentrations in surface soils were suspected to be caused by flaking paint and leaded paint overspraying, the exterior painted walls of VORTAC Building 413 were screened for lead in paint using the Spectrace 9000 XRF. Screening protocol for lead in paint analysis followed the EPA SOP for the Spectrace 9000 field portable XRF, which is presented in Appendix F.2. All four exterior cinderblock walls, painted with white paint that was in good condition, were screened with the XRF. Lead was not detected in the paint on any of the four walls.

Eight Level II surface and subsurface soil samples were also collected around the diesel UST and analyzed for lead and petroleum concentration for comparison to the MSECs. Samples were collected under the fill and vent pipes and on each side of the UST. Subsurface samples were collected at the same location as the surface samples, but at twelve inches below ground surface. XRF lead results ranged from 426 mg/kg to 81 mg/kg. The XRF lead analytical results are presented on Figure 3-3 and in Table 3-2. In addition to XRF, field screening of TRPH was also performed on these samples using the ENSYS Petro RISC test

methods. Samples were prepared and analyzed according to the protocol described in Appendix F.2. The results indicated that TRPH was not detected in any of the surface or subsurface soil samples.

### 3.2.2 Level III POL and Lead Sampling

Ten percent of the total samples collected for screening (Level II) analysis were submitted for Level III confirmation analysis to the analytical laboratory for the following parameters: BTEX, DRO, VPH-G, TRPH, and lead for comparison to MSEC and ADEC POL parameters. A sample summary is presented in Table 3-1. An ADEC POL matrix score and cleanup levels were calculated for the VORTAC/DF facility and are presented in Appendix D.

Four surface soil samples, collected along radial lines 1, 2, 3, and 8, exceeded the 400 mg/kg MSEC criteria for lead. Sample ANN94ESV-SD-414 (1,500 mg/kg) was collected on line 1, position 3; sample ANN94ESV-SD-406 (500 mg/kg) was collected on line 2 position 6; sample ANN94ESV-SD-413 (4,100 mg/kg) was collected on line 3, position 2; and sample ANN94ESV-SD-412 (520 mg/kg) was collected on line 8, position 6.

A statistical correlation was performed between the XRF Level II and TAL Level III lead results. Level III lead concentrations ranged from 14 to 4,100 ppm and were highly correlated with the Level II XRF results. The correlation coefficient was 0.961 indicating that the Level II screening procedure could be used to estimate the total lead concentration obtained using Level III laboratory analysis. A detailed discussion of the correlation of XRF lead to Level III lead values is presented in Section 2.7.4.

Low concentrations of TRPH, DRO, and VPH-G were found in the surface and subsurface soils collected around the UST, at maximum concentrations of 230 mg/kg, 220 mg/kg, and 5.5 mg/kg, respectively. The analytical results are presented in Table 3-3. None of the TRPH, DRO, VPH-G, or BTEX results were found to exceed the ADEC POL cleanup levels calculated on the ADEC matrix scoresheets (Appendix D). In addition, Level III lead concentrations exceeded the 400 mg/kg MSEC for lead for the following UST samples: ANN94ESV-SD-400 (610 mg/kg), ANN94ESV-SD-401 (1,200 mg/kg), ANN94ESV-SD-402 (510 mg/kg), ANN94ESV-SB-400 (580 mg/kg), ANN94ESV-SB-402 (460 mg/kg), and ANN94ESV-SB-403 (440 mg/kg). The results of the Level III lead analysis are presented by location on Figure 3-4 and in Table 3-3.

### 3.2.3 Level IV Source and Target Sampling

Potential source and surface water runoff routes for lead and other contaminants present at the gravel pad source area were assessed. Characterization of the gravel pad source area using Level II and Level III analysis has been previously described. In addition to the XRF field screening samples, Level IV source samples were collected from the area next to Building 413 where CERCLA contamination was identified during the ECI. The potential CERCLA source was characterized by submitting two surface and one shallow subsurface soil samples collected from the west side of Building 413. Surface soil sample ANN94ESV-SD-101 was collected near the northwest corner of the building. Collocated surface (ANN94ESV-SD-100) and subsurface (ANN94ESV-SB-100) soil samples were collected north of the ventilation duct. Due to the presence of a subsurface high-voltage power line, the ANN94ESV-SD-100 location was moved from next to the transformer (as planned in the ECI). The sample locations are presented in Figure 3-4 and Table 3-1. All three samples were submitted for Level IV analysis for TAL metals and Target Compound List (TCL) parameters (see Tables 3-4 and 3-5).

Surface source sample ANN94ESV-SD-100 and ANN94ESV-SD-101 were found to contain concentrations of metals at greater than three times background conditions. Calcium, chromium, copper, lead, magnesium, mercury, nickel, and zinc were found in ANN94ESV-SD-101. Analytical results are presented in Table 3-4. Total lead concentrations for samples ANN94ESV-SD-100 and ANN94ESV-SD-101 were 1,170 mg/kg and 2,260 mg/kg, respectively, which exceeded the MSEC criteria of 400 mg/kg. Zinc (166 mg/kg) was detected in subsurface sample ANN94ESV-SB-100 at concentrations that exceeded three times background or MSEC levels (see Section 3.2.5 for a complete discussion of the background samples). Sample results are presented on Figure 3-5 and in Table 3-4. No other compounds were detected in these samples at concentrations which exceeded three times background concentrations or MSEC levels.

In addition to these source samples, samples ANN94ESV-SD-412, ANN94ESV-SD-413, ANN94ESV-SB-413, ANN94ESV-SD-414, and ANN94ESV-SB-414, which were originally Level III samples, were submitted for reanalysis of Level IV TAL lead only in September 1994. This reanalysis was performed at FAA's request and was performed concurrently with a TCLP metals analysis (see Section 3.2.5). Samples ANN94ESV-SD-413 (6,020 mg/kg), ANN94ESV-SB-413 (467 mg/kg), and ANN94ESV-SD-414 (1,420 mg/kg)

exceeded the lead MSEC of 400 mg/kg. All of these samples exceeded three times background concentrations for lead. Results are presented in Table 3-4 and Figure 3-5.

The wetland adjacent to the VORTAC/DF facility was evaluated and met the criteria of a target wetland according to the HRS model. Two separate surface water pathways were identified at the VORTAC/DF extending northeast and southeast of the facility (see Section 3.2.7 for a complete discussion of the pathways). Sediment samples were collected at the probable point of entry into the wetland and at approximately 0.1 mile and 0.2 mile downgradient of the probable point of entry and gravel pad along each drainage pathway. The southeast pathway extended to Tamgass Harbor where a beach sample was collected at the beach at the end of the drainage. The beach sample was collected from a surface beach area at the mean tide line. Table 3-1 summarizes sample identification, matrix, analytical parameters, and sample descriptions. Sample locations are presented in Figure 3-6.

Six target samples were submitted for Level IV analysis of TAL metals and TCL parameters. Lead was found at concentrations greater than three times background at the probable point of entry to both drainage pathways (stream sediment ANN94ESV-SE-100, 10.9 mg/kg and peat sediment ANN94ESV-SE-103, 18.0 mg/kg). Calcium (4,650 mg/kg) and diethylphthalate (2,300 µg/kg) were found at greater than three times background in sample ANN94ESV-SE-100. Calcium and lead were also found in source samples at elevated concentrations. Diethylphthalate was not detected in source sample. The source of this compound is unknown.

Stream sediment ANN94ESV-SE-102, collected 0.2 mile downgradient of the VORTAC/DF facility in the northeast drainage, was found to contain aluminum and barium at 11,200 mg/kg and 29.6 mg/kg, respectively. These concentrations were greater than three times background stream sediment conditions. Aluminum and barium were found to be present in source samples and in ANN94ESV-SE-101, collected 0.1 mile downgradient, but not at concentrations that exceeded three times background. Therefore, it does not appear the VORTAC/DF facility is the source of these compounds.

Beach sediment ANN94ESV-SE-106 was collected at Tamgass Harbor along the southeast surface water pathway. Arsenic (4.8 mg/kg), chromium (37.5 mg/kg), cobalt (21.5 mg/kg), iron (21,500 mg/kg), magnesium (44,400 mg/kg), manganese (266 mg/kg), nickel (151 mg/kg), sodium (1,380 mg/kg), vanadium (16.8 mg/kg), and zinc (88.6 mg/kg) were all found to exceed three times background beach sediment conditions. Most of these elements were found in source samples at greater than three times background conditions. However,



elemental concentrations found in sediment samples ANN94ESV-SE-103, ANN94ESV-SE-104, and ANN94ESV-SE-105, collected upgradient of ANN94ESV-SE-106, were not detected or were at lower concentrations than those found in the beach sample. Therefore, it does not appear that the VORTAC/DF facility is the source of these contaminants at the beach.

#### **3.2.4 Background Samples**

Background samples were collected for each distinct sample matrix sampled. The matrices encountered at the VORTAC/DF facility included soil/gravel, sandy stream sediment, peaty sediment, and beach sand. The background sample locations were selected in upgradient areas as far removed from potential contaminant sources as practicable. The soil/gravel background sample ANN94ESB-SD-101 was collected near the NDB/H-marker facility as shown in Figure 2-1. All other background sample locations are shown in Figure 2-2. Sample designations are as follows: sandy stream sediment, ANN94ESB-SE-101; peaty sediment, ANN94ESB-SE-102; and beach sand sediment, ANN94ESB-SE-100. The background samples were analyzed for all TAL metals and TCL parameters. The results of the analysis are presented in Table 2-4 for TAL metals and Table 2-3 for TCL organic analytes. Background sample results are discussed in further detail in Section 2.7.1.

#### **3.2.5 Level IV TCLP Sampling**

Source samples ANN94ESV-SD-100, ANN94ESV-SD-101, and ANN94ESV-SB-100 were also submitted for Level IV TCLP metals analysis. Samples ANN94ESV-SB-412, ANN94ESV-SD-413, ANN94ESV-SB-413, ANN94ESV-SD-414, and ANN94ESV-SB-414 were submitted for Level IV TCLP lead only analysis in September 1994 after the field work was completed and at the request of FAA. These results are presented in Table 3-6 and in Figure 3-5. Samples ANN94ESV-SD-412, ANN94ESV-SD-413, ANN94ESV-SB-413, ANN94ESV-SD-414, and ANN94ESV-SB-414 were also submitted for reanalysis for Level IV TAL lead concurrent with the TCLP analysis for comparison purposes. Results are presented on Figure 3-5 and on Table 3-4. TCLP analysis indicated that only lead exceeded regulatory limits (5.0 milligrams per liter [mg/l]). The exceedance occurred in four surface soil samples ANN94ESV-SD-100 (5.7 mg/l), ANN94ESV-SD-101 (11.1 mg/l), ANN94ESV-SD-413 (65.2 mg/l), ANN94ESV-SD-414 (8.1 mg/kg), and in one subsurface samples ANN94ESV-SB-413 (5.2 mg/l). A comparison of Level IV total lead to TCLP lead in the source samples is as follows: ANN94ESV-SD-100, total 1,170 mg/kg, TCLP 5.7 mg/L;

ANN94ESV-SD-101, total 2,260 mg/kg, TCLP 11.1 mg/L; ANN94ESV-SB-100, total 0.6 mg/kg, TCLP 0.87 mg/L; ANN94ESV-SD-412, total 349 mg/kg, TCLP not detected; ANN94ESV-SD-413, total 6,020 mg/kg, TCLP 65.2 mg/l; ANN94ESV-SB-413, total 467 mg/kg, TCLP 5.2 mg/l; ANN94ESV-SD-414, total 1,420 mg/kg, TCLP 8.1 mg/l; and ANN94ESV-SB-414, total 69.3 mg/kg, TCLP 0.28 mg/l. TCLP lead concentrations are presented on Figure 3-5.

### 3.2.6 Wetlands Survey

At the VORTAC/DF facility, a wetland complex was identified immediately surrounding the gravel pad source area. The VORTAC/DF sits on a circular gravel pad. The wetland complex began near the base of the gravel pad and extended in all directions more than 0.2 mile downgradient of the gravel pad source. This complex was dominated by a shore pine-Yellow cedar muskeg with interspersed open water wetlands. The sloping sides of the gravel pad were covered with a thin layer of organic material. Upland species (white clover [*Trifolium repens*], dandelion [*Taraxacum officinale*], yarrow [*Achillea millefolium*], fireweed [*Epilobium anagrostifolium*], thimbleberry [*Rubus parviflorus*], common horsetail [*Equisetum arvense*], dwarf dogwood [*Cornus canadensis*], salmonberry, evergreen huckleberry [*Vaccinium ovatum*], dominated the sloping sides of the gravel pad and were mixed with hydrophytic vegetation near the base of the pad. Since the VORTAC/DF sits on a flat circular pad, overland runoff could occur in any direction. Two drainage pathways were selected to be sampled based on their proximity to the gravel pad source. The northwest and southeast surface water paths are shown in Figure 3-6.

The northwest surface water pathway began at the base of the pad immediately downgradient of Radial Line 1 at the VORTAC and extended in a northwesterly direction. ANN94ESV-SE-100 was collected near the base of the pad. No tree stratum existed at this location. Sweet gale, labrador tea, yellow cedar, shore pine, and evergreen huckleberry comprised the sapling/shrub layer. The herbaceous layer contained numerous grass species, deer cabbage, common juniper, dwarf dogwood, sitka burnet (*Sanguisorba canadensis*), fireweed, common horsetail, and sphagnum moss. The soil was composed of peat and was saturated at 6 inches BGS.

The northwest surface water pathway crossed the road near the road adjacent to the towers at the VORTAC/DF and entered an open water wetland vegetated with buckbean, sedges, and reeds. The land gently sloped northwestward from the open water wetland.

ANN94ESV-SE-101 was collected where the land plateaus. No tree stratum existed at this location. The shrub/sapling layer was composed of shore pine and labrador tea. Deer cabbage, bog laurel, jeffrey shooting star, crowberry, sitka burnet, common juniper, sphagnum moss, and numerous grass species dominated the herbaceous layer. The soil consisted of 4 inches of peaty muck overlaying a cobble layer and was saturated at the surface. Pockets of standing water were intermingled with this muskeg wetland.

The northwest surface water pathway followed the slope of the hill. Downgradient of the previous sampling point, the angle of the slope increased and channels became more prevalent. ANN94ESV-SE-102 was collected in a channel. The vegetation was consistent with that found at the previous sampling point. The channel substrate consisted of 12 inches of peaty muck overlying rock. The channel banks consisted of 4 to 6 inches of peat over rock.

The southeast surface water pathway began at the base of the gravel pad of the VORTAC immediately downgradient of Radial Line 3. This drainage pathway initially headed southeast for approximately 100 feet and then followed an easterly direction towards Tamgass Harbor. ANN94ESV-SE-103 was collected near the base of the pad in an apparent dry drainage channel. No tree stratum existed at this location. The shrub/sapling layer consisted of sweet gale, yellow cedar, shore pine, and labrador tea. Deer cabbage, sitka burnet, dwarf dogwood, crowberry, bog laurel, and sphagnum moss comprised the herbaceous layer. The soil consisted of an organic peat mixed with silty sand.

The southeast surface water pathway continued down the slope of the hill in an easterly direction. Channels developed where the angle of the slope increased and disappeared as the land leveled. Open water wetland were more prevalent in the flatter area. ANN94ESV-SE-104 was collected in a drainage channel approximately 0.1 mile downgradient of the gravel pad source and immediately downgradient of two large open water wetlands. No tree stratum existed at this location. Shore pine, sweet gale, and labrador tea dominated the shrub/shrub layer. Deer cabbage, common juniper, and jeffrey shooting star were the dominant vegetation in the herbaceous layer. Buckbean and grasses were the dominant vegetation in the channel itself. The sampling location was inundated. The channel substrate consisted of 12 inches of muck, contained some sand and silt, underlain by an impermeable layer. The adjacent bank consisted of at least 18 inches of peat.

ANN94ESV-SE-105 was collected approximately 0.2 mile downgradient of the source along the southeastern drainage pathway. The surrounding vegetation consisted of shore pine,

sweet gale, and labrador tea in the shrub/sapling layer; and common juniper, sitka burnet, deer cabbage, and grasses in the herbaceous layer. Buckbean was the dominant plant in the open water wetland. The soil in the open water wetland consisted of 8 inches of peaty muck over a hard pan. The surrounding soil was saturated to the surface and consisted of a mucky peat and sphagnum moss. The soil consisted of four inches of saturated peaty muck overlying a rock or gravel. Open water areas contained buckbean and several grass and sedge species and consisted of a muck substrate overlying gravel.

The area surrounding the VORTAC/DF had extensive drainage patterns. Channels occurred on sloped terrain and subsequently disappeared into marshes or open water areas. The predominant drainage was towards the east and drained into Tamgass Harbor, south of Tent Point. A beach sample (ANN94ESV-SE-106), consisting of sand and gravel, was collected between the low and high tide marks within the channel identified as the primary surface flow from the drainage. No vegetation was observed growing on the beach.

### **3.2.7 Site-Specific Remedial Goals**

As discussed previously in Section 2.8, MSECs were developed to screen the analytical results and to identify contaminants and areas that could have the potential to pose a significant risk of adverse human health effects. Lead was the only contaminant with a range of concentration in soil at the VORTAC/DF that exceeded the conservative MSECs, therefore it was the only one requiring a site-specific remedial goal. EPA has been unable to derive a verifiable reference dose or slope factor from the available toxicity data for lead, partly because of a lack of empirical evidence for a threshold for many of lead's noncarcinogenic effects. Consequently, lead exposures are usually assessed using EPA's Integrated Exposure Uptake Biokinetic Model (IEUBK), which integrates exposure and biokinetic factors to predict the distribution of blood lead levels as a function of lead concentration in soil, dust, water, food, and air. The projected distribution is then compared to a target distribution that is expected to be adequately protective for the receptors under consideration, usually young children. The degree of exposure to these media and the extent of lead uptake from the media are considerably greater for young children than for adults. The factors used in the model would be appropriate for young children residing in the exposure area, but would substantially overestimate blood levels for adults. For this reason, the new soil screening level of 400 mg/kg recommended in EPA's OSWER directive 9355.4-12 (EPA 1994) was used as a

starting point for developing a site-specific remedial goal for lead, but was adjusted to consider the population and environmental conditions at Annette Island.

The potentially exposed population consists of on-site workers and residents living on Annette Island. Information provided in the ECIR (E & E 1992b) indicated that the worker population consisted of 4 people who work periodically at each of the operating FAA facilities, the VORTAC/DF, NDB/H-marker, and RCAG. The typical work schedule involves maintenance personnel visiting each facility once per month and on an as needed basis. It is estimated that the FAA workers spend less than 5% of their monthly work shift at the Annette Island facilities.

Residents living on the island consist of the people living in Metlakatla (630), which is located approximately 5 miles north of the FAA Station, and those living near the FAA facilities. It was estimated in the ECIR that 61 people live or work within 1 to 2 miles of the VORTAC/DF facility. The population living nearest to the FAA station were at the Weather Bureau Housing (WBH) area, located between the NDB/H-marker and RCAG facilities (see Figure 2-1). At the time of the ECI, 15 people, including adults and children, were living in the WBH area.

Although children live on Annette Island, primarily in Metlakatla and the WBH area, exposure to contaminated soil at the VORTAC/DF facility is unlikely due to the remoteness, inaccessibility and secure nature of the facility. The VORTAC/DF facility is located approximately 1 mile from the WBH area and 5 miles from Metlakatla. In addition, as mentioned in Section 3.1, access to the gravel pad where elevated lead concentrations were found has been restricted: first by a locked gate on the access road and second by a secured fence that surrounds the top of the gravel pad, where most of the lead contamination was found.

Although the IEUBK model is not directly relevant to adults or the potential exposure situation on Annette Island, it does provide a starting point for qualitative assessment of potential lead exposure. The first consideration is that the 400 mg/kg soil screening level based on the IEUBK model is explicitly an average concentration for a potential exposure area. The average lead concentration at the VORTAC/DF was calculated based on both level II screening and Level III confirmation data. The Level II samples were collected on a grid that characterized the entire source area, and as such were probably more representative of the area. A subset of these samples, which represented soil in the overland surface water pathway, were selected and submitted for Level III confirmation analysis. The average surface lead concentration at the VORTAC/DF facility was 733 mg/kg, based on Level III

analysis. The Level II results were consistently lower than, but highly correlated ( $r = 0.96$ ) to, the corresponding Level III values. The average Level II concentration was 444 mg/kg, which correlates to a 636 mg/kg Level III average (see Section 2.7.4.1 for a discussion of the correlation).

The 400 mg/kg screening level is considered adequately protective for continuous exposure of young children to soils in a residential setting. The potential exposure situation for workers in the VORTAC/DF facility area differ in two important ways from the situation for which the screening level was intended. First, based on their work schedules, it is likely that less than 25% of the workers total soil contact is to contaminated soil in the VORTAC/DF area. This differs from the 100% contact with contaminated soils assumed in the IEUBK model. Second, the potentially exposed individuals are adults rather than children. A recent study by Bowers, *et al.* (1994) involving adult workers occupationally exposed to lead in Butte, Montana, and Midvale, Utah, indicates that uptake of lead from soil is less than one-third as great in adults as in young children. This means that adults can tolerate soil lead levels three times higher than young children and still have the same blood lead levels. Taken together, these two factors suggest that a soil lead level as much as 60 times higher than 400 mg/kg could be adequately protective for the FAA employees who maintain the VORTAC/DF facility. In contrast, the actual average lead concentration measured in the VORTAC/DF area was less than two times higher than the 400 mg/kg screening level.

The foregoing description of the VORTAC/DF area and the potential for human exposures to soils in that area that might reasonably be expected to indicate that the existing soil lead levels would not result in any adverse health effects, and that there is already a considerable margin of safety. Therefore, no site-specific remedial goal is needed for lead for the VORTAC/DF facility area on Annette Island.

Given the nature of the potentially exposed population and the degree of exposure that might reasonably be expected to occur at the VORTAC/DF, the lead MSEC, based on the standard EPA Region 3 RBC for residential soil, was adjusted upward by a factor of 4 to 1,600 mg/kg. This adjustment assumes that the exposed population, either children or workers, would spend at least 1/4 of their time in contact with the contaminated soil. Realistically, exposure at the VORTAC/DF would probably be less than 25 % due to the remoteness and inaccessibility of the facility. Although this assumption of exposure frequency is overly protective for the VORTAC/DF, it was chosen to provide a margin of safety at all

FAA facilities located on Annette Island. The average lead soil concentration at the VORTAC/DF did not exceed 1,600 mg/kg; consequently, the existing lead concentrations found in the soils at the VORTAC/DF facility on Annette Island do not appear to pose a significant risk of adverse health effects.

### **3.2.8 Deviations From the Work Plan**

All work at the VORTAC/DF facility was performed as specified in the ESI work plan except that an additional surface water runoff pathway was identified that required the collection of three additional sediment samples and one additional beach sample to characterize the pathway. The two pathways were discussed in Section 3.2.1.3. All deviations from the work plan were authorized by the Contracting Officer (CO).

### **3.2.9 Conclusions and Recommendations**

The issues of concern at the VORTAC/DF were the presence of contamination in soil, the exceedance of regulatory criteria and the potential for exposure to the contamination. The results of the investigation are summarized as follows:

- Lead contamination found in surface soil in the gravel pad source area had a range of concentration that exceeded the MSEC. TCLP analysis indicated that the lead in these samples also exceeded the 5 mg/l regulatory criteria. Approximately 300 cubic yards of soil are potentially affected assuming contaminants are in the top six inches of soil across the gravel pad. Further action is recommended to address the lead contamination at the VORTAC/DF facility.
- An assessment of the potential exposure to the lead contamination indicated that it did not pose a significant risk of adverse health effects.

<p><b>Table 3-1</b></p> <p><b>EXPANDED SITE INVESTIGATION SAMPLE SUMMARY</b></p> <p><b>VORTAC FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p>				
Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESV-SD-100	Soil	BNA, TAL metals, TCLP metals, VOC, Pest/PCB	ASC/Level IV	Source sample; collected on west side of Building 413.
ESV-SB-100	Soil	BNA, Pest/PCB, TAL metals, TCLP metals, VOC	ASC/Level IV	Source sample; collected at same location as SD-100 at 1 foot BGS.
ESV-SD-101	Soil	BNA, Pest/PCB, TAL metals, TCLP metals, VOC	ASC/Level IV	Source sample; collected on west side of Building 413.
ESV-SE-100	Stream sediment	BNA, Pest/PCB, TAL metals, VOC	ASC/Level IV	Northeast drainage. Entrance to wetland.
ESV-SE-101	Stream sediment	BNA, Pest/PCB TAL metals, VOC	ASC/Level IV	Northeast drainage. Wetland 0.1 mile downstream of VORTAC.
ESV-SE-102	Stream sediment	BNA, Pest/PCB TAL metals, VOC	ASC/Level IV	Northeast drainage. Wetland 0.2 mile downstream of VORTAC.
ESV-SE-103	Peat sediment	BNA, Pest/PCB TAL metals, VOC	ASC/Level IV	Southwest drainage. Entrance to wetland.
ESV-SE-104	Stream sediment	BNA, Pest/PCB TAL metals, VOC	ASC/Level IV	Southwest drainage. Wetland 0.1 mile downstream of VORTAC.
ESV-SE-105	Stream sediment	BNA, Pest/PCB TAL metals, VOC	ASC/Level IV	Southwest drainage. Wetland 0.2 mile downstream of VORTAC.
ESV-SE-106	Beach sediment	BNA, Pest/PCB TAL metals, VOC	ASC/Level IV	Beach at end of drainage.
ESV-SD-200	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.

Key at end of table.



<p><b>Table 3-1</b></p> <p><b>EXPANDED SITE INVESTIGATION SAMPLE SUMMARY</b></p> <p><b>VORTAC FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p>				
Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESV-SB-200	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-201	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SB-209	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-210	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SB-210	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-232	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-224	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-250	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-203	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SB-201	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-204	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-205	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SB-211	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-233	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-225	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.

Key at end of table.

Table 3-1

**EXPANDED SITE INVESTIGATION SAMPLE SUMMARY  
VORTAC FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA**

Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESV-SD-251	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-206	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SB-203	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-207	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SB-212	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location.
ESV-SD-208	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-234	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-234	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-226	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-226	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-252	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-209	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-204	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-210	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-213	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location

Key at end of table.

recycled paper

3-17

ecology and environment

<p><b>Table 3-1</b></p> <p><b>EXPANDED SITE INVESTIGATION SAMPLE SUMMARY</b></p> <p><b>VORTAC FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p>				
Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESV-SD-211	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-214	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-235	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-235	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-227	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-253	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-212	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-205	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-213	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-214	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-215	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-236	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-236	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-228	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-254	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location

Key at end of table.

<p><b>Table 3-1</b></p> <p><b>EXPANDED SITE INVESTIGATION SAMPLE SUMMARY</b></p> <p><b>VORTAC FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p>				
Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESV-SD-215	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-206	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-216	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-217	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-237	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-237	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-229	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-255	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-218	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-207	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-219	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-220	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-238	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-230	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-256	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location

Key at end of table.

recycled paper

3-19

ecology and environment

<p><b>Table 3-1</b></p> <p><b>EXPANDED SITE INVESTIGATION SAMPLE SUMMARY</b></p> <p><b>VORTAC FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p>				
Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESV-SD-221	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-208	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-222	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-223	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-239	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SB-239	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-231	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-257	Soil	XRF metals	Field/Level II	See Figure 3-2 for grid location
ESV-SD-240	Soil	XRF metals, TRPH	Field/Level II	Fill pipe at UST
ESV-SB-240	Soil	XRF metals, TRPH	Field/Level II	Fill pipe at UST, 1 foot BGS
ESV-SD-241	Soil	XRF metals, TRPH	Field/Level II	South side of UST
ESV-SB-241	Soil	XRF metals, TRPH	Field/Level II	South side of UST, 1 foot BGS
ESV-SD-242	Soil	XRF metals, TRPH	Field/Level II	Vent pipe at UST
ESV-SB-242	Soil	XRF metals, TRPH	Field/Level II	Vent pipe at UST, 1 foot BGS
ESV-SD-243	Soil	XRF metals, TRPH	Field/Level II	North side of UST

Key at end of table.

<p align="center"><b>Table 3-1</b></p> <p align="center"><b>EXPANDED SITE INVESTIGATION SAMPLE SUMMARY</b></p> <p align="center"><b>VORTAC FACILITY</b></p> <p align="center"><b>ANNETTE ISLAND FAA STATION</b></p> <p align="center"><b>ANNETTE ISLAND, ALASKA</b></p>				
Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESV-SB-243	Soil	XRF metals, TRPH	Field/Level II	North side of UST, 1 foot BGS
ESV-SD-400	Soil	Total lead, TRPH, DRO, VPH-G, BTEX	Field/Level II	Same location as ESV-SD-240
ESV-SB-400	Soil	Total lead, TRPH, DRO, VPH-G, BTEX	ASC/Level III	Same location as ESV-SB-240
ESV-SD-401	Soil	Total lead, TRPH, DRO, VPH-G, BTEX	ASC/Level III	Same location as ESV-SD-241
ESV-SB-401	Soil	Total lead, TRPH, DRO, VPH-G, BTEX	ASC/Level III	Same location as ESV-SB-241
ESV-SD-402	Soil	Total lead, TRPH, DRO, VPH-G, BTEX	ASC/Level III	Same location as ESV-SD-242
ESV-SB-402	Soil	Total lead, TRPH, DRO, VPH-G, BTEX	ASC/Level III	Same location as ESV-SB-242
ESV-SD-403	Soil	Total lead, TRPH, DRO, VPH-G, BTEX	ASC/Level III	Same location as ESV-SD-243
ESV-SB-403	Soil	Total lead, TRPH, DRO, VPH-G, BTEX	ASC/Level III	Same location as ESV-SB-243
ESV-SD-414	Soil	Total lead, TCLP lead, TAL lead	ASC/Level III,IV	Line 1, 10 feet, surface sample.
ESV-SB-414	Soil	Total lead, TCLP lead, TAL lead	ASC/Level III,IV	Line 1, 10 feet, subsurface sample 1 foot BGS.
ESV-SD-405	Soil	Total lead	ASC Level III	Line 1, 77 feet, surface sample.
ESV-SD-406	Soil	Total lead	ASC Level III	Line 2, 77 feet, surface sample.
ESV-SD-413	Soil	Total lead, TCLP lead, TAL lead	ASC Level III, IV	Line 3, 5 feet, surface sample.
ESV-SB-413	Soil	Total lead, TCLP lead, TAL lead	ASC Level III, IV	Line 3, 5 feet, subsurface sample 1 foot BGS.

Key at end of table.

Table 3-1

**EXPANDED SITE INVESTIGATION SAMPLE SUMMARY  
VORTAC FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA**

Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESV-SD-404	Soil	Total lead	ASC Level III	Line 3, 47 feet, surface sample.
ESV-SB-404	Soil	Total lead	ASC Level III	Line 3, 47 feet, subsurface sample 1 foot BGS.
ESV-SD-407	Soil	Total lead	ASC Level III	Line 3, 77 feet, surface sample.
ESV-SD-408	Soil	Total lead	ASC/Level III	Line 4, 77 feet, surface
ESV-SD-409	Soil	Total lead	ASC/Level III	Line 5, 77 feet, surface
ESV-SD-410	Soil	Total lead	ASC/Level III	Line 6, 77 feet, surface
ESV-SD-411	Soil	Total lead	ASC/Level III	Line 7, 77 feet, surface
ESV-SD-412	Soil	Total lead, TCLP lead, TAL lead	ASC/Level III, IV	Line 8, 77 feet, surface

**Key:**

- ASC = Analytical Service Center.
- BGS = Below ground surface.
- BNA = Base neutral/acid extractable compounds.
- BTEX = Benzene, toluene, ethylbenzene, and xylene.
- DRO = Diesel-range organics.
- Pest/PCB = Organochlorine pesticides/polychlorinated biphenyls.
- TAL metals = Target Analyte List metals.
- TCLP = Toxicity Characteristic Leaching Procedure.
- TRPH = Total recoverable petroleum hydrocarbons.
- VOC = Volatile organic compounds.
- VPH-G = Volatile petroleum hydrocarbons as gasoline.

Table 3-2

**EXPANDED SITE INVESTIGATION LEVEL II SOIL SAMPLES  
XRF METALS RESULTS (mg/kg)  
VORTAC FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA  
JUNE 1994**

RADIAL LINE 1  Sample ID (ANN94)-  Distance: Depth BGS:	Grid Point 1		Grid Point 2		Grid Point 3		Grid Point 4	Grid Point 5	Grid Point 6
	ESV-SD-200  0 Feet 0 Inches	ESV-SB-200  0 Feet 12 Inches	ESV-SD-201  5 Feet 0 Inches	ESV-SB-209  5 Feet 12 Inches	ESV-SD-202  10 Feet 0 Inches	ESV-SB-210  10 Feet 12 Inches	ESV-SD-232  36 Feet 0 inches	ESV-SD-224 at Fence 46 Feet 0 Inches	ESV-SD-250  77 Feet 0 Inches
Chromium	830	357	730	509	843	356	755	623	231
Manganese	1,252	594	1,042	756	1,085	696	1,266	905	409 U
Iron	44,234	25,604	37,821	29,267	45,578	25,990	53,389	30,948	8,405
Cobalt	472	236	544	304	504	174 U	587	473	174 U
Nickel	757	222	605	303	805	245	952	446	26 U
Copper	242	49 U	143	49 U	79	49 U	54	49 U	49 U
Zinc	386	91	335	69	409	64	200	3,174	70
Arsenic	75 U	33 U	68 U	33 U	121 U	33 U	33 U	35 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	2 U	3	3	2 U	2 U	2 U	2 U	2 U	2 U
Mercury	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U
Lead	746	261	678	48	1,208	43	204	348	98

Key at end of table.



recycled paper

3-23

ecology and environment

<p><b>Table 3-2</b></p> <p><b>EXPANDED SITE INVESTIGATION LEVEL II SOIL SAMPLES</b></p> <p><b>XRF METALS RESULTS (mg/kg)</b></p> <p><b>VORTAC FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>JUNE 1994</b></p>								
<b>RADIAL LINE 2</b>  <b>Sample ID (ANN94)-</b>  <b>Distance:</b> <b>Depth BGS:</b>	Grid Point 1		Grid Point 2	Grid Point 3		Grid Point 4	Grid Point 5	Grid Point 6
	ESV-SD-203	ESV-SB-201	ESV-SD-204	ESV-SD-205	ESV-SB-211	ESV-SD-233	ESV-SD-225 Fence	ESV-SD-251
	0 Feet 0 Inches	0 Feet 12 Inches	5 Feet 0 Inches	10 Feet 0 Inches	10 Feet 12 Inches	29 Feet 0 Inches	49 Feet 0 Inches	77 Feet 0 Inches
Chromium	883	269	751	627	312	615	787	182
Manganese	966	521	1,145	1,126	569	885	1,024	1,140
Iron	38,601	22,442	41,524	45,784	25,415	40,397	42,994	10,033
Cobalt	481	283	502	477	174 U	512	604	174 U
Nickel	594	176	732	788	138	684	773	89
Copper	49 U	49 U	49 U	49 U	49 U	49 U	49 U	49 U
Zinc	89	71	228	245	30 U	186	214	40
Arsenic	33 U	33 U	45 U	50 U	33 U	41 U	40 U	37 U
Selenium	16 U	16 U	16 U	16 U	20	16 U	16 U	16 U
Molybdenum	2 U	3	2 U	2 U	2 U	2 U	2 U	2 U
Mercury	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U
Lead	24	33	453	501	14 U	409	403	373

Key at end of table.

Table 3-2

**EXPANDED SITE INVESTIGATION LEVEL II SOIL SAMPLES  
XRF METALS RESULTS (mg/kg)  
VORTAC FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA  
JUNE 1994**

RADIAL LINE 3  Sample ID (ANN94)-  Distance: Depth BGS:	Grid Point 1		Grid Point 2		Grid Point 3	Grid Point 4		Grid Point 5		Grid Point 6
	ESV-SD-206	ESV-SB-203	ESV-SD-207	ESV-SB-212	ESV-SD-208	ESV-SD-234	ESV-SB-234	ESV-SD-226 Fence	ESV-SB-226 Fence	ESV-SD-252
	0 Feet 0 Inches	0 Feet 12 Inches	5 Feet 0 Inches	5 Feet 12 Inches	10 Feet 0 Inches	30 Feet 0 Inches	30 Feet 12 Inches	48 Feet 0 Inches	48 Feet 12 Inches	77 Feet 0 Inches
Chromium	346	178 U	360	286	324	733	365	495	178 U	178 U
Manganese	1,054	486	607	409 U	709	1,080	620	946	483	433
Iron	32,487	19,291	26,925	14,815	33,106	42,370	22,317	34,742	25,345	20,296
Cobalt	318	293	270	200	356	580	174 U	459	330	174 U
Nickel	372	122	295	132	543	746	76	602	230	26 U
Copper	49 U	49 U	49 U	49 U	49 U	49 U	49 U	49 U	49 U	49 U
Zinc	189	50	1,138	97	190	194	65	1,397	320	50
Arsenic	50 U	33 U	334 U	33 U	40 U	84 U	33 U	52 U	33 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2 U
Mercury	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U
Lead	501	25	3,338	213	401	845	18	519	96	107

Key at end of table.

recycled paper

Table 3-2

**EXPANDED SITE INVESTIGATION LEVEL II SOIL SAMPLES  
XRF METALS RESULTS (mg/kg)  
VORTAC FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA  
JUNE 1994**

RADIAL LINE 4 Sample ID (ANN94)- Distance: Depth BGS:	Grid Point 1		Grid Point 2		Grid Point 3		Grid Point 4		Grid Point 5	Grid Point 6
	ESV-SD-209 0 Feet 0 Inches	ESV-SB-204 0 Feet 12 Inches	ESV-SD-210 5 Feet 0 Inches	ESV-SB-213 5 Feet 12 Inches	ESV-SD-211 10 Feet 0 Inches	ESV-SB-214 10 Feet 12 Inches	ESV-SD-235 30 Feet 0 Inches	ESV-SB-235 30 Feet 12 Inches	ESV-SD-227 Fence 39 Feet 0 Inches	ESV-SD-253 77 Feet 0 Inches
Chromium	781	357	795	282	854	336	683	365	475	178 U
Manganese	1,520	409 U	1,237	509	912	455	1,261	889	1,009	409 U
Iron	91,844	17,334	49,693	26,810	44,847	23,046	46,245	29,316	40,065	14,883
Cobalt	754	211	440	354	323	245	609	274	498	174 U
Nickel	970	129	808	304	853	318	695	292	591	79
Copper	286	49 U	49 U	49 U	49 U	49 U	49 U	49 U	49 U	49 U
Zinc	817	36	250	56	229	35	232	101	3,824	30 U
Arsenic	33 U	33 U	70 U	33 U	60 U	33 U	69 U	34	42 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	19 U	16 U	16 U	16 U	16 U
Molybdenum	2 U	2 U	3	3	2 U	2 U	2 U	4	2 U	31
Mercury	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U
Lead	235	14 U	704	72	595	40	688	37	422	14 U

Key at end of table.

ecology and environment

Table 3-2

**EXPANDED SITE INVESTIGATION LEVEL II SOIL SAMPLES  
XRF METALS RESULTS (mg/kg)  
VORTAC FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA  
JUNE 1994**

RADIAL LINE 5  Sample ID (ANN94)-  Distance: Depth BGS:	Grid Point 1		Grid Point 2	Grid Point 3		Grid Point 4		Grid Point 5	Grid Point 6
	ESV-SD-212	ESV-SB-205	ESV-SD-213	ESV-SD-214	ESV-SB-215	ESV-SD-236	ESV-SB-236	ESV-SD-228 Fence	ESV-SD-254
	0 Feet 0 Inches	0 Feet 12 Inches	5 Feet 0 Inches	10 Feet 0 Inches	10 Feet 12 Inches	31 Feet 0 Inches	31 Feet 12 Inches	49 Feet 0 Inches	77 Feet 0 Inches
Chromium	686	300	248	814	394	799	179	933	178 U
Manganese	1,004	580	409 U	1,066	663	1,064	654	1,193	418
Iron	46,026	21,702	19,204	44,507	26,466	45,278	21,076	50,115	14,731
Cobalt	639	276	322	450	344	576	262	546	203
Nickel	775	155	162	812	292	727	136	878	33
Copper	51	49 U	49 U	49 U	49 U	49 U	49 U	49 U	49 U
Zinc	231	80	62	189	111	214	51	1,147	30 U
Arsenic	41 U	33 U	33 U	52 U	33 U	79 U	33 U	33 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	2 U	2 U	2 U	2 U	2 U	2 U	3	2 U	2 U
Mercury	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U
Lead	414	83	158	518	241	792	36	267	19

Key at end of table.

recycled paper

3-27

ecology and environment

<p><b>Table 3-2</b></p> <p><b>EXPANDED SITE INVESTIGATION LEVEL II SOIL SAMPLES</b></p> <p><b>XRF METALS RESULTS (mg/kg)</b></p> <p><b>VORTAC FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>JUNE 1994</b></p>								
<b>RADIAL LINE 6</b>	<b>Grid Point 1</b>		<b>Grid Point 2</b>	<b>Grid Point 3</b>	<b>Grid Point 4</b>		<b>Grid Point 5</b>	<b>Grid Point 6</b>
<b>Sample ID (ANN94)-</b>	<b>ESV-SD-215</b>	<b>ESV-SB-206</b>	<b>ESV-SD-216</b>	<b>ESV-SD-217</b>	<b>ESV-SD-237</b>	<b>ESV-SB-237</b>	<b>ESV-SD-229</b>	<b>ESV-SD-255</b>
<b>Distance: Depth BGS:</b>	<b>0 Feet 0 inches</b>	<b>0 Feet 12 Inches</b>	<b>5 Feet 0 Inches</b>	<b>10 Feet 0 Inches</b>	<b>31 Feet 0 Inches</b>	<b>31 Feet 12 Inches</b>	<b>Fence 49 Feet 0 Inches</b>	<b>77 Feet 0 Inches</b>
Chromium	287	475	511	584	880	178 U	178 U	178 U
Manganese	692	736	816	1,087	1,084	681	542	529
Iron	31,525	28,756	35,963	43,691	45,467	25,359	19,287	12,971
Cobalt	364	318	305	355	588	366	240	174 U
Nickel	377	349	602	880	778	170	232	26 U
Copper	82	49 U	49 U	49 U	49 U	49 U	49 U	49 U
Zinc	486	100	102	91	174	52	1,102	30 U
Arsenic	51 U	33 U	37 U	33 U	54 U	33 U	33 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2 U
Mercury	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U
Lead	515	119	370	307	544	37	136	265

Key at end of table.

<p align="center"><b>Table 3-2</b></p> <p align="center"><b>EXPANDED SITE INVESTIGATION LEVEL II SOIL SAMPLES</b></p> <p align="center"><b>XRF METALS RESULTS (mg/kg)</b></p> <p align="center"><b>VORTAC FACILITY</b></p> <p align="center"><b>ANNETTE ISLAND FAA STATION</b></p> <p align="center"><b>ANNETTE ISLAND, ALASKA</b></p> <p align="center"><b>JUNE 1994</b></p>							
<b>RADIAL LINE 7</b>  <b>Sample ID (ANN94)-</b>  <b>Distance:</b> <b>Depth BGS:</b>	<b>Grid Point 1</b>		<b>Grid Point 2</b>	<b>Grid Point 3</b>	<b>Grid Point 4</b>	<b>Grid Point 5</b>	<b>Gid Point 6</b>
	<b>ESV-SD-218</b>	<b>ESV-SB-207</b>	<b>ESV-SD-219</b>	<b>ESV-SD-220</b>	<b>ESV-SD-238</b>	<b>ESV-SD-230 Fence</b>	<b>ESV-SD-256</b>
	<b>0 Feet 0 Inches</b>	<b>0 Feet 12 Inches</b>	<b>5 Feet 0 Inches</b>	<b>10 Feet 0 Inches</b>	<b>31 Feet 0 Inches</b>	<b>46 Feet 0 Inches</b>	<b>77 Feet 0 Inches</b>
Chromium	601	291	567	764	797	819	204
Manganese	1,196	720	1,319	1,088	1,111	1,131	427
Iron	47,839	27,843	48,234	46,791	44,427	51,194	11,190
cobalt	502	350	685	515	859	450	178
Nickel	828	263	834	851	727	796	26 U
Copper	49 U	49 U	49 U	49 U	49 U	49 U	49 U
Zinc	118	35	69	61	172	886	44
Arsenic	39 U	33 U	33 U	33 U	37 U	42 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	2 U	2 U	3	2 U	2 U	2 U	2 U
Mercury	35 U	35 U	35 U	35 U	35 U	35 U	35 U
Lead	391	50	152	99	372	417	194

Key at end of table.

Table 3-2

EXPANDED SITE INVESTIGATION LEVEL II SOIL SAMPLES  
XRF METALS RESULTS (mg/kg)  
VORTAC FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA  
JUNE 1994

RADIAL LINE 8  Sample ID (ANN94)-  Distance: Depth BGS:	Grid Point 1		Grid Point 2	Grid Point 3	Grid Point 4		Grid Point 5	Grid Point 6
	ESV-SD-221 0 Feet 0 Inches	ESV-SB-208 0 Feet 12 Inches	ESV-SD-222 5 Feet 0 Inches	ESV-SD-223 10 Feet 0 Inches	ESV-SD-239 29 Feet 0 Inches	ESV-SB-239 29 Feet 12 Inches	ESV-SD-231 Fence 49 Feet 0 Inches	ESV-SD-257 77 Feet 0 Inches
Chromium	201	178 U	877	785	464	517	566	267
Manganese	637	785	1,002	893	980	523	1,240	409 U
Iron	29,772	28,909	46,947	42,836	38,264	17,306	45,078	3,075
Cobalt	283	235	723	657	411	174 U	310	174 U
Nickel	283	219	806	681	584	26 U	806	26 U
Copper	78	49 U	49 U	49 U	49 U	49 U	49 U	49 U
Zinc	276	171	157	115	162	506	136	145
Arsenic	56 U	33 U	33 U	33 U	52 U	33 U	33 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	14	4	2 U	2 U	2 U	3	2 U	2 U
Mercury	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U
Lead	556	286	198	199	521	17	217	321

recycled paper

3-29

ecology and environment

Key at end of table.

<p align="center"><b>Table 3-2</b> <b>EXPANDED SITE INVESTIGATION LEVEL II SOIL SAMPLES</b> <b>XRF METALS RESULTS (mg/kg)</b> <b>VORTAC FACILITY</b> <b>ANNETTE ISLAND FAA STATION</b> <b>ANNETTE ISLAND, ALASKA</b> <b>JUNE 1994</b></p>								
VORTAC UST  Sample ID (ANN94)-  Depth BGS:	Fill Pipe		South Side		Vent Pipe		North Side	
	ESV-SD-240	ESV-SB-240	ESV-SD-241	ESV-SB-241	ESV-SD-242	ESV-SB-242	ESV-SD-243	ESV-SB-243
	0 Inches	12 Inches	0 Inches	0 Inches	0 Inches	0 Inches	0 Inches	12 Inches
Chromium	861	609	593	599	453	535	632	272
Manganese	1,209	1,139	1,049	966	1,060	875	1,085	859
Iron	47,979	48,038	46,616	44,448	41,933	38,640	44,653	39,298
Cobalt	644	536	426	487	427	298	450	492
Nickel	773	782	769	772	559	482	703	543
Copper	49 U	49 U	49 U	49 U	49 U	49 U	49 U	49 U
Zinc	147	129	138	117	340	264	541	81
Arsenic	43 U	38 U	33 U	33 U	42 U	33 U	35 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	2 U	2 U	2 U	2 U	2 U	2 U	2 U	2 U
Mercury	35 U	35 U	35 U	35 U	35 U	35 U	35 U	35 U
Lead	426	378	166	167	424	306	348	81

Key:

BGS = Below ground surface.  
mg/kg = Milligrams per kilogram.  
U = Element was undetected. Reported result is the instrument detection limit.



<p><b>Table 3-3</b></p> <p><b>ESI SOIL SAMPLES</b></p> <p><b>POSITIVELY IDENTIFIED PETROLEUM COMPOUNDS AND TOTAL LEAD</b></p> <p><b>LEVEL III ANALYSIS</b></p> <p><b>VORTAC FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(mg/kg)</b></p>				
Sample ID	Parameters			
	Lead	DRO	VPH-G	TRPH
ANN94ESV-SD-400	610	180 J	ND	230
ANN94ESV-SB-400	580	220 J	ND	69
ANN94ESV-SD-401	1,200	11	ND	110
ANN94ESV-SB-401	200	6.3	ND	100
ANN94ESV-SD-402	510	100 J	5.5	120
ANN94ESV-SB-402	460	19	ND	66
ANN94ESV-SD-403	260	17	ND	ND
ANN94ESV-SB-403	440	15	ND	ND
ANN94ESV-SD-404	1,100	NA	NA	NA
ANN94ESV-SB-404	86	NA	NA	NA
ANN94ESV-SD-405	150	NA	NA	NA
ANN94ESV-SD-406	500	NA	NA	NA
ANN94ESV-SD-407	160	NA	NA	NA
ANN94ESV-SD-408	15	NA	NA	NA
ANN94ESV-SD-409	14	NA	NA	NA
ANN94ESV-SD-410	200	NA	NA	NA
ANN94ESV-SD-411	160	NA	NA	NA
ANN94ESV-SD-412	520	NA	NA	NA
ANN94ESV-SD-413	4,100	NA	NA	NA
ANN94ESV-SB-413	300	NA	NA	NA
ANN94ESV-SD-414	1,500	NA	NA	NA
ANN94ESV-SB-414	110	NA	NA	NA

Key at end of table.

Key:

DRO = Diesel-range organic.  
FAA = Federal Aviation Administration, Alaskan Region.  
ID = Identification.  
J = Estimated.  
mg/kg = Milligrams per kilogram.  
NA = Not analyzed.  
ND = Not detected.  
SB = Subsurface soil.  
SD = Soil.  
TRPH = Total recoverable petroleum hydrocarbons.  
VORTAC = Very High Frequency Omnirange Station/Tactical Air Navigation.  
VPH-G = Volatile petroleum hydrocarbons as gasoline.

<p><b>Table 3-4</b></p> <p><b>ESI SOIL AND SEDIMENT SAMPLES</b></p> <p><b>POSITIVELY IDENTIFIED INORGANIC COMPOUNDS</b></p> <p><b>LEVEL IV ANALYSIS</b></p> <p><b>VORTAC FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(mg/kg)</b></p>					
Sample Number (ANN94-):	ESV-SD-100	ESV-SB-100	ESV-SD-101	ESV-SE-100	ESV-SE-101
<b>Metals</b>					
Aluminum	5,030	4,330	4,330	1,020	2,580
Arsenic	11.5	1.4	10.6	ND	ND
Barium	45.0	39.4	19.4	3.4	10.8
Beryllium	0.11	0.12	0.12	0.09	0.12
Calcium	4,730 J	1,060 J	1,370 J	4,650	832
Chromium	64.2	25.5	71.8	2.3	2.6
Cobalt	51.7	28.2	68.1	ND	ND
Copper	98.6 J	23.3 J	125 J	1.5	4.0
Iron	28,800	18,300	36,400	940 J	3,130 J
Lead	1,170 J	0.60 J	2,260	10.9 J	4.5 J
Magnesium	84,800	47,100	119,000	1,070	1,390
Manganese	531	307	647	26.9	42.0
Mercury	0.35	ND	0.53	ND	ND
Nickel	353	194	507	ND	ND
Potassium	956	797	323	ND	ND
Sodium	51.3	ND	ND	ND	ND
Vanadium	17.4	18.8	16.1	3.7	7.1
Zinc	477 J	166 J	706 J	ND	23.3

Key at end of table.  
recycled paper

<p align="center"><b>Table 3-4</b></p> <p align="center"><b>ESI SOIL AND SEDIMENT SAMPLES</b></p> <p align="center"><b>POSITIVELY IDENTIFIED INORGANIC COMPOUNDS</b></p> <p align="center"><b>LEVEL IV ANALYSIS</b></p> <p align="center"><b>VORTAC FACILITY</b></p> <p align="center"><b>ANNETTE ISLAND FAA STATION</b></p> <p align="center"><b>ANNETTE ISLAND, ALASKA</b></p> <p align="center"><b>(mg/kg)</b></p>					
Sample Number (ANN94-):	ESV-SE-102	ESV-SE-103	ESV-SE-104	ESV-SE-105	ESV-SE-106
<b>Metals</b>					
Aluminum	11,200	1,800	2,690	564	4,780
Arsenic	1.1	ND	ND	ND	4.8
Barium	29.6	5.2	12.8	10.1	22.7
Beryllium	0.23	ND	ND	ND	0.10
Calcium	1,620	307	725	660	2,060
Chromium	6.3	ND	3.1	ND	37.5
Cobalt	4.6	ND	ND	ND	21.3
Copper	7.0	ND	3.8	2.6	9.0
Iron	7,160 J	602 J	4,430 J	3,130 J	21,500 J
Lead	2.7 J	18.0 J	4.8 J	1.6 J	5.1 J
Magnesium	2,900	148	1,030	421	44,400
Manganese	82.6	43	47.4	12.6	266
Mercury	ND	ND	ND	ND	ND
Nickel	3.5	ND	4.4	ND	151
Potassium	ND	ND	ND	ND	ND
Sodium	53.5	ND	ND	ND	1,380
Vanadium	26.1	ND	7.4	ND	16.8
Zinc	ND	30.2	ND	ND	88.6

Key at end of table.

<p align="center"><b>Table 3-4</b></p> <p align="center"><b>ESI SOIL AND SEDIMENT SAMPLES</b></p> <p align="center"><b>POSITIVELY IDENTIFIED INORGANIC COMPOUNDS</b></p> <p align="center"><b>LEVEL IV ANALYSIS</b></p> <p align="center"><b>VORTAC FACILITY</b></p> <p align="center"><b>ANNETTE ISLAND FAA STATION</b></p> <p align="center"><b>ANNETTE ISLAND, ALASKA</b></p> <p align="center"><b>(mg/kg)</b></p>					
<b>Sample Number (ANN94-):</b>	<b>ESV-SD-412*</b>	<b>ESV-SD-413*</b>	<b>ESV-SB-413*</b>	<b>ESV-SD-414*</b>	<b>ESV-SB-414*</b>
<b>Metals</b>					
Aluminum	NA	NA	NA	NA	NA
Arsenic	NA	NA	NA	NA	NA
Barium	NA	NA	NA	NA	NA
Beryllium	NA	NA	NA	NA	NA
Calcium	NA	NA	NA	NA	NA
Chromium	NA	NA	NA	NA	NA
Cobalt	NA	NA	NA	NA	NA
Copper	NA	NA	NA	NA	NA
Iron	NA	NA	NA	NA	NA
Lead	349 J	6,020 J	467 J	1,420 J	69.3 J
Magnesium	NA	NA	NA	NA	NA
Manganese	NA	NA	NA	NA	NA
Mercury	NA	NA	NA	NA	NA
Nickel	NA	NA	NA	NA	NA
Potassium	NA	NA	NA	NA	NA
Sodium	NA	NA	NA	NA	NA
Vanadium	NA	NA	NA	NA	NA
Zinc	NA	NA	NA	NA	NA

**Key:**

J = Estimated concentration.  
 mg/kg = Milligrams per kilogram.  
 NA = Not analyzed.  
 ND = Not detected.  
 SD = Soil sample.  
 SE = Sediment sample.  
 \* = Lead only reanalysis.  
 recycled paper

Table 3-5

**EXPANDED SITE INVESTIGATION SOIL AND SEDIMENT SAMPLES  
POSITIVELY IDENTIFIED ORGANIC COMPOUNDS,  
LEVEL IV ANALYSIS  
VORTAC FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA  
( $\mu\text{g/kg}$ )**

Sample Number (ANN94-):	ESV-SD-100	ESV-SB-100	ESV-SD-101	ESV-SE-100	ESV-SE-101	ESV-SE-102	ESV-SE-103	ESV-SE-104	ESV-SE-105	ESV-SE-106
<b>VOCs</b>										
Chloroform	ND	ND	ND	ND	ND	ND	3	ND	ND	ND
Toluene	110	3	49	ND	2	ND	4	ND	27	ND
<b>BNA</b>										
Diethylphthalate	ND	ND	ND	2,300	1,100	ND	ND	ND	ND	ND

**Key:**

BNA = Base neutral/acid extractable organic compound.  
 ND = Not detected.  
 SB = Subsurface soil sample.  
 SD = Soil sample.  
 SE = Sediment sample.  
 VOC = Volatile organic compounds.

recycled paper

3-37

ecology and environment

<p><b>Table 3-6</b></p> <p><b>ESI SOIL SAMPLES</b></p> <p><b>POSITIVELY IDENTIFIED TCLP METALS</b></p> <p><b>LEVEL IV ANALYSIS</b></p> <p><b>VORTAC FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(mg/L)</b></p>									
Sample Number (ANN94-):	ESV-SD-100	ESV-SB-100	ESV-SD-101	ESV-SD-412	ESV-SD-413	ESV-SB-413	ESV-SD-414	ESV-SB-414	Regulatory Level
<b>Metals</b>									
Barium	0.49	0.42	0.47	NA	NA	NA	NA	NA	100.0
Cadmium	0.12	ND	0.0091	NA	NA	NA	NA	NA	1.0
Lead	5.7	0.87	11.1	ND	65.2	5.2	8.1	0.28	5.0

**Key:**

mg/L = Milligrams per liter.


NA = Not analyzed.

ND = Not detected at quantitation limits noted in parenthesis.

SB = Subsurface soil.

SD = Soil sample.

Source: Ecology and Environment, Inc. 1994.



SOURCE: Field observation

KEY	
	Marsh
	Direction of Surface Water Drainage
NOTE: Buildings Not To Scale	

Approximate Scale In Feet  
 0 15 30

Ecology and Environment, Inc.


Figure: 3-1 Proj. No.: VS1000

Date: 5-25-94 Drawn By: JAL

Title: Annette Island FAA Station  
 VORTAC/DF Facility  
 Site Map



Source: Ecology and Environment, Inc. 1994



Key:	
SD	= composite surface soil sample
SB	= grab soil sample at 1 foot BGS
▲	= Sample location

0 40 80  
SCALE IN FEET

N

Ecology and Environment Inc.	
Figure: 3 - 2	Proj. No: VS1050
Date: 9-9-94	Drawn by: DEH
Title: Annette Island FAA Station ESI VORTAC Facility Level II XRF Screening Sample Location Map June 1994	

500/14 = surface/ 1 foot BGS  
ND = not detected




0 40 80

SCALE IN FEET

**Title: Annette Island FAA Station ESI  
VORTAC Facility Level II XRF Screening  
Lead Results Map (mg/kg)  
JUNE 1994**

Source: Ecology and Environment, Inc. 1994




Key:	
▲	= level III samples
●	= level IV samples
SD	= composite surface soil sample
SB	= grab soil sample at 1 foot BGS

0 40 80  
SCALE IN FEET



Ecology and Environment Inc.	
Figure: 3 - 4	Proj. No: VS1050
Date: 9-9-94	Drawn by: DEH
Title: Annette Island FAA Station ESI Vortac Facility Level III & IV Sample Location Map June 1994	

Source: Ecology and Environment, Inc., 1994







Key:	
1500/110 =	surface/ 1 foot BGS (mg/kg)
● =	Level IV sample location
11.1 =	TCLP result (mg/l)
▲ =	Level III sample location
*	TAL lead reanalysis
ND	not detected

0 40 80  
SCALE IN FEET



Ecology and Environment Inc.	
Figure: 3 - 5	Proj. No: VS1050
Date: 9-9-94	Drawn by: DEH
Title: Annette Island FAA Station ESI Vortac Facility Level III & IV TAL and TCLP Lead Results Map June 1994	



Ecology and Environment Inc.	
Figure: 3-6	Proj. No: VR1000
Date: 9/08/94	Drawn by: EGM
Title: ANNETTE ISLAND FAA STATION VORTAC FACILITY OVERLAND SURFACE WATER PATHWAY SAMPLE LOCATION MAP	

## **4. NONDIRECTIONAL BEACON/H-MARKER FACILITY**

### **4.1 LOCATION AND DESCRIPTION**

The NDB/H-marker facility is an active facility located approximately 1.5 miles northwest of the north end of the runway on 10 leased acres (see Figure 1-2). The former NDB/H-marker building was burned completely in the early 1980s and all that remains is a 500-square-foot foundation. After the building burned, the debris was bulldozed off of the foundation mostly to the south and west sides. During the ECI, ash and burned material could be seen mixed with soil around the perimeter of the foundation. Building 407, a small fiberglass Grassis building, was subsequently placed on the foundation. This building now houses active electronics equipment used to operate the NDB. A fenced antenna tower and live transformer, constructed on a built-up gravel pad, were located immediately to the east of the foundation. A live transformer owned by Metlakatla Power and Light is located next to the road, directly west of the NDB/H-marker building. A gravel service road leads from the main road past the weather bureau living quarters, which is the access point for the RCAG facility, to the NDB/H-marker facility. A gate across the service road is located just beyond the weather bureau housing area, approximately 0.3 mile from the NDB/H-marker facility (see Figure 4-1). The gate is usually not locked and the area beyond the gate, including the NDB/H-marker facility area, can be accessed at all times. The road is used by local residents to access the coastal area at Smuggler Cove.

The property surrounding the NDB/H-marker facility is mostly composed of marsh and muskeg. A small pond is located immediately south of the concrete foundation. A small stream flows west from the pond beneath the road and drains into a marsh area west of the road. See Section 4.2.6 for further discussion of the habitat in the area.

An ECI conducted in August 1991 (E & E 1992b) identified the presence of lead in soil samples collected on the west side of the concrete foundation and on the west side of the

fenced tower. The lead concentration at both of these locations exceeded MSEC. Additionally, contaminants in the TAL metal fraction and the dioxin/furan fraction exceeded three times background concentrations. Both of these areas were targeted for further investigation in the ESI as stated in the FAA SOW dated September 29, 1993.

## **4.2 EXPANDED SITE INVESTIGATION**

### **4.2.1 Level II Soil Grid Sampling**

To determine the extent of lead contamination around the concrete foundation, a grid sampling array was developed to cover the area where burned debris and ash were visible and contamination was suspected. Surface soil samples were initially collected at evenly spaced 5-foot intervals around the foundation. A second tier of samples were collected at a distance of 5-feet from the initial sample grid. The sample location and corresponding sample number for all surface and subsurface soil samples are shown on Figure 4-2. Table 4-1 summarizes the samples collected. The samples were analyzed for lead using a field portable XRF. XRF analytical protocol is presented in Appendix F. Where elevated lead levels in excess of 500 mg/kg were found, a subsurface sample was collected 12-inches beneath the surface sample. A contingency was established in the ESI work plan to collect samples at a deeper 24-inch contour if lead concentrations exceeded 500 mg/kg in the 12-inch subsurface samples, this occurred at three sample locations: ANN94ESN-SB-215 (northwest corner), ANN94ESN-SB-230 (southeast corner); and ANN94ESN-SB-232 (southwest corner).

The results of XRF lead analysis for all sample locations are presented in Table 4-2 and in Figure 4-3. Up to three values are presented on Figure 4-3 as SD/SB/SC for each sample corresponding to the surface (SD), subsurface at 12-inch depth (SB) and subsurface at a 24-inch depth (SC). The distribution of lead concentration in surface and sub-surface soil was variable throughout the study area. Concentrations greater than 500 mg/kg were found primarily on the south and west sides, where a majority of the burned debris was observed. Lead levels greater than 500 mg/kg were also found in one sample on each of the north and east sides of the foundation. Lead was less than 300 mg/kg on the west side of the NDB/H-marker transmitter tower.

### **4.2.2 Level III Lead Sampling**

Selected surface and subsurface Level II samples were submitted for Level III confirmation analysis of lead. A sample summary is presented in Table 4-1 and sample

locations are shown on Figure 4-4. The results of the Level III lead analysis are presented by location on Figure 4-5 and in Table 4-3. Level III total lead results did not correlate with Level II XRF or Level IV lead results found at the same locations. The soils around the NDB/H-marker building foundation consist of gravel intermixed with ash and debris. This matrix nonhomogeneity is suspected to be the cause of poor lead correlation. For this reason, NDB/H-marker Level III confirmation samples were not included in the XRF/ASC lead correlation as described in Section 2.7.4.

#### 4.2.3 Level IV Source and Target Sampling

Potential source and surface water pathways for lead and other contaminants present around the concrete foundation source area were assessed. Characterization of the source area using Level II and Level III analysis has been previously described. Level IV source samples were collected from lead contaminated areas that were identified during the ECI. The potential CERCLA source was characterized by submitting two surface and one shallow subsurface soil samples collected from the west side of the concrete foundation. Surface soil sample ANN94ESN-SD-101 was collected near the southwest corner of the building. Collocated surface (ANN94ESN-SD-100) and subsurface (ANN94ESN-SB-100) soil samples were collected near the northwest corner of the building. The sample locations are presented in Figure 4-4. All three samples were submitted for Level IV analysis for TAL metals and TCL parameters, including dioxin/furan parameters.

All the surface and subsurface source samples were found to contain the following concentrations of metals at greater than three times background concentrations: barium (145 mg/kg), chromium (47.1 mg/kg), lead (1,990 mg/kg), and zinc (345 mg/kg) in surface soil sample ANN94ESN-SD-100; arsenic (31.5 mg/kg), chromium (118 mg/kg), cobalt (73.6 mg/kg), copper (86.7 mg/kg), lead (1,040 mg/kg), magnesium (129,000 mg/kg), nickel (592 mg/kg), selenium (2.3 mg/kg), and zinc (701 mg/kg) in subsurface soil ANN94ESN-SB-100; and chromium (298 mg/kg) and lead (2,450 mg/kg) in surface soil ANN94ESN-SD-101. Inorganic analytical results are reported in Table 4-4. Total lead concentrations are reported on Figure 4-5. Lead exceeded the MSEC criteria of 400 mg/kg for all three of these source samples. In addition, the following dioxin isomers were found in these samples: OCDD (182 ng/kg), 1,2,3,4,6,7,8 HpCDF (4.86 ng/kg), total HpCDD (28.3 ng/kg), and HpCDF (5.60 ng/kg) in ANN94ESN-SD-100; 1,2,3,4,6,7,8-HpCDD (22.0 ng/kg), OCDD (85.4 ng/kg), 1,2,3,4,7,8-HxCDF (4.64 ng/kg), 1,2,3,4,6,7,8-HpCDF (6.75 ng/kg), total HpCDD (22.0



ng/kg), and total HpCDF (11.2 ng/kg) in sample ANN94ESN-SB-100; and OCDD (88.7 ng/kg) in ANN94ESN-SD-101. Dioxin analytical results are reported in Table 4-5. None of the samples exceeded the MSEC value of 1 part per billion (ppb) total equivalence factor (TEF) for dioxins. No other compounds were found to exceed three times background concentrations or MSEC criteria in these samples (see Section 4.2.4 for a complete discussion of the background samples).

In addition to these source samples, sample ANN94ESN-SD-402, which was originally a Level III sample, was submitted in September 1994 for reanalysis of Level IV TAL lead only. This reanalysis was performed at FAA's request concurrent with a TCLP metals analysis (see Section 4.2.5). This sample contained lead at 3,270 mg/kg which exceeded the lead MSEC of 400 mg/kg and exceeded three times background concentrations. Results are presented in Table 4-4 and on Figure 4-5.

The wetland adjacent to the NDB/H-marker facility was evaluated to determine whether it meets the criteria of a target wetland located in the surface water pathway according to the HRS model. One runoff pathway was identified, which extended from the pond and marsh located west of the facility northeast to Smuggler Cove (see Section 4.2.6 for a complete discussion of the pathways). Sediment samples were collected at the probable point of entry into the wetland, at approximately 0.1 mile and 0.2 mile from the probable point of entry, and at the beach at Smuggler Cove. The beach sample was collected from a surface beach area at the mean tide line.

Various compounds were found to be present in target sediment samples collected from the NDB/H-marker facility. Aluminum (7,270 mg/kg), barium (17.0 mg/kg), magnesium (4,890 mg/kg), manganese (62.8 mg/kg), nickel (22.5 mg/kg), and vanadium (12.8 mg/kg) were found to be present in peat sediment sample ANN94ESN-SE-100, which was collected at the wetland probable point of entry. All of these compounds were also found in source samples.

Barium was also found at greater than three times background concentrations in sandy stream sediment sample ANN94ESN-SE-102 (37.1 mg/kg), which was collected 0.2 mile downgradient of ANN94ESN-SE-100; and in beach sediment sample ANN94ESN-SE-103 (75.4 mg/kg), which was collected at the end of the drainage. In addition, sample ANN94ESN-SE-103 contained potassium (3,090 mg/kg) and diethylphthalate (1,400 mg/kg) at concentrations that exceeded three times background. Diethylphthalate was not found in source samples; therefore, it does not appear the NDB is the source of this compound. No

other compounds were found to exceed three times background concentrations or MSEC criteria in these samples. A sample summary is presented in Table 4-1 and sample results are presented in Tables 4-2 through 4-6.

#### **4.2.4 Background Samples**

Background samples were collected for each distinct sample matrix (soil, sediment, and beach sediment) sampled. The matrices encountered at the NDB/H-marker included soil/gravel, sandy sediment, peaty sediment, and beach sand. See sections 2.7.1 and 4.2.4 for a discussion of the background samples.

#### **4.2.5 Level IV TCLP Sampling**

Source samples ANN94ESN-SD-100, ANN94ESN-SB-100, and ANN94EN-SD-101 were also submitted for Level IV TCLP metals analysis. Sample ANN94ESN-SD-402 was submitted for Level IV TCLP lead-only analysis in September 1994 after the field work was completed and at the request of FAA. The results are presented in Table 4-7 and on Figure 4-5. This sample was also submitted for reanalysis of Level IV TAL lead-only concurrent with the TCLP analysis for comparison purposes. Sample ANN94ESN-SD-402 (14.3 mg/l) exceeded the TCLP regulatory limit for lead of 5.0 mg/l. No other sample results exceeded TCLP regulatory limits. Results are presented in Table 4-7 and on Figure 4-5.

#### **4.2.6 Wetlands Survey**

The primary objective of the wetland survey was to identify wetlands 0.2 mile down-gradient of the source. The wetland survey conforms to the definition provided in 40 CFR 230.41 See Section 3.2.1.3 for the definition of a wetland and for a discussion of Annette Island wetlands.

The NDB/H-marker was constructed on a gravel pad. The pad extended several feet in all directions beyond the remaining foundation. Drainage ditches extended from floor drains on the south end of the foundation. Surface runoff apparently followed the drainage ditches, crossed the road, and then traveled southwest to a low point. At this low point, the surface runoff intersected another drainage ditch. This drainage ditch subsequently emptied into a small channel, which drained into a series of ponds. This area represented the closest wetland along the drainage pathway from the NDB/H-marker and was chosen as the wetland point of entry. ANN94ESN-SE-100 was collected from this location. The overland surface

water pathway is shown in Figure 4-6. Vegetation in this area consisted of sitka alder (*Alnus sitkensis*), shore pine, yellow cedar, and sweet gale in the shrub layer. There was no tree stratum in this area. Horsetail, deer cabbage, fragile fern (*Cystopteris fragilis*), jeffrey shooting star, skunk cabbage, labrador tea, bog laurel, crowberry, indian helleborne (*Veratrum viride*), and various sedges (*Carex spp.*) were in the herbaceous layer. The soil was peat overlying a muck and was saturated. Standing water was observed in the area.

South of ANN94ESN-SE-100 surface water channelized and then drained into a series of ponds. From the ponds, water drained to the west towards Clarence Strait. A drainage channel formed and entered a forested wetland that had upland incursions. The channel substrate varied from sandy soils to organic muck overlying sandy soils. The channel meandered through the wetland and disappeared approximately 100 feet from the beach. ANN94ESN-SE-101 and ANN94ESN-SE-102 were collected in the stream channel within the forested wetland at 0.1 mile and 0.2 mile downgradient of the wetland probable point of entry, respectively. The channel varied from one to two feet in depth and contained approximately 4 to 6 inches of water. The soils on the banks of the stream channel were organic peat and muck overlying sands. The channel substrate varied from organic material overlying sands and gravel, to a sand and gravel bottom.

The vegetation in the forested wetland consisted of yellow cedar, western redcedar, shore pine, and hemlock in the tree stratum. The shrub/shrub layer contains evergreen huckleberry, oval-leaf blueberry (*Vaccinium ovalifolium*), fool's huckleberry, labrador tea, yellow cedar, and hemlock. The herbaceous layer contained skunk cabbage, deer cabbage, labrador tea, crowberry, dwarf dogwood, sphagnum moss, and grasses. The stream channel was lined with hydrophytic vegetation, which extended away from the channel. The areal extent of the hydrophytic vegetation depended on the slope of the land adjacent to the channel.

A spring trickled over exposed bedrock on the beach at the approximate location where the channel disappears. Vegetation ended abruptly at the highwater mark on the beach. ANN94ESN-SE-103 was collected on the beach below the high tide line within the spring area. The sample consisted of sands and gravel.

#### **4.2.7 Site Specific Remedial Goals**

As discussed previously in Section 2.8, MSECs were developed to screen the analytical results and to identify contaminants and areas that could have the potential to pose a significant risk of adverse human health effects. Lead was the only contaminant with a range

of concentration in soil at the NDB/H-marker that exceeded the conservative MSECs; therefore, it was the only one requiring a site-specific remedial goal.

The potentially exposed population consists of on-site workers and residents living on Annette Island. Information provided in the ECIR (E & E 1992b) indicated that the worker population consisted of 4 people who work periodically at each of the operating FAA facilities: the VORTAC/DF, NDB/H-marker, and RCAG. The typical work schedule involves maintenance personnel visiting each facility once per month and on an as-needed basis. It is estimated that the FAA workers spend less than 25% of their monthly work shift at the Annette Island facilities.

Residents living on the island consist of the people living in Metlakatla (630), which is located approximately 5 miles north of the FAA Station, and those living near the FAA facilities. It was estimated in the ECIR that 61 people live or work within 2-3 miles of the NDB/H-marker facility. The population living nearest to the FAA station were at the WBH area, located within 1/4 mile of the NDB/H-marker (Figure 4-1). At the time of the ECI, 15 people, including adults and children, were living in the WBH area.

Access to the contaminated soil at the NDB/H-marker is unrestricted. As discussed in Section 4.1, there was a gate on the access road between the WBH area and the NDB/H-marker, but it was not locked and local residents used the road to access coastal areas. Children living on Annette Island, primarily in Metlakatla and the WBH area, could gain access to the NDB/H-marker facility, although it is unlikely that they would spend much time in direct contact with the contaminated soil at the NDB/H-marker.

As discussed in Section 3.2.7, the IEUBK model, although not directly relevant to the adult population or the potential exposure situation on Annette Island, did provide a starting point for qualitative assessment of potential lead exposure. The recommended 400 mg/kg soil screening level was based on an average concentration for a potential exposure area. The average lead concentration at the NDB/H-marker was calculated based on both Level II screening and Level III confirmation data. The Level II samples were collected on a grid that characterized the entire source area, and as such were probably more representative of the area. A subset of these samples, which represented soil in the overland surface water pathway, were selected and submitted for Level III confirmation analysis. Unlike at the VORTAC/DF, the soil at the NDB/H-marker was not homogenous, and was composed of soil, gravel and an ash layer.

The average surface lead concentration in the biased Level III samples was 1392 mg/kg. The average of the Level II results was lower and, due to the non-homogeneous soil, was marginally correlated ( $r = 0.79$ ) to the corresponding Level III values. The average Level II concentration was 524 mg/kg, which correlates to a 732 mg/kg Level III average (see Section 2.7.4.1 for a discussion of the correlation). Although young children could come into contact with contaminated soils in the NDB/H-marker area, exposure to those soils is unlikely to account for more than a small fraction of their total soil exposure, perhaps 5% to 10% at most. Since the 400 mg/kg screening level is considered adequately protective for young children when 100% of their exposure is to soils with that lead concentration, higher soil concentrations would be acceptable in an area like the NDB/H-marker area that is likely to contribute only a small fraction of an individual's total soil exposure. While the average soil lead concentration in the NDB/H-marker area may be as much as two to four times higher than the screening level, the fraction of exposure accounted for by that soil is probably at least 10 to 20 times lower than the 100% that formed the basis of the screening level. Therefore, the existing lead concentrations in the NDB/H-marker area soils appear to be adequately protective for young children because of the small contribution that area is likely to make to the children's total soil exposure.

The FAA employees who maintain the agency's facilities on Annette Island are the individuals likely to experience the greatest exposure to the NDB/H-marker area soils. The existing soil lead concentrations also appear to be adequately protective for these individuals because of their limited exposure to the soils and because of their lesser sensitivity to lead in soils as previously discussed in Section 3.2.7.

Since a review of the site conditions and potential exposures that might reasonably occur indicates that the existing soil lead concentrations appear to be acceptable for both young children, who are normally the group most sensitive to lead exposure, and facility worker who probably experience the greatest exposure, no site-specific remedial goal for lead in NDB/H-marker area soils on Annette Island appears to be needed.

#### **4.2.8 Deviations From the Work Plan**

All work at the NDB/H-marker facility was performed as specified in the ESI work plan except that surface water runoff pathway was thought to be the same for both the RCAG and the NDB/H-marker facilities. After inspecting the pathway, it was determined that they were separate and required three additional sediment samples and one additional beach sample

to characterize the pathway at the RCAG. See Section 5.2.4 for a discussion of the RCAG runoff pathway.

#### **4.2.9 Conclusions and Recommendations**

The issues of concern at the NDB/H-marker were the presence of contamination in soil, the exceedance of regulatory criteria and the potential for exposure to the contamination. The results of the investigation are summarized as follows:

- Lead contamination found in surface soil in the source area had a range of concentration which exceeded the MSEC. TCLP analysis indicated that the lead exceeded the 5.0 mg/L regulatory criteria. Approximately 150 cubic yards of soil are potentially affected at this facility, assuming contamination exists in the top 24 inches of soil across the site. Further action is recommended to address the lead contamination; and
- An assessment of the potential exposure to the lead contamination indicated that it did not pose a significant risk of adverse health effects. However, access to the lead contaminated soil is not restricted. Steps should be taken to contain the contaminated soil and to control access to it.

Table 4-1

**EXPANDED SITE INVESTIGATION SAMPLE SUMMARY  
NDB/H-MARKER FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA**

Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESN-SD-100	Surface soil	BNA, Dioxin, Pest/PCB, TAL metals, TCLP metals, VOC, XRF metals	ASC, Triangle/Level IV	Source sample—northwest side of building.
ESN-SB-100	Subsurface soil	BNA, Dioxin, Pest/PCB, TAL metals, TCLP metals, VOC, XRF metals	ASC, Triangle/Level IV	Same location as ESN-SD-100 at 1 foot BGS.
ESN-SD-101	Surface soil	BNA, Dioxin, Pest/PCB, TAL metals, TCLP metals, VOC, XRF metals	ASC, Triangle/Level IV	Source sample—southwest side of building.
ESN-SE-100	Peaty sediment	BNA, Dioxin, Pest/PCB TAL metals, VOC	ASC, Triangle/Level IV	Entrance to wetland.
ESN-SE-101	Sandy stream sediment	BNA, Dioxin, Pest/PCB TAL metals, VOC	ASC, Triangle/Level IV	Wetland 0.1 mile downgradient of ESN-SE-100
ESN-SE-102	Sandy stream sediment	BNA, Dioxin, Pest/PCB TAL metals, VOC	ASC, Triangle/Level IV	Wetland 0.2 mile downgradient of ESN-SE-100
ESN-SE-103	Sandy stream sediment	BNA, Dioxin, Pest/PCB TAL metals, VOC	ASC, Triangle/Level IV	Beach at end of drainage
ESN-SD-400	Surface soil	Total lead	ASC/Level III	Same location as ESN-SD-100
ESN-SB-400	Subsurface soil	Total lead	ASC/Level III	Same location as ESN-SB-100
ESN-SD-401	Surface soil	Total lead	ASC/Level III	Same location as ESN-SD-101
ESN-SD-402	Surface soil	Total lead, TCLP lead, TAL lead	ASC/Level III,IV	Source sample—southwest side of building
ESN-SD-403	Surface soil	Total lead	ASC/Level III	Source sample—north side of building
ESN-SB-404	Subsurface soil	Total lead	ASC/Level III	Source sample—southwest corner of building
ESN-SB-405	Subsurface soil	Total lead	ASC/Level III	Source sample—southeast side of building
ESN-SD-210	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-210	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations

Key at end of table.

recycled paper

4-11

ecology and environment

<p><b>Table 4-1</b></p> <p><b>EXPANDED SITE INVESTIGATION SAMPLE SUMMARY</b></p> <p><b>NDB/H-MARKER FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p>				
Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESN-SD-211	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-211	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-212	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-212	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-213	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-213	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-214	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-214	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-215	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-215	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SC-215	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-216	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-216	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-217	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-217	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-218	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-218	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-219	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations

Key at end of table.



Table 4-1

**EXPANDED SITE INVESTIGATION SAMPLE SUMMARY  
NDB/H-MARKER FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA**

Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESN-SB-219	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-220	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-220	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-221	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-221	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-222	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-222	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-223	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-223	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-224	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-224	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-225	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-226	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-226	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-227	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-227	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-230	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-230	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations

Key at end of table.

recycled paper

4-13

ecology and environment

<p><b>Table 4-1</b></p> <p><b>EXPANDED SITE INVESTIGATION SAMPLE SUMMARY</b></p> <p><b>NDB/H-MARKER FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p>				
Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESN-SC-230	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-232	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-232	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SC-232	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SD-260	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations
ESN-SB-260	Soil	XRF metals	Field/Level II	See Figure 4-2 for locations

**Key:**

- ASC = Analytical Service Center.
- BGS = Below ground surface.
- BNA = Base neutral/acid extractable compounds.
- BTEX = Benzene, toluene, ethylbenzene, and xylene.
- DRO = Diesel-range organics.
- Pest/PCB = Organochlorine pesticides/polychlorinated biphenyls.
- SB = Soil at 1 foot BGS.
- SC = Soil at 2 feet BGS.
- SD = Surface soil.
- SE = Sediment.
- TAL metals = Target Analyte List metals.
- TCLP = Toxicity characteristic leaching procedure.
- VPH-G = Volatile petroleum hydrocarbons as gasoline.
- XRF = X-ray fluorescence.

**Table 4-2**  
**EXPANDED SITE INVESTIGATION**  
**NDB/H-MARKER FACILITY**  
**LEVEL II SOIL SAMPLES**  
**XRF METALS RESULTS (mg/kg)**  
**ANNETTE ISLAND FAA STATION**  
**ANNETTE ISLAND, ALASKA**  
**JUNE 1994**

Sample ID (ANN94-):	ESN-SD-100	ESN-SB-100	ESN-SD-101	ESN-SD-210	ESN-SB-210	ESN-SD-211
Depth BGS (inches):	0	12	0	0	12	0
Chromium	784	825	515	426	256	476
Manganese	474	867	424	409 U	409 U	566
Iron	26,827	33,542	18,275	18,778	14,690	23,744
Cobalt	394	404	195	174 U	174 U	244
Nickel	420	507	58	58	77	151
Copper	49 U	94	49 U	49 U	49 U	53
Zinc	336	738	382	258	57	996
Arsenic	33 U	50 U	33 U	176 U	33 U	160 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	4	4	2 U	5	4	3
Mercury	35 U	35 U	35 U	35 U	35 U	35 U
Lead	199	500	270	1,757	46	1,597

Key at end of table.

<p align="center"><b>Table 4-2</b> <b>EXPANDED SITE INVESTIGATION</b> <b>NDB/H-MARKER FACILITY</b> <b>LEVEL II SOIL SAMPLES</b> <b>XRF METALS RESULTS (mg/kg)</b> <b>ANNETTE ISLAND FAA STATION</b> <b>ANNETTE ISLAND, ALASKA</b> <b>JUNE 1994</b></p>						
Sample ID (ANN94-):	ESN-SB-211	ESN-SD-212	ESN-SB-212	ESN-SD-213	ESN-SB-213	ESN-SD-214
Depth BGS (inches):	12	0	0	12	0	12
Chromium	436	564	926	240	178 U	412
Manganese	692	800	1,024	409 U	409 U	449
Iron	21,847	32,127	44,791	18,470	16,905	23,727
Cobalt	305	454	510	174 U	186	233
Nickel	76	484	827	103	48	233
Copper	49 U	49 U	49 U	49 U	49 U	49 U
Zinc	113	669	216	122	111	72
Arsenic	33 U	78 U	33 U	33 U	33 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	4	3	2 U	4	2 U	2 U
Mercury	35 U	35 U	35 U	35 U	35 U	35 U
Lead	254	778	112	130	71	62

Key at end of table.

**Table 4-2**  
**EXPANDED SITE INVESTIGATION**  
**NDB/H-MARKER FACILITY**  
**LEVEL II SOIL SAMPLES**  
**XRF METALS RESULTS (mg/kg)**  
**ANNETTE ISLAND FAA STATION**  
**ANNETTE ISLAND, ALASKA**  
**JUNE 1994**

Sample ID (ANN94-):	ESN-SB-214	ESN-SD-215	ESN-SB-215	ESN-SC-215	ESN-SD-216	ESN-SB-216
Depth BGS (inches):	12	0	12	24	0	12
Chromium	245	242	282	223	356	333
Manganese	527	481	511	660	756	609
Iron	25,510	17,148	25,060	23,182	28,404	25,075
Cobalt	205	174 U	158	232	320	169
Nickel	175	160	187	75	212	335
Copper	49 U	49 U	49 U	88	49 U	49 U
Zinc	186	95	416	367	163	253
Arsenic	33 U	33 U	91 U	38 U	33 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	2 U	2 U	3	5	2 U	5
Mercury	35 U	35 U	35 U	35 U	35 U	35 U
Lead	230	81	914	380	37	228

Key at end of table.

recycled paper

4-17

ecology and environment

<p><b>Table 4-2</b></p> <p><b>EXPANDED SITE INVESTIGATION</b></p> <p><b>NDB/H-MARKER FACILITY</b></p> <p><b>LEVEL II SOIL SAMPLES</b></p> <p><b>XRF METALS RESULTS (mg/kg)</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>JUNE 1994</b></p>						
Sample ID (ANN94-):	ESN-SD-217	ESN-SB-217	ESN-SD-218	ESN-DB-218	ESN-SD-219	ESN-SB-219
Depth BGS (inches):	0	12	0	12	0	12
Chromium	181	196	178 U	203	195	178 U
Manganese	581	409 U	474	409 U	672	409 U
Iron	24,068	15,242	20,385	14,465	22,361	13,124
Cobalt	251	174 U	174 U	174 U	215	174 U
Nickel	57	84	241	64	90	110
Copper	49 U	49 U	404	49 U	49 U	49 U
Zinc	132	78	2,463	95	373	131
Arsenic	33 U	33 U	404 U	33 U	33 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	2 U	3	9	2 U	2 U	4
Mercury	35 U	35 U	35 U	35 U	35 U	35 U
Lead	54	38	4,045	52	243	96

Key at end of table.

Table 4-2

**EXPANDED SITE INVESTIGATION  
NDB/H-MARKER FACILITY  
LEVEL II SOIL SAMPLES  
XRF METALS RESULTS (mg/kg)  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA  
JUNE 1994**

Sample ID (ANN94-):	ESN-SD-220	ESN-SB-220	ESN-SD-221	ESN-SB-221	ESN-SD-222	ESN-SB-222
Depth BGS (inches):	0	12	0	12	0	12
Chromium	321	178 U	501	483	186	228
Manganese	409 U	658	409 U	699	409 U	501
Iron	19,176	24,447	20,233	24,294	20,007	22,183
Cobalt	174 U	259	187	312	174 U	177
Nickel	136	73	62	49	107	39
Copper	49 U	49 U	49 U	49 U	60	49 U
Zinc	477	132	257	279	230	616
Arsenic	48 U	33 U	33 U	33 U	33 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	5	3	6	4	4	3
Mercury	35 U	35 U	35 U	35 U	35 U	35 U
Lead	482	61	278	202	208	260

Key at end of table.

<p><b>Table 4-2</b></p> <p><b>EXPANDED SITE INVESTIGATION</b></p> <p><b>NDB/H-MARKER FACILITY</b></p> <p><b>LEVEL II SOIL SAMPLES</b></p> <p><b>XRF METALS RESULTS (mg/kg)</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>JUNE 1994</b></p>						
Sample ID (ANN94-):	ESN-SD-223	ESN-SB-223	ESN-SD-224	ESN-SB-224	ESN-SD-225	ESN-SD-226
Depth BGS (inches):	0	12	0	12	0	0
Chromium	333	178 U	384	372	336	304
Manganese	409 U	409 U	1,096	820	767	426
Iron	19,218	16,139	37,452	28,068	31,133	24,447
Cobalt	174 U	188	306	158	385	174 U
Nickel	87	59	389	157	371	26 U
Copper	49 U	49 U	49 U	49 U	49 U	49 U
Zinc	170	81	99	81	126	161
Arsenic	33 U	33 U	33 U	33 U	33 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	2 U	3	4	3	2 U	6
Mercury	35 U	35 U	35 U	35 U	35 U	35 U
Lead	127	15	90	35	74	174

Key at end of table.



**Table 4-2**  
**EXPANDED SITE INVESTIGATION**  
**NDB/H-MARKER FACILITY**  
**LEVEL II SOIL SAMPLES**  
**XRF METALS RESULTS (mg/kg)**  
**ANNETTE ISLAND FAA STATION**  
**ANNETTE ISLAND, ALASKA**  
**JUNE 1994**

Sample ID (ANN94-):	ESN-SB-226	ESN-SD-227	ESN-SB-227	ESN-SD-230	ESN-SB-230	ESN-SC-230
Depth BGS (inches):	12	0	12	0	12	24
Chromium	285	264	178 U	178 U	178 U	178 U
Manganese	781	516	561	409 U	409 U	703
Iron	30,071	23,777	24,319	19,387	18,687	26,125
Cobalt	174 U	174 U	174 U	174 U	174 U	174 U
Nickel	57	67	59	88	84	61
Copper	49 U	49 U	98	49 U	49 U	49 U
Zinc	94	132	276	300	866	246
Arsenic	33 U	33 U	43 U	33 U	60 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U	16 U
Molybdenum	4	2 U	5	4	2 U	2 U
Mercury	35 U	35 U	35 U	35 U	35 U	35 U
Lead	52	93	427	288	600	90

Key at end of table.

recycled paper

4-21

ecology and environment

<p><b>Table 4-2</b></p> <p><b>EXPANDED SITE INVESTIGATION</b></p> <p><b>NDB/H-MARKER FACILITY</b></p> <p><b>LEVEL II SOIL SAMPLES</b></p> <p><b>XRF METALS RESULTS (mg/kg)</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>JUNE 1994</b></p>					
Sample ID (ANN94-):	ESN-SD-232	ESN-SB-232	ESN-SC-232	ESN-SD-260	ESN-SB-260
Depth BGS (inches):	0	12	24	0	12
Chromium	178 U	178 U	178 U	178 U	185
Manganese	409 U	409 U	409 U	421	409 U
Iron	16,524	22,239	20,520	14,508	393
Cobalt	174 U	174 U	174 U	174 U	174 U
Nickel	114	70	43	26 U	26 U
Copper	49 U	104	49 U	66	49 U
Zinc	461	1,078	532	1,079	418
Arsenic	75 U	89 U	44 U	33 U	33 U
Selenium	16 U	16 U	16 U	16 U	16 U
Molybdenum	3	6	4	2 U	2 U
Mercury	35 U	35 U	35 U	35 U	35 U
Lead	746	891	445	256	43

Key at end of table.

Table 4-2 (Cont.)

Table 4-2  
Page 9 of 9

Key:

BGS = Below ground surface.  
FAA = Federal Aviation Administration, Alaskan Region.  
ID = Identification.  
mg/kg = Milligrams per kilogram.  
NDB = Nondirectional beacon.  
SB = Subsurface soil 1 foot below ground surface.  
SC = Subsurface soil 2 feet below ground surface.  
SD = Surface soil.  
U = Element was undetected. Reported result is the instrument detection limit.  
XRF = X-ray fluorescence.

Table 4-3		
ESI SOIL SAMPLES		
LEVEL III TOTAL LEAD ANALYSIS		
NDB FACILITY		
ANNETTE ISLAND FAA STATION ESI		
ANNETTE ISLAND, ALASKA		
JUNE 1994		
(mg/kg)		
Sample Number (ANN94-)	Description	Lead
ESN-SD-400	Source: surface soil	580
ESN-SB-400	Source: subsurface soil 1 foot BGS	950
ESN-SD-401	Source: surface soil	530
ESN-SD-402	Source: surface soil	4,400
ESN-SD-403	Source: surface soil	67
ESN-SB-404	Source: subsurface soil 1 foot BGS	4,800
ESN-SB-405	Source: subsurface soil 1 foot BGS	240

<p><b>Table 4-4</b></p> <p><b>ESI SOIL AND SEDIMENT SAMPLES</b></p> <p><b>POSITIVELY IDENTIFIED INORGANIC COMPOUNDS</b></p> <p><b>LEVEL IV ANALYSIS</b></p> <p><b>NDB FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(mg/kg)</b></p>				
Sample Number (ANN94-):	ESN-SD-100	ESN-SB-100	ESN-SD-101	ESN-SE-100
<b>Metals</b>				
Aluminum	2,880	3,790	3,980	7,270
Arsenic	5.8	31.5	3.0	ND
Barium	145	81.2	61.6	17.0
Beryllium	0.12	0.13	0.11	0.16
Calcium	1,490 J	3,470 J	1,480 J	1,060
Chromium	57.1	118	298	8.4
Cobalt	28.3	73.6	5.7	4.7
Copper	35.1 J	86.7 J	26.1 J	4.0
Iron	15,500	38,600	9,760	4,820 J
Lead	1,990	1,040	2,450	10.3 J
Magnesium	34,900	129,000	6,140	4,890
Manganese	381	676	111	62.8
Nickel	159	592	23.7	22.5
Potassium	308	ND	603	ND
Selenium	0.56 J	2.3 J	ND	ND
Vanadium	12.0	15.7	11.8	12.8
Zinc	345 J	701 J	141 J	29.7

Key at end of table.

4-24

<p><b>Table 4-4</b></p> <p><b>ESI SOIL AND SEDIMENT SAMPLES</b></p> <p><b>POSITIVELY IDENTIFIED INORGANIC COMPOUNDS</b></p> <p><b>LEVEL IV ANALYSIS</b></p> <p><b>NDB FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(mg/kg)</b></p>				
Sample Number (ANN94-):	ESN-SE-101	ESN-SE-102	ESN-SE-103	ESN-SD-402
<b>Metals</b>				
Aluminum	1,950	5,160	10,200	NA
Arsenic	ND	1.3 J	1.0	NA
Barium	6.1	37.1	75.4	NA
Beryllium	ND	0.14	0.21	NA
Calcium	773	1,650	1,600	NA
Chromium	2.1	6.5	5.9	NA
Cobalt	ND	5.0	10.3	NA
Copper	ND	3.0	11.2	NA
Iron	3,720 J	16,300 J	18,300 J	NA
Lead	1.4 J	9.5 J	2.1 J	3,270 J
Magnesium	1,050	3,110	7,880	NA
Manganese	38.8	137	253	NA
Nickel	ND	33	7.6	NA
Potassium	ND	608	3,090	NA
Selenium	ND	ND	ND	NA
Vanadium	3.4	14.9	38.8	NA
Zinc	26.6	46.1	53.1	NA

**Key:**

J = Estimated concentration.  
 mg/kg = Milligrams per kilogram.  
 NA = Not analyzed.  
 SD = Surface soil.  
 SB = Subsurface soil.  
 SE = Sediment.

<p><b>Table 4-5</b></p> <p><b>ESI SOIL AND SEDIMENT, SAMPLES</b></p> <p><b>POSITIVELY IDENTIFIED DIOXIN ISOMERS, LEVEL IV ANALYSIS</b></p> <p><b>NDB FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(ng/kg)</b></p>				
Sample Number (ANN94-):	ESN-SD-100	ESN-SB-100	ESN-SD-101	ESN-SE-100
<b>Dioxin Isomers</b>				
1,2,3,4,6,7,8-HpCDD	ND	22.0	ND	ND
OCDD	182	85.4	88.7	ND
1,2,3,4,7,8-HxCDF	ND	4.64	ND	ND
1,2,3,6,7,8-HxCDF	ND	2.50	ND	ND
1,2,3,4,6,7,8-HpCDF	4.86	6.75	ND	ND
TEF	0.231	1.08	0.0887	0
Total TCDD	ND	ND	ND	ND
Total PeCDD	ND	ND	ND	51.3
Total HpCDD	28.3	22.0	ND	—
Total HxCDD	ND	ND	ND	130
Total TCDF	ND	ND	ND	78.9
Total HxCDF	ND	7.46	ND	ND
Total HpCDF	5.60	11.2	ND	ND

Key at end of table.

<p><b>Table 4-5</b></p> <p><b>ESI SOIL AND SEDIMENT, SAMPLES</b></p> <p><b>POSITIVELY IDENTIFIED DIOXIN ISOMERS, LEVEL IV ANALYSIS</b></p> <p><b>NDB FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(ng/kg)</b></p>			
Sample Number (ANN94-):	ESN-SE-101	ESN-SE-102	ESN-SE-103
<b>Dioxin Isomers</b>			
1,2,3,4,6,7,8-HpCDD	ND	ND	ND
OCDD	ND	ND	16.6
1,2,3,4,7,8-HxCDF	ND	ND	ND
1,2,3,6,7,8-HxCDF	ND	ND	ND
1,2,3,4,6,7,8-HpCDF	ND	ND	ND
TEF	0	0	0.0166
Total TCDD	ND	6.25	ND
Total PeCDD	ND	ND	ND
Total HpCDD	ND	ND	ND
Total TCDF	ND	3.75	ND
Total HxCDF	ND	14	ND
Total HpCDF	ND	ND	ND

**Key:**

- = Peaks were detected within detection time window, but they failed one or more criteria and are listed as EMPC.
- EMPC = Estimated maximum possible concentration.
- ND = Not detected.
- ng/kg = Nanograms per kilogram.
- SD = Surface soil.
- SB = Subsurface soil.
- SE = Sediment.
- TEF = Total equivalence factor.



4-28

<p align="center"><b>Table 4-6</b></p> <p align="center"><b>EXPANDED SITE INVESTIGATION SOIL AND SEDIMENT SAMPLES</b></p> <p align="center"><b>POSITIVELY IDENTIFIED ORGANIC COMPOUNDS, LEVEL IV ANALYSIS</b></p> <p align="center"><b>NDB FACILITY</b></p> <p align="center"><b>ANNETTE ISLAND FAA STATION</b></p> <p align="center"><b>ANNETTE ISLAND, ALASKA</b></p> <p align="center"><b>(µg/kg)</b></p>							
Sample Number (ANN94-):	ESN-SD-100	ESN-SB-100	ESN-SD-101	ESN-SE-100	ESN-SE-101	ESN-SE-102	ESN-SE-103
<b>BNA</b>							
Diethylphthalate	51 J	ND	ND	95	ND	ND	1,400
Phenanthrene	85 J	ND	ND	ND	ND	ND	ND
Fluoranthene	85 J	68 J	ND	ND	ND	ND	ND
Pyrene	80 J	82 J	92 J	ND	ND	ND	ND
Chrysene	ND	ND	41 J	ND	ND	ND	ND
Benzo(b)fluoranthene	43 J	51 J	47 J	ND	ND	ND	ND

**Key:**

BNA = Base neutral/acid extractable organic compound.

J = Estimated concentration.

µg/kg = Micrograms per kilogram.

ND = Not detected.

SE = Sediment sample.


SD = Soil sample.

SB = Subsurface soil.


<p>Table 4-7</p> <p>ESI SOIL AND SEDIMENT SAMPLES</p> <p>POSITIVELY IDENTIFIED TCLP METALS, LEVEL IV ANALYSIS</p> <p>NDB FACILITY</p> <p>ANNETTE ISLAND FAA STATION</p> <p>ANNETTE ISLAND, ALASKA</p> <p>(mg/L)</p>					
Sample Number (ANN94-):	ESN-SD-100	ESN-SB-100	ESN-SD-101	ESN-SD-402	Regulatory Limit
<b>Metals</b>					
Barium	0.75 J	1.2 J	0.78 J	NA	100.0
Cadmium	0.0053 J	ND	0.0066 J	NA	1.0
Chromium	0.031 J	ND	0.090 J	NA	5.0
Lead	3.0 J	1.5 J	1.2 J	14.3 J	5.0

Key:



J = Estimated.  
mg/L = Milligrams per liter.  
NA = Not analyzed.  
SD = Soil sample.  
SB = Subsurface soil sample.  
TCLP = Toxic characteristic leaching procedure.



Source: Ecology and Environment, Inc. 1994




KEY	
SD	= composite surface soil sample
SB	= grab soil sample at 1 foot BGS
SC	= grab soil sample at 2 feet BGS
X	= sample location




Ecology and Environment Inc.	
Figure: 4 - 2	Proj. No: VS1050
Date: 9-9-94	Drawn by: DEH
Title: Annette Island FAA Station FSI NDB Facility Level II XRF Screening Sample Locations June 1994	

Source: Ecology and Environment, Inc. 1994




← N




Ecology and Environment Inc.	
Figure: 4 - 3	Proj. No: VS1050
Date: 9-9-94	Drawn by: DEH
Title: Annette Island FAA Station ESI NDB Facility Level II XRF Screening Lead Results Map (mg/kg) June 1994	

Source: Ecology and Environment, Inc. 1994




KEY:	
●	= level IV sample location
▲	= level III sample location
SD	= composite surface soil sample
SB	= grab soil sample at 1 foot BGS




Ecology and Environment Inc.	
Figure: 4 - 4	Proj. No: VS1050
Date: 9-9-94	Drawn by: DEH
Annette Island FAA Station ESI NDB Facility Level III & IV Sample Location Map June 1994	

Source: Ecology and Environment, Inc. 1994




◀ N

KEY:	
1.2417	= TCLP Extractable lead (mg/l)
1,990/1,040	= surface/ 1 foot BGS TAL lead (mg/kg)
●	= level IV sample location
▲	= level III sample location
NA	= not analyzed
*	= TAL lead only reanalysis




SCALE IN FEET

Ecology and Environment Inc.	
Figure: 4 - 5	Proj. No: VS1050
Date: 9-9-94	Drawn by: DEH
Annette Island FAA Station ESI NDB Facility Level III & IV TAL and TCLP Lead Results Map June 1994	



## LOCATION MAP



## LEGEND

- SHORES
- SE-103 SAMPLE LOCATIONS (ANN94-ESN- )
- SURFACE WATER FLOW



APPROXIMATE SCALE IN FEET

0 500 1000 1500 2000

Ecology and Environment Inc.	
Figure: 4-6	Proj. No: VR1000
Date: 9/08/94	Drawn by: EGM
Title: ANNETTE ISLAND FAA STATION NDB FACILITY OVERLAND SURFACE WATER PATHWAY AND TARGET SAMPLE LOCATION MAP	



## **5. REMOTE CENTER AIR/GROUND COMMUNICATIONS FACILITY**

### **5.1 LOCATION AND DESCRIPTION**

The RCAG is an inactive facility located approximately 1.5 miles northwest of the north end of the runway on 5.7 acres (see Figures 2-1 and 5-1).

The RCAG facility consists primarily of Building 408, which is constructed of concrete block. Surrounding structures include an inactive 500-gallon gasoline UST, a live MPL transformer, two antenna towers and a former drum storage area. The surrounding property is mostly marsh and muskeg. A small pond is located south of Building 408. The RCAG has been operated by FAA since 1948.

The former drum storage area was the focus of the ESI sampling effort because the ECI conducted in August 1991 (E & E 1992b) identified the presence of TAL metals in soil samples which exceeded the three times background criteria for the EPA HRS model. The drum storage area was targeted for further investigation in the FAA SOW dated September 29, 1993. The drums were removed on 1993 (E & E 1993a), leaving an area of cleared brush approximately 65 feet south of building 408. The cleared area measured 65 feet long, in the north-south direction and varied in width on average of 20 feet.

### **5.2 EXPANDED SITE INVESTIGATION**

#### **5.2.1 Level IV Source and Target Sampling**

The potential source and surface water pathway for the former drum storage area was assessed. This potential CERCLA source was characterized by collecting three surface soil samples along the length of the clearing: ANN94ESR-SD-100 was collected near the west end; ANN94ESR-SD-101 near the center; and ANN94ESR-SD-102 near the east end. The sample locations are presented in Figure 5-1. All three samples were submitted for Level IV

analysis for TAL metals, TCL parameters, and TCLP metals. A sample summary is presented in Table 5-1 and the results of the analyses are presented in Tables 5-2 to 5-4.

Source samples contained the following concentrations of contaminants at greater than three times background concentrations: copper (481 mg/kg) and zinc (270 mg/kg) in ANN94ESR-SD-100; barium (20.1 mg/kg), copper (26.6 mg/kg), lead (22.6 mg/kg), magnesium (2,020 mg/kg), nickel (13.8 mg/kg), zinc (258 mg/kg), and toluene (957  $\mu$ g/kg) in ANN94ESR-SD-101; and magnesium (2,680 mg/kg), nickel (11.8 mg/kg), zinc (162 mg/kg), and toluene (93  $\mu$ g/kg) in ANN94ESR-SD-102. No compounds exceeded MSEC criteria.

The wetland adjacent to the RCAG facility was evaluated to determine whether it meets the criteria of a target wetland located in the surface water pathway according to the HRS model. One runoff pathway was identified that extended from the former drum storage area northeast to Smuggler Cove (see Section 5.2.4 for a complete discussion of the pathways). Samples were not collected at the point of entry into the wetland since the source samples were within the target wetland. Sediment samples were collected at approximately 0.1 mile and 0.2 mile downgradient of the source area and at the end of the drainage pathway at the beach at Smuggler Cove. The beach sample was collected from a surface beach area at the mean tide line. Sample locations are presented in Figure 5-2. In addition, one sediment sample was collected from the west side of the pond that is located on the west side of Building 408 (see Figure 5-1). Since the surface water pathway at this facility was difficult to ascertain due to the level terrain, this sample provided information due to potential cross-gradient migration.

No compounds were found to exceed three times background concentrations or MSEC criteria in samples collected from the northeasterly runoff pathway. Sample ANN94E-SB-SD-100, collected on the far side of the pond and west of Building 408, was found to contain the following compounds at concentrations that exceeded three times background: barium (16.2 mg/kg), calcium (3,500 mg/kg), copper (6.78 mg/kg), magnesium (3,230 mg/kg), nickel (17.5 mg/kg), zinc (89.4 mg/kg), toluene (1,000  $\mu$ g/kg) and xylene (120  $\mu$ g/kg). All of these compounds were detected in the source samples. Target sample results are presented in Tables 5-2 and 5-3.

### **5.2.2 Background Samples**

Background samples were collected for each distinct sample matrix (soil, sediment, and beach sediment) sampled. The matrices encountered at the RCAG included sandy sediment, peaty sediment, and beach sand. See Sections 2.7.1 and 4.2.4 for a discussion of the background samples.

### **5.2.3 Level IV TCLP Sampling**

Source samples ANN94ESR-SD-100, ANN94ESR-SD-101, and ANN94ESR-SD-102 were also submitted for Level IV TCLP metals analysis. The results are presented in Table 5-4. No samples were found to exceed TCLP regulatory limits.

### **5.2.4 Wetlands Survey**

The primary objective of the wetland survey was to identify wetlands 0.2 mile downgradient of the source. See Section 3.2.1.3 for the definition of a wetland and a discussion of Annette Island wetlands. The RCAG sits on a gravel pad vegetated by upland species. It is surrounded by a large shore pine-yellow cedar muskeg wetland complex. A pond lies northwest of the RCAG. The potential source of contaminants was the former drum storage area located in a small depression within the wetland complex immediately adjacent to south edge of the gravel pad.

Since the potential source was in a wetland, the size of the wetland was determined. In addition, the source was in a depression that was part of a larger wetland complex. Defined drainage patterns existed into and out of the depression; therefore, only the size of the depression was determined and not the entire wetland complex. The depression was 1,340 square feet or 0.031 acres in size. The wetlands in the immediate vicinity of the source were separated by microtopographic changes. The depressional wetland contained shore pine and sweet gale in the shrub/scrub layer and deer cabbage, evergreen huckleberry, false lily of the valley, and sphagnum moss in the herbaceous layer. No tree stratum was present. Trees in the depressional wetland appeared to have been cut down. The soils in this wetland were organic, and standing water was encountered within 12 inches of the ground surface in a soil pit. On the north and east sides of the depressional wetland, yellow cedars approximately 50 feet in height, shore pines, and evergreen huckleberries grew on a topographic rise in an organic soil. Sitka alders grew on a topographic rise on the south side of the depression and separated the source depression from another depression which sloped towards the pond. This

depression was dominated by labrador tea. The overland surface water drainage pathway is shown in Figures 3-4 and 5-2.

From the depression, the direction of drainage was to the northeast for approximately 30 feet, at which point the slope of the terrain increased. The drainage followed the slope of a hill and began to channelize. At the base of the hill was an open water area which drained to the northeast. The side of the hill and open water area are in a shore pine-cedar muskeg wetland complex. A channel exited the openwater area to the northwest. ANN94ESR-SE-101 was collected approximately 0.1 mile from the source in this channel. The channel contained approximately 6 inches of water, was approximately 2.5 feet deep, and contained organic and sandy soils. At this sampling location, the predominant vegetation included yellow cedar, shore pine, and western redcedar in the tree stratum; sweet gale, labrador tea, and fool's huckleberry in the shrub stratum; and deer cabbage, skunk cabbage, false lily of the valley, black lily (*Fritillaria camschatcensis*), dwarf dogwood, labrador tea, and sphagnum moss in the herbaceous layer.

The stream channel then entered a forested wetland. The stream channel meandered through the forested wetland and eventually drained into an estuarine pond that drained into the ocean. ANN94ESR-SE-102 was collected in the forested wetland approximately 0.2 mile downgradient of the source and within an approximate 3-foot-deep stream channel, that contained approximately 6 inches of water. The stream channel consisted of a sandy gravelly substrate, and the stream banks were composed of organic soils. No vegetation was growing within the stream channel. Yellow cedars, western redcedar, and hemlock grew in the tree and shrub/shrub strata on the channel banks. Skunk cabbage and sphagnum moss dominated the herb layer on the channel banks.

ANN94ESR-SE-103 was collected on the beach below the high tide line and within the flow of water from the stream drainage. The sample was collected downgradient of a pond and an apparent estuarine marsh and was composed of sand and gravel.

#### **5.2.5 Deviations From the Work Plan**

All work at the RCAG facility was performed as specified in the ESI work plan except that the surface water runoff pathway was thought to be the same for both the RCAG and the NDB/H-marker facilities. After inspecting the pathway, it was determined that they were separate, and three additional sediment samples and one additional beach sample were required to characterize the pathway at the RCAG.

#### **5.2.6 ESI Conclusions and Recommendations**

There are no ESI concerns at the RCAG facility that require further action.

### **5.3 INTERIM CLEANUP ACTIVITY**

#### **5.3.1 Field Activities**

The IC activity was performed as specified in the IC work plan. The abandoned 500-gallon gasoline UST was pumped-out in preparation for the decommissioning of the tank. The location of the tank is shown in Figure 5-1. One hundred gallons of fuel were estimated to be present at the time of the work plan preparation; however, when the tank was inspected during the IC, it was found to be empty. Approximately 5 gallons of water (and a minor amount of fuel) was pumped from the tank into a 55-gallon drum. A local resident, who anticipated taking the fuel from the tank for personal use, took the 55-gallon drum. He planned to allow the water to evaporate and use the drum for fuel storage. The empty UST was capped and locked.

#### **5.3.2 Conclusions and Recommendations**

The IC project was completed. Further action is required to decommission the empty UST according to ADEC regulations.

Table 5-1

**EXPANDED SITE INVESTIGATION SAMPLE SUMMARY  
RCAG FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA**

Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ESR-SD-100	Soil	VOC, BNA, Pest/PCB, TAL metals, TCLP Metals	ASC/Level IV	Source sample. SSE of Building
ESR-SD-101	Soil	VOC, BNA, Pest/PCB, TAL metals, TCLP Metals	ASC/Level IV	Source sample. SE of building
ESR-SD-102	Soil	VOC, BNA, Pest/PCB, TAL metals, TCLP Metals	ASC/Level IV	Source sample. S of building.
ESR-SE-101	Stream sediment	VOC, BNA, Pest/PCB, TAL metals	ASC/Level IV	Wetland. 0.1 mile downgradient and east of source.
ESR-SE-102	Stream sediment	VOC, BNA, Pest/PCB, TAL metals	ASC/Level IV	Wetland. 0.2 mile downgradient and east of source.
ESR-SE-103	Beach sediment	VOC, BNA, Pest/PCB, TAL metals	ASC/Level IV	Beach at end of drainage.
ESB-SD-100	Peaty sediment	VOC, BNA, Pest/PCB, TAL metals	ASC/Level IV	Wetland. Across pond west of building.

Key:

ASC = Analytical Service Center.  
 BNA = Base neutral/acid extractable organic compound.  
 Pest/PCB = Organochlorine pesticides/polychlorinated biphenyls.  
 SD = Surface Soil.  
 SE = Sediment.  
 TAL metals = Target Analyte List metals.  
 TCLP metals = Toxic Characteristic Leaching Procedure Metals.  
 VOC = Volatile organic compound.

<p><b>Table 5-2</b></p> <p><b>ESI SOIL AND SEDIMENT SAMPLES</b></p> <p><b>POSITIVELY IDENTIFIED INORGANIC COMPOUNDS,</b></p> <p><b>LEVEL IV ANALYSIS</b></p> <p><b>RCAG FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(mg/kg)</b></p>				
Sample Number (ANN94-):	ESR-SE-103	ESB-SD-100	ESR-SD-100	ESR-SD-101
<b>Metals</b>				
Aluminum	5,550	811	807	676
Arsenic	ND	ND	ND	ND
Barium	66.9	16.2	ND	20.1
Beryllium	0.13	ND	ND	ND
Calcium	1,450	3,500 J	805 J	4,850 J
Chromium	1.7	ND	ND	ND
Cobalt	5.4	ND	ND	ND
Copper	4.3	6.7 J	481 J	26.6 J
Iron	8,480 J	1,560	1,100	1,170
Lead	ND	14.2 J	ND	22.6 J
Magnesium	4,010	3,230	863	2,020
Manganese	134	16.5	4.3	11.2
Nickel	4.1	17.5	ND	13.8
Potassium	1,720	ND	ND	ND
Vanadium	21.6	ND	ND	ND
Zinc	21.4	89.4 J	270 J	258 J

<p><b>Table 5-2</b></p> <p><b>ESI SOIL AND SEDIMENT SAMPLES</b></p> <p><b>POSITIVELY IDENTIFIED INORGANIC COMPOUNDS,</b></p> <p><b>LEVEL IV ANALYSIS</b></p> <p><b>RCAG FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(mg/kg)</b></p>			
Sample number (ANN94-)	ESR-SD-102	ESR-SE-101	ESR-SE-102
<b>Metals</b>			
Aluminum	858	6,780	2,910
Arsenic	ND	0.75	1.8 J
Barium	11.6	21.4	10.4
Beryllium	ND	0.15	0.07
Calcium	1,140 J	1,960	946
Chromium	ND	6.4	4.1
Cobalt	ND	6.3	2.3
Copper	4.7 J	8.8	2.8
Iron	942	8,950 J	4,450 J
Lead	7.9 J	2.3 J	2.3 J
Magnesium	2,680	4,590	1,640
Manganese	9.5	154	77.3
Nickel	11.8	6.5	5.2
Potassium	ND	335	ND
Vanadium	ND	21.1	8.3
Zinc	162 J	43.6	29.6

Key:

J = Estimated concentration.  
 mg/kg = Milligrams per kilogram.  
 ND = Not detected.  
 SE = Sediment sample.  
 SD = Soil sample.



<p><b>Table 5-3</b></p> <p><b>EXPANDED SITE INVESTIGATION SOIL AND SEDIMENT SAMPLES</b></p> <p><b>POSITIVELY IDENTIFIED ORGANIC COMPOUNDS, LEVEL IV ANALYSIS</b></p> <p><b>RCAG FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(µg/kg)</b></p>							
Sample Number (ANN94-)	ESR-SD-100	ESR-SD-101	ESR-SD-102	ESR-SE-101	ESR-SE-102	ESR-SE-103	ESB-SD-100
<b>VOCs</b>							
Toluene	15 B	57 J	93 J	ND	ND	ND	1,000
Total Xylenes	11 J	ND	ND	ND	ND	ND	120
<b>BNA</b>							
Phenanthrene	ND	1,400 J	ND	ND	ND	ND	380 J
Anthracene	ND	200 J	ND	ND	ND	ND	ND
Fluoranthene	ND	790 J	ND	ND	ND	ND	380 J
Pyrene	ND	1,400 J	ND	ND	ND	ND	ND
Chrysene	ND	520 J	ND	ND	ND	ND	ND

**Key:**

B = Blank contamination.  
 BNA = Base neutral/acid extractable organic compound.  
 J = Estimated concentration.  
 µg/kg = Micrograms per kilogram,  
 ND = Not detected.  
 SE = Sediment sample  
 SD = Soil Sample  
 VOCs = Volatile organic compounds.

Table 5-4			
EXPANDED SITE INVESTIGATION SOIL AND SEDIMENT SAMPLES POSITIVELY IDENTIFIED TCLP METALS, LEVEL IV ANALYSIS RCAG FACILITY ANNETTE ISLAND FAA STATION ANNETTE ISLAND, ALASKA (mg/L)			
Sample Number (ANN94-):	ESR-SD-100	ESR-SD-101	ESR-SC-102
Barium	0.93 J	0.67 J	0.73

Key:


J = Estimated concentration.  
mg/L = Milligram per liter.  
SD = Soil sample.  
TCLP = Toxic Characteristic Leaching Procedure.



Source: Ecology and Environment, Inc. 1994

recycled paper

5-11

ecology and environment






LEGEND

- SHORES
- SAMPLE LOCATIONS (ANN94-ESR- )
- SURFACE WATER FLOW



APPROXIMATE SCALE IN FEET



Ecology and Environment Inc.	
Figure: 5-2	Proj. No: VR1000
Date: 9/08/94	Drawn by: EGM
Title: ANNETTE ISLAND FAA STATION RCAG FACILITY OVERLAND SURFACE WATER PATHWAY AND TARGET SAMPLE LOCATION MAP	

## **6. HANGAR FACILITY**

### **6.1 LOCATION AND DESCRIPTION**

The Hangar facility is located near the south end of the north-south runway (See Figure 1-2). It is currently being used for storage of lumber by the Metlakatla Indian Community. The Hangar facility is located on property formerly leased by FAA. An ECI conducted in August 1991 (E & E 1992b) identified the presence of several PCB-containing transformers in a room on the northeast corner of the building, (see Figure 6-1). The transformers were removed in 1992 under Task Order No. 13 (E & E 1993a).

### **6.2 INTERIM CLEANUP**

#### **6.2.1 Field Activities**

The hangar-floor PCB remediation program required the cleanup of a small section of the northeast room within the Hangar facility (Figure 6-2). The estimated area of the affected floor was 200 square feet. The initial task was to sweep the affected area to remove sawdust, paint chips, and debris. The debris was analyzed with the XRF and was found to contain a total lead concentration of 2,430 ppm. The source of the lead containing material appeared to be paint chips peeled from facility walls. The floor sweepings were containerized, manifested, and disposed of as hazardous material. The shipping manifests are presented in Appendix E of Volume 2.

Following the general floor sweeping, the stained areas were cleaned using PES-51 citrus-based-solvent. The stained areas were repeatedly scrubbed and wiped with absorbent pads until the stain was no longer visible. In the process of removing the stains, the painted surface was also removed leaving bare concrete. The floor cleaning was followed by the collection of three wipe samples in accordance with EPA Region X PCB wipe sample protocol. These samples were analyzed in the field using an ENSYS PCB RISC wipe test kit

and all were found to contain less than  $10 \mu\text{g}/100 \text{ cm}^2$  of PCB, which is EPA's action level for indoor low-contact impervious surfaces. ENSYS PCB RISC analysis protocol is presented in Appendix F.5.

Confirmation samples were then collected from each of the three areas that had been field tested, and the samples were submitted to an analytical laboratory for quick-turnaround confirmation analysis. The confirmation samples were numbered ANN94ICH-OI-400 through ANN94ICH-OI-403. Sample ANN94ICH-OI-403 was submitted as a blank QC sample. The location of the samples are shown in Figure 6-2 along with the analytical results. The confirmation analysis indicated that PCBs were present in much higher concentration, ranging from 456 to  $4,590 \mu\text{g}/100 \text{ cm}^2$ , even though the field screening results indicated  $< 10 \mu\text{g}/100 \text{ cm}^2$  PCB. PCBs were not detected in the blank sample. A summary of samples collected at the Hangar facility are presented in Table 6-1.

Because the stained areas exceeded the  $10 \mu\text{g}/100 \text{ cm}^2$  criteria, the study area was recleaned using hexane, a stronger solvent. Confirmation samples were again collected and submitted for quick-turnaround laboratory analysis. The confirmation samples were numbered ANN94ICH-OI-430 through ANN94ICH-OI-433. Sample ANN94ICH-OI-432 was submitted as a blank QC sample. The location of the samples are shown in Figure 6-2 along with the analytical results. In general, the concentration of Aroclor 1260 was decreased by the second cleaning; however, the concentrations still remained greater than  $100 \mu\text{g}/100 \text{ cm}^2$ . PCBs were not detected in the blank sample. Sample results are presented in Table 6-2.

The PCB-contaminated sampling and wipe material from the initial cleaning and the lead contaminated floor sweepings were contained in one 55-gallon drum, manifested and shipped by the subcontractor in compliance with applicable EPA regulations. The material was transported from Annette Island by licensed chartered aircraft to Anchorage and transferred to an approved RCRA disposal facility. The shipment manifest was provided to FAA and the mandatory EPA PCB importation letter will be forwarded to EPA as prescribed in the regulations. The shipping manifests are presented in Appendix E of Volume 2.

The PCB-contaminated sampling and wipe material from the second cleaning was contained in one 30-gallon drum and placed in the hazardous materials storage building located at the VORTAC/DF facility (Figure 3-1). The drum will be stored there until it can be transferred to a RCRA disposal facility.

### **6.2.2 Deviations From Work Plan**

All work at the Hangar facility was performed in accordance with the IC work plan. As discussed in Section 6.2.3, the PCB contamination that remains following the cleaning of the Hangar floor, requires additional remediation.

### **6.2.3 Conclusions and Recommendations**

The floor cleaning procedure used in the Hangar facility was ineffective in reducing PCB concentrations to less than 10  $\mu\text{g}/100\text{cm}^2$ . Additional cleaning or removal of the concrete floor may be required to completely remediate the contaminated area.

<p align="center"><b>Table 6-1</b></p> <p align="center"><b>INTERIM CLEANUP SAMPLE SUMMARY</b></p> <p align="center"><b>HANGAR FACILITY</b></p> <p align="center"><b>ANNETTE ISLAND FAA STATION</b></p> <p align="center"><b>ANNETTE, ALASKA</b></p>				
<b>Sample No. (ANN94-)</b>	<b>Matrix</b>	<b>Analytical Parameters</b>	<b>Laboratory</b>	<b>Comments</b>
ICH-OI-200	PCB wipe	PCB	Field	See Figure 6-2 for location.
ICH-OI-201	PCB wipe	PCB	Field	See Figure 6-2 for location.
ICH-OI-202	PCB wipe	PCB	Field	See Figure 6-2 for location.
ICH-OI-400	PCB wipe	PCB	NTL	See Figure 6-2 for location.
ICH-OI-401	PCB wipe	PCB	NTL	See Figure 6-2 for location.
ICH-OI-402	PCB wipe	PCB	NTL	See Figure 6-2 for location.
ICH-OI-403	PCB wipe	PCB	NTL	Blank
ICH-OI-430	PCB wipe	PCB	NTL	See Figure 6-2 for location
ICH-OI-431	PCB wipe	PCB	NTL	See Figure 6-2 for location.
ICH-OI-432	PCB wipe	PCB	NTL	Blank
ICH-OI-433	PCB wipe	PCB	NTL	See Figure 6-2 for location.

**Key:**

NTL = Northern Testing Laboratories.  
PCB = Polychlorinated biphenyl.



recycled paper

6-5

ecology and environment

Table 6-2


**INTERIM CLEANUP PCB WIPE SAMPLES  
POSITIVELY IDENTIFIED PCBs,  
LEVEL III ANALYSIS  
HANGAR FACILITY  
ANNETTE ISLAND FAA STATION  
ANNETTE ISLAND, ALASKA  
( $\mu\text{g}/100 \text{ cm}^2$ )**

Sample Number (ANN94-):	ICH-OI-400	ICH-OI-401	ICH-OI-402	ICH-OI-403 (blank)	ICH-OI-430	ICH-OI-431	ICH-OI-432 (blank)	ICH-OI-433
<b>PCB</b>								
Aroclor 1260	456	4,590	3,820	ND	1,080	633	ND	1,110

Key:


ND = Not detected.

Source: Ecology and Environment, Inc. 1994



NOTE: Building Not To Scale

SOURCE: Field observation



Ecology and Environment, Inc.

Figure: 6-1


Proj. No.: VS1000

Date: 5-25-94

Drawn By: JAL

Title: Annette Island FAA Station  
Hangar Facility Site Map

Source: Ecology and Environment, Inc. 1994



Sample Number ANN-94-ICH-OI-

KEY	
Note: Only Arochlor 1260 was detected.	
<input type="checkbox"/>	Wipe Sample
ND	Not Detected



## Ecology and Environment, Inc.

Figure: 6-2 Proj. No.: VS1050

Date: 10-18-94 Drawn By: DEH

Title: Annette Island FAA Station IC  
Hangar Facility  
Wipe Sample Location and  
Results Map  
June 1994

## **7. APPROACH LIGHTING SYSTEM (ALS) FACILITY**

### **7.1 LOCATION AND DESCRIPTION**

The ALS Facility is located north of the north end of the north-south runway (See Figure 1-2), on property formerly leased by FAA prior to 1973. An ECI conducted in August 1991 (E & E 1992b) identified the presence of 15 towers on the property. During the ESI, an additional structure, a Short Approach Lighting System Runway End Identification Lights (SALSR) was identified. The SALSR is a steel building mounted on skids and it contained a number of oil-filled electrical transformers and related electrical equipment. A diagram showing the location of the electrical equipment in the building is presented in Figure 7-1. It was determined by the FAA CO at the time of the IC investigation that oil samples should be collected from the electrical equipment, if possible, and submitted for PCB analysis.

### **7.2 INTERIM CLEANUP**

#### **7.2.1 Field Activities**

Electrical equipment in the SALSR building was examined to determine if it contained oil. In a few instances, holes were drilled in small sealed units that could not be opened. A description of the electrical equipment found in the SALSR is summarized in Table 7-1. Of the oil containing units, all were sampled except for three sealed capacitors (approximately 5 gallons each) that could not be accessed. Nine oil samples were collected, and the samples were numbered ANN94ICS-OI-410 through ANN94ICS-418. A sample summary is presented in Table 7-2. The analytical results are presented in Table 7-3, and the locations of the samples are shown on Figure 7-1. PCB concentrations were less than 50 mg/kg in all samples except sample ANN94ICS-OI-417, which was collected from a large 100-gallon transformer located at the northwest corner of the building. Sample ANN94ICS-OI-417 contained 70 mg/kg of Aroclor-1260.

### **7.2.2 Deviations from the Work Plan**

The ALS facility was not included in the ESI/IC work plan. As mentioned previously, the SALSr was first identified during the ESI/IC activity, and the decision to investigate it was made in the field.

### **7.2.3 Conclusions and Recommendations**

The entire SALSr, including the oil-containing electrical equipment, is no longer in use and requires removal in accordance with FAA's good-housekeeping protocol. The 100-gallon transformer containing PCBs at a concentration of 70 mg/kg should be removed and disposed of according to EPA TSCA regulations. The three 5-gallon capacitors which were not sampled should be considered as PCB-containing and included with the PCB oil for removal.

**Table 7-1**  
**INTERIM CLEANUP**  
**ELECTRICAL EQUIPMENT INVENTORY**  
**ALS FACILITY**  
**ANNETTE ISLAND FAA STATION**  
**ANNETTE ISLAND, ALASKA**  
**JUNE 1994**

Component	Serial Number	Manufacturer	Gallons of Oil	Sample No. (ANN94-)	Dimensions
Transformer	61AC5867	Westinghouse	8	ICS-OI-410	2.5' × 2.5' × 8' tall
Transformer	12-1960	Electric Specialty	1	ICS-OI-411	1' × 1' × 2.5' tall
Transformer	12-1960	Electric Specialty	1	ICS-OI-412	1' × 1' × 2.5' tall
Transformer	60M5938	Westinghouse	8	ICS-OI-413	3' × 3' × 3.5' tall
Circuit breaker	940017J	Westinghouse	5	ICS-OI-414	1.5' × 1.5' × 2.5' tall
Transformer	None	Unknown	100	ICS-OI-415/418 (Dup)	2' × 3' × 4' tall
Transformer	None	Unknown	100	ICS-OI-416	2' × 3' × 4' tall
Transformer	None	Unknown	100	ICS-OI-417	2' × 3' × 4' tall
Capacitor	None	Unknown	1	Not sampled.	—
Capacitor	None	Unknown	1	Not sampled.	—
Capacitor	None	Unknown	1	Not sampled.	—

Key:

PCB =Polychlorinated biphenyls.

<p><b>Table 7-2</b></p> <p><b>INTERIM CLEANUP SAMPLE SUMMARY</b></p> <p><b>ALS FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p>				
Sample No. (ANN94-)	Matrix	Analytical Parameters	Laboratory	Comments
ICS-OI-410	Oil	PCB	ASC, Level III	Transformer oil
ICS-OI-411	Oil	PCB	ASC, Level III	Transformer oil
ICS-OI-412	Oil	PCB	ASC, Level III	Transformer oil
ICS-OI-413	Oil	PCB	ASC, Level III	Transformer oil
ICS-OI-414	Oil	PCB	ASC, Level III	Transformer oil
ICS-OI-415	Oil	PCB	ASC, Level III	Transformer oil
ICS-OI-416	Oil	PCB	ASC, Level III	Transformer oil
ICS-OI-417	Oil	PCB	ASC, Level III	Transformer oil
ICS-OI-418	Oil	PCB	ABC, Level III	Duplicate of ICS-OI-415

**Key**

ASC = Analytical Services Center.  
PCB = Polychlorinated biphenyls.


<p><b>Table 7-3</b></p> <p><b>INTERIM CLEANUP OIL SAMPLES</b></p> <p><b>POSITIVELY IDENTIFIED PCB COMPOUNDS - LEVEL III</b></p> <p><b>ALS FACILITY</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p> <p><b>(mg/kg)</b></p>			
Sample Number (ANN94-)	Type	PCB-1254	PCB-1260
ICS-OI-410	8 gallon transformer	ND(5.0)	ND(5.0)
ICS-OI-411	1 gallon transformer	ND(5.0)	ND(5.0)
ICS-OI-412	1 gallon transformer	7.7	ND(5.0)
ICS-OI-413	8 gallon transformer	ND(5.0)	3.7
ICS-OI-414	5 gallon circuit breaker	ND(5.0)	13
ICS-OI-415	100 gallon transformer	ND(5.0)	25
ICS-OI-416	100 gallon transformer	ND(5.0)	26
ICS-OI-417	50 gallon transformer	ND(10.0)	70
ICS-OI-418	Duplicate of ICS-OI-415	ND(5.0)	27

Key:

ND = Not detected.



Source: Ecology and Environment, Inc. 1994



## **8. GLIDE SLOPE TRANSMITTER (GS) FACILITY**

### **8.1 LOCATION AND DESCRIPTION**

The GS facility is located on formerly leased property on the east side of the north-south runway near the north end (see Figure 1-2). The facility consists of Building 405 and associated electrical equipment. FAA's lease ended in 1973 and the facility is inactive. An ECI conducted in August 1991 (E & E 1992b) identified the presence of an abandoned transformer in a transclosure next to building 405. The oil in the transformer was tested during the ECI and found to contain less than 50 mg/kg PCB. Consequently, it was not removed during the removal action in 1992 (E & E 1993a). During the ESI, however, the transformer was inspected and found to be in disrepair, and the decision was made by the FAA CO that the oil should be removed and disposed of to prevent future spillage.

### **8.2 INTERIM CLEANUP ACTIVITIES**

#### **8.2.1 Field Activities**

Approximately 15 gallons of non-PCB oil were pumped from the abandoned transformer into a 55-gallon drum. Sorbent pads were then used to clean the transformer of the remaining oil. The sorbent material and all pumping equipment were then triple-bagged for disposal. The drummed oil and all waste material were manifested and shipped by the subcontractor in compliance with applicable EPA regulations. The material was transported from Annette Island by licensed chartered aircraft to Anchorage and transferred to an approved RCRA disposal facility. The shipment manifest was provided to FAA and the mandatory EPA PCB importation letter will be forwarded to EPA as prescribed in the regulations. A copy of the shipping manifest is presented in Appendix E, Volume 2.

### **8.2.2 Deviations From the Work Plan**

The GS facility was not included in the ESI/IC work plan. As mentioned previously, the transformer was found in disrepair, and the decision to remove the non-PCB oil from it was made during the ESI/IC activity.

### **8.2.3 Conclusions and Recommendations**

The empty transformer should be disposed of as part of FAA's good housekeeping practice.

## **9. LOCALIZER (LOC) FACILITY**

### **9.1 LOCATION AND DESCRIPTION**

The LOC facility is located southwest of the south end of the north-south runway on property formerly leased by FAA (see Figure 1-2). All that remains at this facility is an abandoned building in disrepair.

### **9.2 INTERIM CLEANUP ACTIVITIES**

#### **9.2.1 Field Activities**

During the ESI, five small, sealed (less than 1 gallon) transformers, which appeared to contain oil, were discovered lying on the ground next to the building. At the direction of the FAA CO, the transformers were collected and placed in a 30-gallon drum for storage in the hazardous materials storage building located at the VORTAC/DF facility.

#### **9.2.2 Deviations From the Work Plan**

The LOC facility was not included in the ESI/IC work plan. Authorization for work performed at this facility was made by the FAA CO during the ESI/IC activity.

#### **9.2.3 Conclusions and Recommendations**

No further action is required at the LOC facility.

## **10. STATION RECOMMENDATION SUMMARY**

This section presents recommendations for the entire Annette Island FAA Station and reflects the information and conclusions discussed in the facility-specific conclusions and recommendations sections. A concise summary of the recommendations is provided in Table 10-1. Facilities investigated are described in detail in Sections 3 through 9.

### **10.1 VORTAC/DF FACILITY**

#### **10.1.1 Expanded Site Investigation**

Based on sample results, further action is recommended to address lead contamination that exceeded MSEC and TCLP criteria in source samples. Approximately 300 cubic yards of soil are potentially affected.

### **10.2 NDB/H-MARKER FACILITY**

#### **10.2.1 Expanded Site Investigation**

Based on sample results, further action is recommended to address lead contamination that exceeded MSEC and TCLP criteria in source samples. Approximately 150 cubic yards of soil are potentially affected. Since access to this facility is not restricted, steps should be taken to contain the contaminated soil and control access to it.

### **10.3 RCAG FACILITY**

#### **10.3.1 Expanded Site Investigation**

No CERCLA-regulated contaminants exceeded MSEC or TCLP regulatory criteria at the RCAG facility. No further action is recommended for this facility.

### **10.3.2 Interim Cleanup**

Further action is required to decommission the empty UST according to ADEC regulations.

## **10.4 HANGAR FACILITY**

### **10.4.1 Interim Cleanup**

Additional cleaning or removal of the Hangar floor is required to remediate the area according to TSCA regulations.

## **10.5 ALS FACILITY**

### **10.5.1 Interim Cleanup**

Further action is required to remove an inactive PCB-containing transformer according to TSCA regulations. In addition, action is required to remove non-PCB containing inactive electrical equipment according to FAA's good housekeeping practices.

## **10.6 GS FACILITY**

### **10.6.1 Interim Cleanup**

Further action is required to dispose of an empty transformer according to FAA good housekeeping practices.

## **10.7 LOC FACILITY**

### **10.7.1 Interim Cleanup**

No further action at the LOC facility is required.

## **10.8 ADDITIONAL RECOMMENDATIONS**

There are no additional recommendations regarding the Annette Island FAA Station.

<p><b>Table 10-1</b></p> <p><b>STATION RECOMMENDATIONS</b></p> <p><b>ANNETTE ISLAND FAA STATION</b></p> <p><b>ANNETTE ISLAND, ALASKA</b></p>		
Facility	ESI	IC
VORTAC/DF	Address lead contamination on gravel pad.	An IC was not conducted at this facility.
NDB/H-Marker	Address lead contamination in soil next to old building foundation. Contain and control contaminated soil.	An IC was not conducted at this facility.
RCAG	No further investigation is recommended.	Decommission UST per ADEC regulations.
Hangar	An ESI was not conducted at this facility. No conditions requiring investigation were observed during IC field operations.	Reclean or remove PCB-contaminated floor.
ALS	An ESI was not conducted at this facility. No conditions requiring investigation were observed during IC field operations.	Remove PCB and non-PCB containing electrical equipment.
GS	An ESI was not conducted at this facility. No conditions requiring investigation were observed during IC field operations.	Remove non-PCB containing transformer.
LOC	An ESI was not conducted at this facility. No conditions requiring investigation were observed during IC field operations.	No further action is recommended at this facility.

**Key:**

ALS = Airport lighting system.  
 ESI = Expanded Site Investigation.  
 FAA = Federal Aviation Administration, Alaskan Region,  
 GS = Glide slope.  
 IC = Interim Cleanup.  
 LOC = Localizer.  
 NDB = Nondirectional beacon.  
 VORTAC/DF = Very high frequency omnidirectional range tactical air/ground communications/directional finder.

## 11. REFERENCES

- Alaska Department of Community and Regional Affairs (ADCRA), 1984, Metlakatla, prepared by Calista Professional Services.
- Alaska Department of Environmental Conservation (ADEC), 1992, *Draft Method for Determination of Gasoline-Range Organics (GRO)*, Juneau, Alaska.
- \_\_\_\_\_, 1991, *Interim Guidance for Non-UST Contaminated Soil*.
- Alaska, Department of Natural Resources (ADNR), May 21, 1991, letter to M. Nesterenko, Ecology and Environment, Inc., Cultural Resources at 19 FAA Facilities, File Number 3130-IR FAA.
- American Society for Testing and Materials (ASTM), 1989, *Standard Practice for Description and Identification of Soils (Visual-Manual Procedure)*, Philadelphia, Pennsylvania.
- Barth, D.S., and B.J. Mason, May 1984, *Soil Sampling Quality Assurance Users Guide*, EPA 600/4-84-043, USEPA, Environmental Monitoring Systems Laboratory, P.O. Box 15027, Las Vegas, Nevada.
- Code of Federal Regulations (CFR), 1990, Title 40, Part 300, Hazard Ranking System, Final Rule, United States Government Printing Office, Washington, DC.
- Eberhardt, W., 1988, FAA Hazardous Waste Program Manager (AAL-463H), Memo regarding site visit to Annette Island to David Epstein, Supervisor (AAL-463), March 18, 1988.
- Ecology and Environment, Inc. (E & E), 1993a, *Trip Report, Federal Aviation Administration Hazardous Waste Removal/Disposal Project, Annette Island FAA Station, Contract No. DTFA 04-90-C-20014*, Task Order No. 13, prepared for the Alaska Department of Transportation, Federal Aviation Administration, 222 West 7th Avenue, No. 14, Anchorage, Alaska 99513, September.
- \_\_\_\_\_, 1993b, *Expanded Site Investigation Work Plan*, Federal Aviation Administration, Annette Island, Alaska, Federal Aviation Administration (FAA), Annette Island FAA Station File, Hazardous Materials Branch, Anchorage, Alaska.



\_\_\_\_\_, 1992a, Master Compliance Plan (MCP), Facilities Environmental Compliance Program, FAA Alaskan Region, Anchorage, Alaska.

\_\_\_\_\_, 1992b, *Environmental Compliance Investigation Report for the Annette Island FAA Facility*, Annette Island, Alaska.

\_\_\_\_\_, 1992c, *Generic Work Plan for Conducting Environmental Investigations at Federal Aviation Administration Alaska Flight Service Stations*, Anchorage, Alaska.

Harding Lawson Associates (HLA), 1990, FAA UST Management Report for Annette Island, Anchorage, Alaska.

Reed, P. B., 1988, *National List of Plant Species that Occur in Wetlands: Alaska (Region A)*; National Wetlands Inventory, U.S. Fish and Wildlife Service, U.S. Department of Interior.

State of Alaska, 1992, *Alaska Administrative Code, Title 11, Natural Resources*, Juneau, Alaska.

\_\_\_\_\_, 1991, *Alaska Administrative Code, Title 18, Environmental Conservation*, revised October 1992, Juneau, Alaska.

United States Army Corps of Engineer (USACE), 1990, *Pre-Design Report, Phase II Field Investigation, Annette Island Landing Field, Annette Island, Alaska*, Contract No. DACA85-88-D-0014, Delivery Order No. 13, prepared by Ecology and Environment, Inc.

United States Department of Agriculture (USDA), 1979, *Exploratory Soil Survey of Alaska*, Soil Conservation Service,

United States Environmental Protection Agency (EPA), 1994, Revised Interim Soil Lead Guidance for CERCLA Sites and RCRA Corrective Action Facilities, OSWER Directive # 9355.4-12, July 14, 1994.

\_\_\_\_\_, 1991a, *Risk Assessment Guidance for Superfund, Volume I: Human Health Evaluation, Supplemental Guidance, Standard Default Exposure Factors*, Washington, D.C.

\_\_\_\_\_, 1991b, *Risk Assessment Guidance for Superfund, Volume 1: Human Health Evaluation Manual, Supplemental Guidance, Standard Default Exposure Factors, Interim Final*, Office of Emergency and Remedial Response, OSWER Directive No. 9285.6-03.

\_\_\_\_\_, 1991c, *Preliminary Assessment/Site Investigation (PA/SI) Data Requirements for Federal Facility Docket Sites*.

\_\_\_\_\_, 1990, *Test Methods for Evaluating Solid Waste*, SW-846, Third Edition, Washington, D.C.

\_\_\_\_\_, 1987, *Data Quality Objectives for Remedial Response Activities*, Office of Emergency and Remedial Response and Office of Waste Programs and Enforcement, OSWER Directive 9335.0-7B, EPA 540/G-87/003A, Washington, DC.

United States Geological Survey (USGS), 1971, Geological Survey Research (Chapter D), Annette Island, Alaska. Professional Paper 750-D.

\_\_\_\_\_, 1955, minor revisions, 1962, 7.5' Topographic Map, Ketchikan (A-5) Quadrangle, Alaska.